


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒

|   |                  |                    |  |                |  |   |                                    |              |              |               |
|---|------------------|--------------------|--|----------------|--|---|------------------------------------|--------------|--------------|---------------|
| <b>APPLICATION FOR PERMIT TO DRILL</b>  |                  |                    |  |                |  | <b>1. WELL NAME and NUMBER</b><br>5-27D-36  |                                    |              |              |               |
| <b>2. TYPE OF WORK</b><br>DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/> |                  |                    |  |                |  | <b>3. FIELD OR WILDCAT</b><br>CEDAR RIM   |                                    |              |              |               |
| <b>4. TYPE OF WELL</b><br>Oil Well Coalbed Methane Well: NO   |                  |                    |  |                |  | <b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b>  |                                    |              |              |               |
| <b>6. NAME OF OPERATOR</b><br>BILL BARRETT CORP   |                  |                    |  |                |  | <b>7. OPERATOR PHONE</b><br>303 312-8164  |                                    |              |              |               |
| <b>8. ADDRESS OF OPERATOR</b><br>1099 18th Street Ste 2300, Denver, CO, 80202   |                  |                    |  |                |  | <b>9. OPERATOR E-MAIL</b><br>BHilgers@billbarrettcorp.com   |                                    |              |              |               |
| <b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b><br>20G0005608   |                  |                    | <b>11. MINERAL OWNERSHIP</b><br>FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>    |                |  | <b>12. SURFACE OWNERSHIP</b><br>FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> |                                    |              |              |               |
| <b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b><br>Utah Division of Wildlife Resources   |                  |                    |  |                |  | <b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b><br>801-538-4700  |                                    |              |              |               |
| <b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b><br>1594 West North Temple, Suite 2110, Salt Lake City, UT 84114                                     |                  |                    |  |                |  | <b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>   |                                    |              |              |               |
| <b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>   |                  |                    | <b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b><br>YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/> |                |  | <b>19. SLANT</b><br>VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>                               |                                    |              |              |               |
| <b>20. LOCATION OF WELL</b>   | <b>FOOTAGES</b>  |                    | <b>QTR-QTR</b>   | <b>SECTION</b> | <b>TOWNSHIP</b>  | <b>RANGE</b>  | <b>MERIDIAN</b>                    |              |              |               |
| <b>LOCATION AT SURFACE</b>  | 1252 FNL 660 FWL |                    | SWNW   | 27             | 3.0 S  | 6.0 W   | U                                  |              |              |               |
| <b>Top of Uppermost Producing Zone</b>  | 1980 FNL 708 FWL |                    | SWNW   | 27             | 3.0 S  | 6.0 W   | U                                  |              |              |               |
| <b>At Total Depth</b>   | 1980 FNL 700 FWL |                    | SWNW   | 27             | 3.0 S  | 6.0 W   | U                                  |              |              |               |
| <b>21. COUNTY</b><br>DUCESNE  |                  |                    | <b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b><br>700  |                |  | <b>23. NUMBER OF ACRES IN DRILLING UNIT</b><br>640  |                                    |              |              |               |
|   |                  |                    | <b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b><br>2066   |                |  | <b>26. PROPOSED DEPTH</b><br>MD: 9758 TVD: 9645   |                                    |              |              |               |
| <b>27. ELEVATION - GROUND LEVEL</b><br>6064   |                  |                    | <b>28. BOND NUMBER</b><br>LPM8874725   |                |  | <b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b><br>Duchesne City Culinary Water Dock   |                                    |              |              |               |
| <b>Hole, Casing, and Cement Information</b>   |                  |                    |  |                |  |   |                                    |              |              |               |
| <b>String</b>   | <b>Hole Size</b> | <b>Casing Size</b> | <b>Length</b>  | <b>Weight</b>  | <b>Grade &amp; Thread</b>  | <b>Max Mud Wt.</b>  | <b>Cement</b>                      | <b>Sacks</b> | <b>Yield</b> | <b>Weight</b> |
| COND  | 26               | 16                 | 0 - 80   | 65.0           | Unknown  | 8.8   | Unknown                            | 0            | 0.0          | 0.0           |
| SURF  | 12.25            | 9.625              | 0 - 3000   | 45.5           | J-55 ST&C  | 8.8   | Halliburton Light , Type Unknown   | 450          | 3.16         | 11.0          |
|   |                  |                    |  |                |  |   | Halliburton Premium , Type Unknown | 210          | 1.36         | 14.8          |
| PROD  | 8.75             | 5.5                | 0 - 9758   | 17.0           | P-110 LT&C   | 9.7   | Unknown                            | 640          | 2.31         | 11.0          |
|   |                  |                    |  |                |  |   | Unknown                            | 910          | 1.42         | 13.5          |
| <b>ATTACHMENTS</b>  |                  |                    |  |                |  |   |                                    |              |              |               |
| <b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>   |                  |                    |  |                |  |   |                                    |              |              |               |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  |                  |                    |  |                | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN                 |   |                                    |              |              |               |
| <input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)   |                  |                    |  |                | <input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER |   |                                    |              |              |               |
| <input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)  |                  |                    |  |                | <input checked="" type="checkbox"/> TOPOGRAPHICAL MAP                      |   |                                    |              |              |               |
| <b>NAME</b> Venessa Langmacher  |                  |                    | <b>TITLE</b> Senior Permit Analyst   |                |  | <b>PHONE</b> 303 312-8172   |                                    |              |              |               |
| <b>SIGNATURE</b>  |                  |                    | <b>DATE</b> 08/04/2011   |                |  | <b>EMAIL</b> vlangmacher@billbarrettcorp.com  |                                    |              |              |               |
| <b>API NUMBER ASSIGNED</b><br>43013509170000  |                  |                    | <b>APPROVAL</b><br><br>Permit Manager  |                |  |   |                                    |              |              |               |

**RECEIVED: August 17, 2011**

**DRILLING PLAN**

BILL BARRETT CORPORATION

**5-27D-36 BTR Well Pad**

SW NW, 1252' FNL and 660' FWL, Section 27, T3S-R6W, USB&amp;M (surface hole)

SW NW, 1980' FNL and 700' FWL, Section 27, T3S-R6W, USB&amp;M (bottom hole)

Duchesne County, Utah

**1 - 2. Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals**

| <b><u>Formation</u></b> | <b><u>Depth – MD</u></b> | <b><u>Depth – TVD</u></b> |
|-------------------------|--------------------------|---------------------------|
| Lower Green River*      | 5,306'                   | 5,216'                    |
| Douglas Creek           | 6,159'                   | 6,047'                    |
| Black Shale             | 6,901'                   | 6,788'                    |
| Castle Peak             | 7,075'                   | 6,962'                    |
| Uteland Butte           | 7,410'                   | 7,297'                    |
| Wasatch*                | 7,796'                   | 7,683'                    |
| TD                      | 9,758'                   | 9,645'                    |

\*PROSPECTIVE PAY

The Wasatch and the Lower Green River are primary objectives for oil/gas.

Base of Useable Water = 5,550'

**3. BOP and Pressure Containment Data**

| <b><u>Depth Intervals</u></b>   | <b><u>BOP Equipment</u></b>                     |
|---|---|
| 0 – 3,000'  | No pressure control required                    |
| 3,000' – TD   | 11" 5000# Ram Type BOP<br>11" 5000# Annular BOP |
| - Drilling spool to accommodate choke and kill lines;   |   |
| - Ancillary equipment and choke manifold rated at 5,000 psi. All BOP and BOPE tests will be in accordance with the requirements of onshore Order No. 2; |   |
| - The BLM and the State of Utah Division of Oil, Gas and Mining will be notified 24 hours in advance of all BOP pressure tests.                         |   |
| - BOP hand wheels may be underneath the sub-structure of the rig if the drilling rig used is set up To operate most efficiently in this manner.         |   |

**4. Casing Program**

| <b><u>Hole Size</u></b>  | <b><u>SETTING DEPTH</u></b> |        | <b><u>Casing Size</u></b> | <b><u>Casing Weight</u></b> | <b><u>Casing Grade</u></b> | <b><u>Thread</u></b> | <b><u>Condition</u></b> |
|--|-----------------------------|--------|---------------------------|-----------------------------|----------------------------|----------------------|-------------------------|
| 26"  | Surface                     | 80'    | 16"                       | 65#                         |                            |                      |                         |
| 12 1/4"  | Surface                     | 3,000' | 9 5/8"                    | 36#                         | J or K 55                  | BT&C                 | New                     |
| 8 3/4"   | Surface                     | TD     | 5 1/2"                    | 17#                         | P-110                      | LT&C                 | New                     |
| <b>NOTE: In addition, 8 3/4" hole size may change to 7 7/8" at the point the bit is changed out.</b> |                             |        |                           |                             |                            |                      |                         |

Bill Barrett Corporation  
Drilling Program  
#5-27D-36 BTR  
Duchesne County, Utah

5. **Cementing Program**

| <b>Casing</b>            | <b>Cementing</b>  |
|--------------------------|---|
| 16" Conductor Casing     | <i>Grout</i>  |
| 9 5/8" Surface Casing    | <p><i>Lead</i> with approximately 450 sx Halliburton Light Premium with additives mixed at 11.0 ppg (yield = 3.16 ft<sup>3</sup>/sx) circulated to surface with 75% excess. Top of lead estimated at surface.</p> <p><i>Tail</i> with approximately 210 sx Halliburton Premium cement with additives mixed at 14.8 ppg (yield = 1.36 ft<sup>3</sup>/sx), calculated hole volume with 75% excess. Top of tail estimated at 2,500'.</p> |
| 5 1/2" Production Casing | <p><i>Lead</i> with approximately 640 sx Tuned Light cement with additives, mixed at 11.0 ppg (yield = 2.31 ft<sup>3</sup>/sx,) . Top of lead estimated at 2,500'.</p> <p><i>Tail</i> with approximately 910 sx Halliburton Econocem cement with additives mixed at 13.5 ppg (yield = 1.42 ft<sup>3</sup>/sx). Top of tail estimated at 6,401'.</p>   |

6. **Mud Program**

| <b><u>Interval</u></b>  | <b><u>Weight</u></b> | <b><u>Viscosity</u></b> | <b><u>Fluid Loss</u></b><br><b><u>(API filtrate)</u></b> | <b><u>Remarks</u></b>            |
|---|----------------------|-------------------------|--|----------------------------------|
| 0' – 80'  | 8.3 – 8.8            | 26 – 36                 | NC   | Freshwater Spud Mud Fluid System |
| 80' – 3,000'  | 8.3 – 8.8            | 26 – 36                 | NC   | Freshwater Spud Mud Fluid System |
| 3,000' – TD   | 8.6 – 9.7            | 42-52                   | 20 cc or less  | DAP Polymer Fluid System         |
| Note: Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kicks" will be available at wellsite. BBC may require minor amounts of diesel to be added to its fluid system in order to reduce torque and drag. |                      |                         |  |                                  |

7. **Testing, Logging and Core Programs**

|          |   |
|----------|---|
| Cores    | None anticipated  |
| Testing  | None anticipated; drill stem tests may be run on shows of interest;   |
| Sampling | 30' to 50' samples; surface casing to TD. Preserve samples all show intervals;  |
| Surveys  | MWD as needed to land wellbore;   |
| Logging  | DIL-GR-SP, FDC-CNL-GR-CALIPER-Pe-Microlog, Sonic-GR (all TD to surface). FMI & Sonic Scanner to be run at geologist's discretion. |

Bill Barrett Corporation  
Drilling Program  
#5-27D-36 BTR  
Duchesne County, Utah

**8. Anticipated Abnormal Pressures or Temperatures**

No abnormal pressures or temperatures or other hazards are anticipated.

Maximum anticipated bottom hole pressure equals approximately 4865 psi\* and maximum anticipated surface pressure equals approximately 2743 psi\*\* (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

\*Max Mud Wt x 0.052 x TD = A (bottom hole pressure)

\*\*Maximum surface pressure = A – (0.22 x TD)

**9. Auxiliary Equipment**

- a) Upper kelly cock; lower Kelly cock will be installed while drilling
- b) Inside BOP or stab-in valve (available on rig floor)
- c) Safety valve(s) and subs to fit all string connections in use
- d) Mud monitoring will be visually observed

**10. Location and Type of Water Supply**

Water for the drilling and completion will be trucked from the Duchesne City Culinary Water Dock located in Sec. 1, T4S, R5W.

**11. Drilling Schedule**

Location Construction: July 2012  
Spud: July 2012  
Duration: 15 days drilling time  
45 days completion time

**PRESSURE CONTROL EQUIPMENT – Schematic Attached**

**A. Type: Eleven (11) Inch Double Gate Hydraulic BOP with Eleven (11) Inch Annular Preventer.** The blow out preventer will be equipped as follows:

1. One (1) blind ram (above).
2. One (1) pipe ram (below).
3. Drilling spool with two (2) side outlets (choke side 3-inch minimum, kill side 2-inch minimum).
4. 3-inch diameter choke line.
5. Two (2) choke line valves (3-inch minimum).
6. Kill line (2-inch minimum).
7. Two (2) chokes with one (1) remotely controlled from the rig floor.
8. Two (2) kill line valves, and a check valve (2-inch minimum).
9. Upper and lower kelly cock valves with handles available.
10. Safety valve(s) & subs to fit all drill string connections in use.
11. Inside BOP or float sub available.
12. Pressure gauge on choke manifold.
13. Fill-up line above the uppermost preventer.

**B. Pressure Rating:** 5,000 psi

**C. Testing Procedure:**

Annular Preventer

At a minimum, the Annular Preventer will be pressure tested to 50% of the rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition, the Annular Preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be

maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

**D. Choke Manifold Equipment:**

All choke lines will be straight lines unless turns use tee blocks or are targeted with running tees, and will be anchored to prevent whip and vibration.

**E. Accumulator:**

The accumulator will have sufficient capacity to open the hydraulically-controlled choke line valve (if so equipped), close all rams plus the annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of closing unit pumps. The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity and the fluid level of the reservoir will be maintained at the manufacturer's recommendations.

The BOP system will have two (2) independent power sources to close the preventers. Nitrogen bottles (3 minimum) will be one (1) of these independent power sources and will maintain a charge equal to the manufacturer's specifications.

The accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack and at least once every six (6) months thereafter. The accumulator pressure will be corrected if the measured precharge pressure is found to be above or below the maximum or minimum limits specified in the *Onshore Oil & Gas Order Number 2*.

A manual locking device (i.e. hand wheels) or automatic locking device will be installed on all systems of 2M or greater. A valve will be installed in the closing line as close as possible to the annular preventer to act as a locking device. This valve will be maintained in the open position and will be closed only when the power source for the accumulator is inoperative.

Remote controls shall be readily accessible to the driller. Remote controls for all 3M or greater systems will be capable of closing all preventers. Remote controls for 5M or greater systems will be capable of both opening and closing all preventers. Master controls will be at the accumulator and will be capable of opening and closing all preventers and the choke line valve (if so equipped).


**F. Miscellaneous Information:**

The Blow-Out Preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*. The hydraulic BOP closing unit will be located at least twenty-five (25) feet from the well head but readily accessible to the driller. Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill this hole.

A flare line will be installed after the choke manifold, extending 125 feet (minimum) from the center of the drill hole to a separate flare pit.

# BILL BARRETT CORPORATION


## TYPICAL 5,000 p.s.i. CHOKE MANIFOLD





# BILL BARRETT CORPORATION

## TYPICAL 5,000 p.s.i. BLOWOUT PREVENTER





# Bill Barrett Corporation

## LAKE CANYON & BLACK TAIL RIDGE CEMENT VOLUMES

**Well Name:** 5-27D-36 BTR

### Surface Hole Data:

|                |         |
|----------------|---------|
| Total Depth:   | 3,000'  |
| Top of Cement: | 0'      |
| OD of Hole:    | 12.250" |
| OD of Casing:  | 9.625"  |

### Calculated Data:

|              |        |                 |
|--------------|--------|-----------------|
| Lead Volume: | 1370.2 | ft <sup>3</sup> |
| Lead Fill:   | 2,500' |                 |
| Tail Volume: | 274.0  | ft <sup>3</sup> |
| Tail Fill:   | 500'   |                 |

### Cement Data:

|              |      |                     |
|--------------|------|---------------------|
| Lead Yield:  | 3.16 | ft <sup>3</sup> /sk |
| % Excess:    | 75%  |                     |
| Top of Lead: | 0'   |                     |

### Calculated # of Sacks:

|              |     |
|--------------|-----|
| # SK's Lead: | 450 |
|--------------|-----|

|              |        |                     |
|--------------|--------|---------------------|
| Tail Yield:  | 1.36   | ft <sup>3</sup> /sk |
| % Excess:    | 75%    |                     |
| Top of Tail: | 2,500' |                     |

|              |     |
|--------------|-----|
| # SK's Tail: | 210 |
|--------------|-----|

### Production Hole Data:

|                |        |
|----------------|--------|
| Total Depth:   | 9,758' |
| Top of Cement: | 2,500' |
| Top of Tail:   | 6,401' |
| OD of Hole:    | 8.750" |
| OD of Casing:  | 5.500" |

### Calculated Data:

|              |        |                 |
|--------------|--------|-----------------|
| Lead Volume: | 1478.0 | ft <sup>3</sup> |
| Lead Fill:   | 3,901' |                 |
| Tail Volume: | 1272.1 | ft <sup>3</sup> |
| Tail Fill:   | 3,357' |                 |

### Cement Data:

|             |      |                     |
|-------------|------|---------------------|
| Lead Yield: | 2.31 | ft <sup>3</sup> /sk |
| Tail Yield: | 1.42 | ft <sup>3</sup> /sk |
| % Excess:   | 50%  |                     |

### Calculated # of Sacks:

|              |     |
|--------------|-----|
| # SK's Lead: | 640 |
| # SK's Tail: | 910 |

|  |
|--|
| <b>5-27D-36 BTR Proposed Cementing Program</b> |
|--|

| <u>Job Recommendation</u>         | <u>Surface Casing</u>                  |
|-----------------------------------|--|
| <b>Lead Cement - (2500' - 0')</b> |  |
| Halliburton Light Premium         | Fluid Weight: 11.0 lbm/gal             |
| 5.0 lbm/sk Silicalite Compacted   | Slurry Yield: 3.16 ft <sup>3</sup> /sk |
| 0.25 lbm/sk Kwik Seal             | Total Mixing Fluid: 19.48 Gal/sk       |
| 0.125 lbm/sk Poly-E-Flake         | Top of Fluid: 0'                       |
| 2.0% Bentonite                    | Calculated Fill: 2,500'                |
|                                   | Volume: 244.02 bbl                     |
|                                   | <b>Proposed Sacks: 450 sks</b>         |
| <b>Tail Cement - (TD - 2500')</b> |  |
| Premium Cement                    | Fluid Weight: 14.8 lbm/gal             |
| 2.0% Calcium Chloride             | Slurry Yield: 1.36 ft <sup>3</sup> /sk |
|                                   | Total Mixing Fluid: 6.37 Gal/sk        |
|                                   | Top of Fluid: 2,500'                   |
|                                   | Calculated Fill: 500'                  |
|                                   | Volume: 48.80 bbl                      |
|                                   | <b>Proposed Sacks: 210 sks</b>         |

| <u>Job Recommendation</u>            | <u>Production Casing</u>               |
|--------------------------------------|--|
| <b>Lead Cement - (6401' - 2500')</b> |  |
| Tuned Light™ System                  | Fluid Weight: 11.0 lbm/gal             |
|                                      | Slurry Yield: 2.31 ft <sup>3</sup> /sk |
|                                      | Total Mixing Fluid: 10.65 Gal/sk       |
|                                      | Top of Fluid: 2,500'                   |
|                                      | Calculated Fill: 3,901'                |
|                                      | Volume: 263.23 bbl                     |
|                                      | <b>Proposed Sacks: 640 sks</b>         |
| <b>Tail Cement - (9758' - 6401')</b> |  |
| Econocem™ System                     | Fluid Weight: 13.5 lbm/gal             |
| 0.125 lbm/sk Poly-E-Flake            | Slurry Yield: 1.42 ft <sup>3</sup> /sk |
| 1.0 lbm/sk Granulite TR 1/4          | Total Mixing Fluid: 6.61 Gal/sk        |
|                                      | Top of Fluid: 6,401'                   |
|                                      | Calculated Fill: 3,357'                |
|                                      | Volume: 226.55 bbl                     |
|                                      | <b>Proposed Sacks: 910 sks</b>         |

T3S, R6W, U.S.B.&M.

BILL BARRETT CORPORATION


Well location, #5-27D-36 BTR, located as shown in the SW 1/4 NW 1/4 of Section 27, T3S, R6W, U.S.B.&M., Duchesne County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT A ROAD INTERSECTION LOCATED IN THE NW 1/4 OF SECTION 36, T3S, R6W, U.S.B.&M., TAKEN FROM THE RABBIT GULCH QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5904 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.




| LINE TABLE |             |         |
|------------|-------------|---------|
| LINE       | BEARING     | LENGTH  |
| L1         | S03°43'33"E | 728.83' |

| NAD 83 (TARGET BOTTOM HOLE) |                            | NAD 83 (SURFACE LOCATION) |                            |
|-----------------------------|----------------------------|---------------------------|----------------------------|
| LATITUDE =                  | 40°11'33.39" (40.192608)   | LATITUDE =                | 40°11'40.58" (40.194606)   |
| LONGITUDE =                 | 110°33'22.58" (110.556272) | LONGITUDE =               | 110°33'23.19" (110.556442) |
| NAD 27 (TARGET BOTTOM HOLE) |                            | NAD 27 (SURFACE LOCATION) |                            |
| LATITUDE =                  | 40°11'33.55" (40.192653)   | LATITUDE =                | 40°11'40.74" (40.194650)   |
| LONGITUDE =                 | 110°33'20.01" (110.555558) | LONGITUDE =               | 110°33'20.63" (110.555731) |

LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE POINT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ROBERT L. KAY  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH  
04-27-11

REVISED: 04-27-11


UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

|                         |                            |                          |
|-------------------------|----------------------------|--------------------------|
| SCALE<br>1" = 1000'     | DATE SURVEYED:<br>08-11-10 | DATE DRAWN:<br>08-20-10  |
| PARTY<br>T.A. C.N. C.C. | REFERENCES<br>G.L.O. PLAT  |                          |
| WEATHER<br>HOT          | FILE                       |                          |
|                         |                            | BILL BARRETT CORPORATION |





**LEGEND:**

PROPOSED LOCATION



**BILL BARRETT CORPORATION**

**#5-27D-36 BTR**  
**SECTION 27, T3S, R6W, U.S.B.&M.**  
**1252' FNL 660' FWL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813


**ACCESS ROAD**  
**MAP**

**08 30 10**  
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: J.J. REVISED: 00-00-00







**LEGEND:**

- EXISTING ROAD
- PROPOSED ACCESS ROAD



**BILL BARRETT CORPORATION**

**#5-27D-36 BTR**  
**SECTION 27, T3S, R6W, U.S.B.&M.**  
**1252' FNL 660' FWL**



**Utah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813


**ACCESS ROAD**  
**MAP**

**08 30 10**  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: J.J. REVISED: 00-00-00

**B**  
**TOPO**





**APPROXIMATE TOTAL PIPELINE DISTANCE = 888' +/-**

**LEGEND:**

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**BILL BARRETT CORPORATION**

**#5-27D-36 BTR**  
**SECTION 27, T3S, R6W, U.S.B.&M.**  
**1252' FNL 660' FWL**

**TOPOGRAPHIC**  
**MAP**

**08 30 10**  
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: J.J. REVISED: 00-00-00





## WELL DETAILS: 5-27D-36 BTR




US State Plane 1927 (Exact solution) Utah Central 4302 NAD 1927 (NADCON CONUS)



Bill Barrett Corporation

| +N/-S | +E/-W | Northing  | Easting    | Latitude        | Longitude        |
|-------|-------|-----------|------------|-----------------|------------------|
| 0.00  | 0.00  | 679339.48 | 2263777.23 | 40° 11' 40.74 N | 110° 33' 20.63 W |

Ground Level: 6062.00 Well #1 - 16' KB

Azimuths to True North  
Magnetic North: 11.55°Magnetic Field  
Strength: 52288.4snT  
Dip Angle: 65.82°  
Date: 5/3/2011  
Model: IGRF2010

## SECTION DETAILS

| MD      | Inc   | Azi    | TVD     | +N/-S   | +E/-W | Dleg | TFace  | VSect  | Target            |
|---------|-------|--------|---------|---------|-------|------|--------|--------|-------------------|
| 0.00    | 0.00  | 0.00   | 0.00    | 0.00    | 0.00  | 0.00 | 0.00   | 0.00   |                   |
| 3400.00 | 0.00  | 0.00   | 3400.00 | 0.00    | 0.00  | 0.00 | 0.00   | 0.00   |                   |
| 4592.18 | 23.84 | 176.22 | 4558.07 | -243.97 | 16.13 | 2.00 | 176.22 | 244.50 |                   |
| 4984.51 | 23.84 | 176.22 | 4916.91 | -402.22 | 26.60 | 0.00 | 0.00   | 403.10 |                   |
| 6574.08 | 0.00  | 0.00   | 6461.00 | -727.51 | 48.11 | 1.50 | 180.00 | 729.10 |                   |
| 9758.08 | 0.00  | 0.00   | 9645.00 | -727.51 | 48.11 | 0.00 | 0.00   | 729.10 | 5-27D-36 BTR PBHL |



|                  |                             |                                     |                       |
|------------------|-----------------------------|-------------------------------------|-----------------------|
| <b>Database:</b> | EDM 5000.1 Single User Db   | <b>Local Co-ordinate Reference:</b> | Well Well #1 - 16' KB |
| <b>Company:</b>  | Bill Barrett Corp.          | <b>TVD Reference:</b>               | KB @ 6078.00ft        |
| <b>Project:</b>  | Duchesne County, UT [NAD27] | <b>MD Reference:</b>                | KB @ 6078.00ft        |
| <b>Site:</b>     | 5-27D-36 BTR                | <b>North Reference:</b>             | True                  |
| <b>Well:</b>     | Well #1 - 16' KB            | <b>Survey Calculation Method:</b>   | Minimum Curvature     |
| <b>Wellbore:</b> | Wellbore #1                 |                                     |                       |
| <b>Design:</b>   | plan1 03may11 rbw           |                                     |                       |

|                    |                                      |                      |                |
|--------------------|--------------------------------------|----------------------|----------------|
| <b>Project</b>     | Duchesne County, UT [NAD27]          |                      |                |
| <b>Map System:</b> | US State Plane 1927 (Exact solution) | <b>System Datum:</b> | Mean Sea Level |
| <b>Geo Datum:</b>  | NAD 1927 (NADCON CONUS)              |                      |                |
| <b>Map Zone:</b>   | Utah Central 4302                    |                      |                |

|                       |          |              |                   |                   |                  |
|-----------------------|----------|--------------|-------------------|-------------------|------------------|
| Site                  |          | 5-27D-36 BTR |                   |                   |                  |
| Site Position:        |          | Northing:    | 679,339.48 usft   | Latitude:         | 40° 11' 40.74 N  |
| From:                 | Lat/Long | Easting:     | 2,263,777.23 usft | Longitude:        | 110° 33' 20.63 W |
| Position Uncertainty: | 0.00 ft  | Slot Radius: | 1.10 ft           | Grid Convergence: | 0.60 °           |

| Well                 | Well #1 - 16' KB |         |                     |                   |               |                  |
|----------------------|------------------|---------|---------------------|-------------------|---------------|------------------|
| Well Position        | +N/-S            | 0.00 ft | Northing:           | 679,339.48 usft   | Latitude:     | 40° 11' 40.74 N  |
|                      | +E/-W            | 0.00 ft | Easting:            | 2,263,777.23 usft | Longitude:    | 110° 33' 20.63 W |
| Position Uncertainty |                  | 0.00 ft | Wellhead Elevation: |                   | Ground Level: | 6,062.00 ft      |

|                  |                   |                    |                        |                      |                            |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| <b>Wellbore</b>  | Wellbore #1       |                    |                        |                      |                            |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination (°)</b> | <b>Dip Angle (°)</b> | <b>Field Strength (nT)</b> |
|                  | IGRF2010          | 5/3/2011           | 11.55                  | 65.82                | 52,288                     |

|                          |                              |                   |                   |                      |      |
|--------------------------|------------------------------|-------------------|-------------------|----------------------|------|
| <b>Design</b>            | plan1 03may11 rbw            |                   |                   |                      |      |
| <b>Audit Notes:</b>      |                              |                   |                   |                      |      |
| <b>Version:</b>          | <b>Phase:</b>                | PROTOTYPE         |                   | <b>Tie On Depth:</b> | 0.00 |
| <b>Vertical Section:</b> | <b>Depth From (TVD) (ft)</b> | <b>+N/-S (ft)</b> | <b>+E/-W (ft)</b> | <b>Direction (°)</b> |      |
|                          | 0.00                         | 0.00              | 0.00              | 176.22               |      |

| <b>Plan Sections</b> |                 |             |                     |            |            |                       |                      |                     |         |                   |
|----------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|----------------------|---------------------|---------|-------------------|
| Measured Depth (ft)  | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target            |
| 0.00                 | 0.00            | 0.00        | 0.00                | 0.00       | 0.00       | 0.00                  | 0.00                 | 0.00                | 0.00    |                   |
| 3,400.00             | 0.00            | 0.00        | 3,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                 | 0.00                | 0.00    |                   |
| 4,592.18             | 23.84           | 176.22      | 4,558.07            | -243.97    | 16.13      | 2.00                  | 2.00                 | 0.00                | 176.22  |                   |
| 4,984.51             | 23.84           | 176.22      | 4,916.91            | -402.22    | 26.60      | 0.00                  | 0.00                 | 0.00                | 0.00    |                   |
| 6,574.08             | 0.00            | 0.00        | 6,461.00            | -727.51    | 48.11      | 1.50                  | -1.50                | 0.00                | 180.00  |                   |
| 9,758.08             | 0.00            | 0.00        | 9,645.00            | -727.51    | 48.11      | 0.00                  | 0.00                 | 0.00                | 0.00    | 5-27D-36 BTR PBHL |

|                  |                             |                                     |                       |
|------------------|-----------------------------|-------------------------------------|-----------------------|
| <b>Database:</b> | EDM 5000.1 Single User Db   | <b>Local Co-ordinate Reference:</b> | Well Well #1 - 16' KB |
| <b>Company:</b>  | Bill Barrett Corp.          | <b>TVD Reference:</b>               | KB @ 6078.00ft        |
| <b>Project:</b>  | Duchesne County, UT [NAD27] | <b>MD Reference:</b>                | KB @ 6078.00ft        |
| <b>Site:</b>     | 5-27D-36 BTR                | <b>North Reference:</b>             | True                  |
| <b>Well:</b>     | Well #1 - 16' KB            | <b>Survey Calculation Method:</b>   | Minimum Curvature     |
| <b>Wellbore:</b> | Wellbore #1                 |                                     |                       |
| <b>Design:</b>   | plan1 03may11 rbw           |                                     |                       |

| Planned Survey                         |                 |             |                     |            |            |                       |                       |                      |                     |
|--|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft)                    | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 0.00                                   | 0.00            | 0.00        | 0.00                | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 100.00                                 | 0.00            | 0.00        | 100.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 200.00                                 | 0.00            | 0.00        | 200.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 300.00                                 | 0.00            | 0.00        | 300.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 400.00                                 | 0.00            | 0.00        | 400.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 500.00                                 | 0.00            | 0.00        | 500.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 600.00                                 | 0.00            | 0.00        | 600.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 700.00                                 | 0.00            | 0.00        | 700.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 800.00                                 | 0.00            | 0.00        | 800.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 900.00                                 | 0.00            | 0.00        | 900.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,000.00                               | 0.00            | 0.00        | 1,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,100.00                               | 0.00            | 0.00        | 1,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,200.00                               | 0.00            | 0.00        | 1,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,300.00                               | 0.00            | 0.00        | 1,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,400.00                               | 0.00            | 0.00        | 1,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,500.00                               | 0.00            | 0.00        | 1,500.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,600.00                               | 0.00            | 0.00        | 1,600.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,700.00                               | 0.00            | 0.00        | 1,700.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,800.00                               | 0.00            | 0.00        | 1,800.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,900.00                               | 0.00            | 0.00        | 1,900.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,000.00                               | 0.00            | 0.00        | 2,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,100.00                               | 0.00            | 0.00        | 2,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,200.00                               | 0.00            | 0.00        | 2,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,300.00                               | 0.00            | 0.00        | 2,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,400.00                               | 0.00            | 0.00        | 2,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,500.00                               | 0.00            | 0.00        | 2,500.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,600.00                               | 0.00            | 0.00        | 2,600.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,700.00                               | 0.00            | 0.00        | 2,700.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,800.00                               | 0.00            | 0.00        | 2,800.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,900.00                               | 0.00            | 0.00        | 2,900.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,000.00                               | 0.00            | 0.00        | 3,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,100.00                               | 0.00            | 0.00        | 3,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,135.00                               | 0.00            | 0.00        | 3,135.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| <b>Green River</b>                     |                 |             |                     |            |            |                       |                       |                      |                     |
| 3,200.00                               | 0.00            | 0.00        | 3,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,300.00                               | 0.00            | 0.00        | 3,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,400.00                               | 0.00            | 0.00        | 3,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| <b>Start Build 2.00</b>                |                 |             |                     |            |            |                       |                       |                      |                     |
| 3,500.00                               | 2.00            | 176.22      | 3,499.98            | -1.74      | 0.12       | 1.75                  | 2.00                  | 2.00                 | 0.00                |
| 3,600.00                               | 4.00            | 176.22      | 3,599.84            | -6.96      | 0.46       | 6.98                  | 2.00                  | 2.00                 | 0.00                |
| 3,700.00                               | 6.00            | 176.22      | 3,699.45            | -15.66     | 1.04       | 15.69                 | 2.00                  | 2.00                 | 0.00                |
| 3,800.00                               | 8.00            | 176.22      | 3,798.70            | -27.82     | 1.84       | 27.88                 | 2.00                  | 2.00                 | 0.00                |
| 3,834.67                               | 8.69            | 176.22      | 3,833.00            | -32.84     | 2.17       | 32.91                 | 2.00                  | 2.00                 | 0.00                |
| <b>Mahogany</b>                        |                 |             |                     |            |            |                       |                       |                      |                     |
| 3,900.00                               | 10.00           | 176.22      | 3,897.47            | -43.43     | 2.87       | 43.52                 | 2.00                  | 2.00                 | 0.00                |
| 4,000.00                               | 12.00           | 176.22      | 3,995.62            | -62.47     | 4.13       | 62.60                 | 2.00                  | 2.00                 | 0.00                |
| 4,100.00                               | 14.00           | 176.22      | 4,093.06            | -84.91     | 5.62       | 85.10                 | 2.00                  | 2.00                 | 0.00                |
| 4,200.00                               | 16.00           | 176.22      | 4,189.64            | -110.74    | 7.32       | 110.98                | 2.00                  | 2.00                 | 0.00                |
| 4,300.00                               | 18.00           | 176.22      | 4,285.27            | -139.91    | 9.25       | 140.21                | 2.00                  | 2.00                 | 0.00                |
| 4,400.00                               | 20.00           | 176.22      | 4,379.82            | -172.39    | 11.40      | 172.77                | 2.00                  | 2.00                 | 0.00                |
| 4,500.00                               | 22.00           | 176.22      | 4,473.17            | -208.15    | 13.77      | 208.60                | 2.00                  | 2.00                 | 0.00                |
| 4,592.18                               | 23.84           | 176.22      | 4,558.07            | -243.97    | 16.13      | 244.50                | 2.00                  | 2.00                 | 0.00                |
| <b>Start 392.33 hold at 4592.18 MD</b> |                 |             |                     |            |            |                       |                       |                      |                     |
| 4,600.00                               | 23.84           | 176.22      | 4,565.22            | -247.12    | 16.34      | 247.66                | 0.00                  | 0.00                 | 0.00                |

|                  |                             |                                     |                       |
|------------------|-----------------------------|-------------------------------------|-----------------------|
| <b>Database:</b> | EDM 5000.1 Single User Db   | <b>Local Co-ordinate Reference:</b> | Well Well #1 - 16' KB |
| <b>Company:</b>  | Bill Barrett Corp.          | <b>TVD Reference:</b>               | KB @ 6078.00ft        |
| <b>Project:</b>  | Duchesne County, UT [NAD27] | <b>MD Reference:</b>                | KB @ 6078.00ft        |
| <b>Site:</b>     | 5-27D-36 BTR                | <b>North Reference:</b>             | True                  |
| <b>Well:</b>     | Well #1 - 16' KB            | <b>Survey Calculation Method:</b>   | Minimum Curvature     |
| <b>Wellbore:</b> | Wellbore #1                 |                                     |                       |
| <b>Design:</b>   | plan1 03may11 rbw           |                                     |                       |

| Planned Survey                                       |                 |             |                     |            |            |                       |                       |                      |                     |
|--|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft)                                  | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 4,700.00   | 23.84           | 176.22      | 4,656.68            | -287.46    | 19.01      | 288.09                | 0.00                  | 0.00                 | 0.00                |
| 4,800.00   | 23.84           | 176.22      | 4,748.15            | -327.80    | 21.68      | 328.51                | 0.00                  | 0.00                 | 0.00                |
| 4,900.00   | 23.84           | 176.22      | 4,839.61            | -368.13    | 24.35      | 368.94                | 0.00                  | 0.00                 | 0.00                |
| 4,984.51   | 23.84           | 176.22      | 4,916.91            | -402.22    | 26.60      | 403.10                | 0.00                  | 0.00                 | 0.00                |
| <b>Start Drop -1.50</b>                              |                 |             |                     |            |            |                       |                       |                      |                     |
| 5,000.00   | 23.61           | 176.22      | 4,931.09            | -408.44    | 27.01      | 409.33                | 1.50                  | -1.50                | 0.00                |
| 5,100.00   | 22.11           | 176.22      | 5,023.23            | -447.20    | 29.57      | 448.18                | 1.50                  | -1.50                | 0.00                |
| 5,200.00   | 20.61           | 176.22      | 5,116.36            | -483.55    | 31.98      | 484.60                | 1.50                  | -1.50                | 0.00                |
| 5,300.00   | 19.11           | 176.22      | 5,210.41            | -517.45    | 34.22      | 518.58                | 1.50                  | -1.50                | 0.00                |
| 5,305.91   | 19.02           | 176.22      | 5,216.00            | -519.38    | 34.35      | 520.51                | 1.50                  | -1.50                | 0.00                |
| <b>TGR3</b>  |                 |             |                     |            |            |                       |                       |                      |                     |
| 5,400.00   | 17.61           | 176.22      | 5,305.32            | -548.88    | 36.30      | 550.08                | 1.50                  | -1.50                | 0.00                |
| 5,500.00   | 16.11           | 176.22      | 5,401.02            | -577.82    | 38.21      | 579.08                | 1.50                  | -1.50                | 0.00                |
| 5,600.00   | 14.61           | 176.22      | 5,497.44            | -604.25    | 39.96      | 605.57                | 1.50                  | -1.50                | 0.00                |
| 5,700.00   | 13.11           | 176.22      | 5,594.53            | -628.16    | 41.54      | 629.53                | 1.50                  | -1.50                | 0.00                |
| 5,800.00   | 11.61           | 176.22      | 5,692.20            | -649.52    | 42.95      | 650.94                | 1.50                  | -1.50                | 0.00                |
| 5,900.00   | 10.11           | 176.22      | 5,790.41            | -668.32    | 44.20      | 669.78                | 1.50                  | -1.50                | 0.00                |
| 6,000.00   | 8.61            | 176.22      | 5,889.08            | -684.55    | 45.27      | 686.04                | 1.50                  | -1.50                | 0.00                |
| 6,100.00   | 7.11            | 176.22      | 5,988.13            | -698.20    | 46.17      | 699.72                | 1.50                  | -1.50                | 0.00                |
| 6,159.27   | 6.22            | 176.22      | 6,047.00            | -705.06    | 46.63      | 706.60                | 1.50                  | -1.50                | 0.00                |
| <b>Douglas Creek</b>                                 |                 |             |                     |            |            |                       |                       |                      |                     |
| 6,200.00   | 5.61            | 176.22      | 6,087.51            | -709.25    | 46.90      | 710.80                | 1.50                  | -1.50                | 0.00                |
| 6,300.00   | 4.11            | 176.22      | 6,187.15            | -717.71    | 47.46      | 719.27                | 1.50                  | -1.50                | 0.00                |
| 6,400.00   | 2.61            | 176.22      | 6,286.98            | -723.56    | 47.85      | 725.14                | 1.50                  | -1.50                | 0.00                |
| 6,500.00   | 1.11            | 176.22      | 6,386.92            | -726.80    | 48.06      | 728.38                | 1.50                  | -1.50                | 0.00                |
| 6,574.08   | 0.00            | 0.00        | 6,461.00            | -727.51    | 48.11      | 729.10                | 1.50                  | -1.50                | 0.00                |
| <b>Start 3184.00 hold at 6574.08 MD - 3PT Marker</b> |                 |             |                     |            |            |                       |                       |                      |                     |
| 6,600.00   | 0.00            | 0.00        | 6,486.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 6,700.00   | 0.00            | 0.00        | 6,586.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 6,800.00   | 0.00            | 0.00        | 6,686.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 6,900.00   | 0.00            | 0.00        | 6,786.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 6,901.08   | 0.00            | 0.00        | 6,788.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>Black Shale</b>                                   |                 |             |                     |            |            |                       |                       |                      |                     |
| 7,000.00   | 0.00            | 0.00        | 6,886.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,075.08   | 0.00            | 0.00        | 6,962.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>Castle Peak</b>                                   |                 |             |                     |            |            |                       |                       |                      |                     |
| 7,100.00   | 0.00            | 0.00        | 6,986.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,200.00   | 0.00            | 0.00        | 7,086.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,300.00   | 0.00            | 0.00        | 7,186.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,400.00   | 0.00            | 0.00        | 7,286.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,410.08   | 0.00            | 0.00        | 7,297.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>Uteland Butte</b>                                 |                 |             |                     |            |            |                       |                       |                      |                     |
| 7,490.08   | 0.00            | 0.00        | 7,377.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR1</b>   |                 |             |                     |            |            |                       |                       |                      |                     |
| 7,500.00   | 0.00            | 0.00        | 7,386.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,600.00   | 0.00            | 0.00        | 7,486.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,700.00   | 0.00            | 0.00        | 7,586.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,796.08   | 0.00            | 0.00        | 7,683.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>Wasatch</b>                                       |                 |             |                     |            |            |                       |                       |                      |                     |
| 7,800.00   | 0.00            | 0.00        | 7,686.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,900.00   | 0.00            | 0.00        | 7,786.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 7,952.08   | 0.00            | 0.00        | 7,839.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |

|                  |                             |                                     |                       |
|------------------|-----------------------------|-------------------------------------|-----------------------|
| <b>Database:</b> | EDM 5000.1 Single User Db   | <b>Local Co-ordinate Reference:</b> | Well Well #1 - 16' KB |
| <b>Company:</b>  | Bill Barrett Corp.          | <b>TVD Reference:</b>               | KB @ 6078.00ft        |
| <b>Project:</b>  | Duchesne County, UT [NAD27] | <b>MD Reference:</b>                | KB @ 6078.00ft        |
| <b>Site:</b>     | 5-27D-36 BTR                | <b>North Reference:</b>             | True                  |
| <b>Well:</b>     | Well #1 - 16' KB            | <b>Survey Calculation Method:</b>   | Minimum Curvature     |
| <b>Wellbore:</b> | Wellbore #1                 |                                     |                       |
| <b>Design:</b>   | plan1 03may11 rbw           |                                     |                       |

| Planned Survey       |                 |             |                     |            |            |                       |                       |                      |                     |
|----------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft)  | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| <b>CR2</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 8,000.00             | 0.00            | 0.00        | 7,886.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,100.00             | 0.00            | 0.00        | 7,986.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,200.00             | 0.00            | 0.00        | 8,086.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,232.08             | 0.00            | 0.00        | 8,119.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR3</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 8,300.00             | 0.00            | 0.00        | 8,186.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,400.00             | 0.00            | 0.00        | 8,286.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,500.00             | 0.00            | 0.00        | 8,386.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,552.08             | 0.00            | 0.00        | 8,439.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR4</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 8,600.00             | 0.00            | 0.00        | 8,486.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,700.00             | 0.00            | 0.00        | 8,586.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,800.00             | 0.00            | 0.00        | 8,686.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,828.08             | 0.00            | 0.00        | 8,715.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR4A</b>          |                 |             |                     |            |            |                       |                       |                      |                     |
| 8,900.00             | 0.00            | 0.00        | 8,786.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 8,955.08             | 0.00            | 0.00        | 8,842.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR5</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 9,000.00             | 0.00            | 0.00        | 8,886.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,100.00             | 0.00            | 0.00        | 8,986.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,138.08             | 0.00            | 0.00        | 9,025.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR6</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 9,200.00             | 0.00            | 0.00        | 9,086.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,300.00             | 0.00            | 0.00        | 9,186.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,400.00             | 0.00            | 0.00        | 9,286.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,458.08             | 0.00            | 0.00        | 9,345.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>CR7</b>           |                 |             |                     |            |            |                       |                       |                      |                     |
| 9,500.00             | 0.00            | 0.00        | 9,386.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,600.00             | 0.00            | 0.00        | 9,486.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,700.00             | 0.00            | 0.00        | 9,586.92            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| 9,758.08             | 0.00            | 0.00        | 9,645.00            | -727.51    | 48.11      | 729.10                | 0.00                  | 0.00                 | 0.00                |
| <b>TD at 9758.08</b> |                 |             |                     |            |            |                       |                       |                      |                     |

| Design Targets                                |               |              |          |            |            |                 |                |                 |                  |
|---|---------------|--------------|----------|------------|------------|-----------------|----------------|-----------------|------------------|
| Target Name                                   | Dip Angle (°) | Dip Dir. (°) | TVD (ft) | +N/-S (ft) | +E/-W (ft) | Northing (usft) | Easting (usft) | Latitude        | Longitude        |
| - hit/miss target                             |               |              |          |            |            |                 |                |                 |                  |
| - Shape                                       |               |              |          |            |            |                 |                |                 |                  |
| 5-27D-36 BTR PBHL                             | 0.00          | 0.00         | 9,645.00 | -727.51    | 48.11      | 678,612.51      | 2,263,833.02   | 40° 11' 33.55 N | 110° 33' 20.01 W |
| - plan hits target center                     |               |              |          |            |            |                 |                |                 |                  |
| - Rectangle (sides W140.00 H200.00 D3,184.00) |               |              |          |            |            |                 |                |                 |                  |

|                  |                             |                                     |                       |
|------------------|-----------------------------|-------------------------------------|-----------------------|
| <b>Database:</b> | EDM 5000.1 Single User Db   | <b>Local Co-ordinate Reference:</b> | Well Well #1 - 16' KB |
| <b>Company:</b>  | Bill Barrett Corp.          | <b>TVD Reference:</b>               | KB @ 6078.00ft        |
| <b>Project:</b>  | Duchesne County, UT [NAD27] | <b>MD Reference:</b>                | KB @ 6078.00ft        |
| <b>Site:</b>     | 5-27D-36 BTR                | <b>North Reference:</b>             | True                  |
| <b>Well:</b>     | Well #1 - 16' KB            | <b>Survey Calculation Method:</b>   | Minimum Curvature     |
| <b>Wellbore:</b> | Wellbore #1                 |                                     |                       |
| <b>Design:</b>   | plan1 03may11 rbw           |                                     |                       |

| Formations          |                     |               |           |         |                   |  |
|---------------------|---------------------|---------------|-----------|---------|-------------------|--|
| Measured Depth (ft) | Vertical Depth (ft) | Name          | Lithology | Dip (°) | Dip Direction (°) |  |
| 3,135.00            | 3,135.00            | Green River   |           | 0.00    |                   |  |
| 3,834.67            | 3,833.00            | Mahogany      |           | 0.00    |                   |  |
| 5,305.91            | 5,216.00            | TGR3          |           | 0.00    |                   |  |
| 6,159.27            | 6,047.00            | Douglas Creek |           | 0.00    |                   |  |
| 6,574.08            | 6,461.00            | 3PT Marker    |           | 0.00    |                   |  |
| 6,901.08            | 6,788.00            | Black Shale   |           | 0.00    |                   |  |
| 7,075.08            | 6,962.00            | Castle Peak   |           | 0.00    |                   |  |
| 7,410.08            | 7,297.00            | Uteland Butte |           | 0.00    |                   |  |
| 7,490.08            | 7,377.00            | CR1           |           | 0.00    |                   |  |
| 7,796.08            | 7,683.00            | Wasatch       |           | 0.00    |                   |  |
| 7,952.08            | 7,839.00            | CR2           |           | 0.00    |                   |  |
| 8,232.08            | 8,119.00            | CR3           |           | 0.00    |                   |  |
| 8,552.08            | 8,439.00            | CR4           |           | 0.00    |                   |  |
| 8,828.08            | 8,715.00            | CR4A          |           | 0.00    |                   |  |
| 8,955.08            | 8,842.00            | CR5           |           | 0.00    |                   |  |
| 9,138.08            | 9,025.00            | CR6           |           | 0.00    |                   |  |
| 9,458.08            | 9,345.00            | CR7           |           | 0.00    |                   |  |

| Plan Annotations    |                     |                   |            |                                  |  |
|---------------------|---------------------|-------------------|------------|----------------------------------|--|
| Measured Depth (ft) | Vertical Depth (ft) | Local Coordinates |            |                                  |  |
|                     |                     | +N/-S (ft)        | +E/-W (ft) | Comment                          |  |
| 3,400.00            | 3,400.00            | 0.00              | 0.00       | Start Build 2.00                 |  |
| 4,592.18            | 4,558.07            | -243.97           | 16.13      | Start 392.33 hold at 4592.18 MD  |  |
| 4,984.51            | 4,916.91            | -402.22           | 26.60      | Start Drop -1.50                 |  |
| 6,574.08            | 6,461.00            | -727.51           | 48.11      | Start 3184.00 hold at 6574.08 MD |  |
| 9,758.08            | 9,645.00            | -727.51           | 48.11      | TD at 9758.08                    |  |

**EASEMENT LEASE AGREEMENT**  
**BILL BARRETT CORP.**  
**FOR WELLSITES #16-27D-36 BTR, #13-16-36 BTR, #5-27D-36 BTR, and their**  
**Supporting Roads and Pipelines, AND #7-16-36 BTR Pipeline Extension**  
**RABBITT GULCH UNIT OF TABBY MOUNTAIN WILDLIFE MANAGEMENT AREA**

UDWR Easement Lease No. DUC-1011EA-169 70 1493

THIS NON-EXCLUSIVE EASEMENT LEASE AGREEMENT (“**Agreement**”) is made by and between the **Utah Division of Wildlife Resources** whose address is 1594 West North Temple, Suite 2110, Salt Lake City, Utah 84114-6301 (hereafter "**Surface Owner**") and Bill Barrett Corp., whose address is 1099 18<sup>th</sup> Street, Suite 2300, Denver, Colorado 80202 (hereafter “**Lessee**”). Surface Owner and Lessee are collectively referred to as “the **Parties**”. “**Easement Lease**” means the lease of an easement or right-of-way, for which the purpose, specific use, rights granted, location, term, fees, and other conditions are set forth herein.

**EXHIBITS**

|     |  |
|-----|--|
| A.1 | Legal Descriptions of Wellsite, and Access Road and Pipeline Centerlines for Wellsite #16-27D-36                           |
| A.2 | Depiction of #16-27D-36 Wellsite and Access Road   |
| A.3 | Depiction of Pipeline for #16-27D-36 Wellsite  |
| B.1 | Legal Descriptions of Wellsite, and Access Road and Pipeline Centerlines for Wellsite #13-16-36 BTR                        |
| B.2 | Depiction of #13-16-36 BTR Wellsite and Access Road  |
| B.3 | Depiction of Pipeline for #13-16-36 BTR Wellsite   |
| C.1 | Legal Descriptions of Wellsite, and Access Road and Pipeline Centerlines for Wellsite #5-27D-36 BTR                        |
| C.2 | Depiction of #5-27D-36 BTR Wellsite and Access Road  |
| C.3 | Depiction of Pipeline for #5-27D-36 BTR Wellsite   |
| D.1 | Legal Descriptions Pipeline Centerline Extension of Corridor Servicing Wellsite #7-16-36 BTR                               |
| D.2 | Depiction of #7-16-36 BTR Pipeline Extension   |
| E   | Surface Use Plan for Lessee’s 2010 – 2011 Development Program, Lake Canyon and Blacktail Ridge Area, Duchesne County, Utah |
| F   | Reclamation Performance Bond Number LPM9032134   |
| G   | Cooperative Mitigation Agreement   |

**SECTION 1 GRANT AND LOCATION OF EASEMENT**

- 1.1

**Burdened Property.** Surface Owner owns certain real property known to Surface Owner as the Rabbit Gulch Unit of the Tabby Mountain Wildlife Management Area (“**WMA**”). Surface Owner represents that its purposes and uses of owning said WMA is to provide important habitat for wildlife, and to provide wildlife-based recreation for the general public. Surface Owner grants and conveys to Lessee a nonexclusive easement lease (“**Easement**”) for four wellsites (“**Wellsites**” or “**Damage Areas**”) and pipelines and access roads associated with those wellsites. The legal descriptions of the road and pipeline centerlines, and of the wellsites, whichever the case may be, of the portions of the WMA to which Lessee is hereby granted an Easement are set forth in Exhibits A.1, B.1, C.1, and D.1, said property hereafter referred to as “**Burdened Property**” and approximately depicted in Exhibits A.2, A.3, B.2, B.3, C.2, C.3, and D.2. Lessee shall have a 50-foot wide easement, 25 feet on either side of the pipeline centerlines described respectively in Exhibits A.1, B.1, C.1, and D.1 during the construction of the respective pipelines, thereafter to be reduced to a 30-foot width, 15 feet on either side of the respective centerlines. Access roads shall be of a width of 30 feet, 15 feet on either side of the respective centerlines described in Exhibits A.1, B.1, and C.1.
- 1.2

**Right of Third Parties.** This Easement is subject to all valid interests of third parties. Surface Owner claims title in fee simple, but does not warrant to Lessee the validity of title to the Burdened Property. Lessee shall have no claim for damages or refund against Surface Owner for any claimed failure or deficiency of Surface Owner’s title to said lands, or for interference by any third party.

## SECTION 26 MODIFICATION

Any modification of this Agreement must be in writing and signed by the parties. Surface Owner or Lessee shall not be bound by any oral representations of Surface Owner or Lessee. Authorized signatures for the Division of Wildlife Resources may be provided by only the Director or the Director's designee.

## SECTION 27 SURVIVAL

Any obligations which are not fully performed upon termination of this Easement shall not cease, but shall continue as obligations until fully performed.

## SECTION 28 WAIVER

No Waiver of Conditions by Surface Owner of any default of Lessee or failure of Surface Owner to timely enforce any provision of this Agreement shall constitute a waiver of or constitute a bar to subsequent enforcement of the same or other provisions of this Agreement. No provision in this Agreement shall be construed to prevent Surface Owner from exercising any legal or equitable remedy it may have.

## SECTION 29 WATER RIGHTS

Lessee shall not file an application to appropriate water from the surface or subsurface of Surface Owner's lands unless the application is approved by Surface Owner in writing and is filed in the name of the Surface Owner. All water structures, including impoundment, diversion and conveyance structures or works, used to impound, divert or convey water claimed solely under a Surface Owner water right shall be the property of Surface Owner.

## SECTION 30 INVALIDITY

If any provision of this Agreement proves to be invalid, void, or illegal, it shall in no way affect, impair, or invalidate any other provision of this Agreement.

IN WITNESS WHEREOF, the Parties have executed this Agreement, effective on the date of the last signature below.

### SURFACE OWNER


STATE OF UTAH  
DEPARTMENT OF NATURAL  
RESOURCES, DIVISION OF WILDLIFE  
RESOURCES

By:   
James F. Karpowitz **ACTING DIRECTOR**  
Director of Wildlife Resources

Date: 4/14/11

### LESSEE

**BILL BARRETT CORP.**

By:   
Huntington T. Walker  
Sr. Vice President - Land  
Bill Barrett Corporation

Date: April 4<sup>th</sup>, 2011

**SURFACE USE PLAN**

BILL BARRETT CORPORATION

**5-27D-36 BTR Well Pad**

SW NW, 1252' FNL and 660' FWL, Section 27, T3S-R6W, USB&M (surface hole)

SW NW, 1980' FNL and 700' FWL, Section 27, T3S-R6W, USB&M (bottom hole)

Duchesne County, Utah

---

The onsite inspection for this pad occurred on May 17, 2011. Site specific conditions or changes as a result of that onsite are indicated below. Plat changes requested at the onsite are reflected within this APD.

- Divert drainages around well pad as reflected on Figure 1;
- Utilize 20 mil liners over felt;
- Juniper Green paint color

The excavation contractor would be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:

- a. The proposed well site is located approximately 12.1 miles northwest of Duchesne, Utah. Maps and directions reflecting the route to the proposed well site are included (see Topographic maps A and B).
- b. The existing Duchesne County maintained Koch Road (CR-23) would be utilized from Highway 40 for 3.8 miles. From the Koch Road existing El Paso maintained access continues for 0.9 miles to the planned new access road.
- c. Project roads would require routine year-round maintenance to provide year-round access. Maintenance would include inspections, reduction of ruts and holes, maintenance to keep water off the road, replacement of surfacing materials, and clearing of sediment blocking ditches and culverts. Should snow removal become necessary, roads would be cleared with a motor grader and snow would be stored along the down gradient side to prohibit runoff onto the road. Aggregate would be used as necessary to maintain a solid running surface and minimize dust generation.
- d. Vehicle operators would obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions. Travel would be limited to the existing access roads and proposed access road.
- e. The use of roads under State Road Department and Duchesne County Road maintenance are necessary to access the project area with no improvements proposed. No encroachment or pipeline crossing permits are required.



Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- f. All existing roads would be maintained and kept in good repair during all phases of operation.

2. Planned Access Road:

- a. Approximately 857 feet of new access road trending south is planned from the existing El Paso maintained access road (see Topographic Map B).
- b. The road would be constructed to a 30-foot ROW width with an 18-foot travel surface. See section 12.d. below for disturbance estimates.
- c. New road construction and improvements of existing roads would typically require the use of motor graders, crawler tractors, 10-yard end dump trucks, and water trucks. The standard methodology for building new roads involves the use of a crawler tractor or track hoe to windrow the vegetation to one side of the road corridor, remove topsoil to the opposing side of the corridor, and rough-in the roadway. This is followed by a grader or bulldozer to establish barrow ditches and crown the road surface. Where culverts are required, a track hoe or backhoe would trench the road and install the culverts. Some hand labor would be required when installing and armoring culverts. Road base or gravel in some instances would be necessary and would be hauled in and a grader used to smooth the running surface.
- d. The proposed road would be constructed to facilitate drainage, control erosion and minimize visual impacts by following natural contours where practical. No unnecessary side-casting of material would occur on steep slopes.
- e. A maximum grade of 10% would be maintained throughout the project with minimum cuts and fills, as necessary, to access the well.
- f. Excess rock from construction of the pad may be used for surfacing of the access road if necessary. Any additional aggregate necessary would be obtained from private or State of Utah lands in conformance with applicable regulations. Aggregate would be of sufficient size, type, and amount to allow all weather access and alleviate dust.
- g. Where topsoil removal is necessary, it would be windrowed (i.e. stockpiled/accumulated along the edge of the ROW and in a low row/pile parallel with the ROW) and re-spread over the disturbed area after construction and backfilling are completed. Vegetation removed from the disturbed area would also be re-spread to provide protection, nutrient recycling, and a seed source for reclamation.
- h. Turnouts are not proposed because the access road is short and adequate site distance exists in all directions.

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- i. No culverts and no low-water crossings are anticipated. Adequate drainage structures, where necessary, would be incorporated into the remainder of the road to prevent soil erosion and accommodate all-weather traffic.
  - j. No gates or cattle guards are anticipated at this time.
  - k. Surface disturbance and vehicular travel would be limited to the approved location access road. Adequate signs would be posted, as necessary, to warn the public of project related traffic.
  - l. All access roads and surface disturbing activities would conform to the appropriate standard, **no higher than necessary**, to accommodate their intended function adequately as outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition – Revised 2007.
  - m. The operator would be responsible for all maintenance needs of the new access road.
- 3. Location of Existing Wells (see One-Mile Radius Map):
  - a. Following is a list of wells with surface hole locations within a one-mile radius of the proposed pad:

|                       |      |
|-----------------------|------|
| i. water wells        | none |
| ii. injection wells   | none |
| iii. disposal wells   | none |
| iv. drilling wells    | none |
| v. temp shut-in wells | one  |
| vi. producing wells   | six  |
| vii. abandoned wells  | six  |
- 4. Location of Production Facilities
  - a. Surface facilities would consist of a wellhead, separator, gas meter, (1) 500 gal methanol tank, (1) 500 glycol tank, (3) 500 bbl oil tanks, (1) 500 bbl water tank, (1) 500 bbl test tank, (1) 1000 gal propane tank, a pumping unit or Roto-flex unit or gas lift unit with a natural gas fired motor, solar panels, solar chemical and methanol pumps and one trace pump. See attached proposed facility diagram.
  - b. Most wells would be fitted with a pump jack or Roto-flex unit or gas lift to assist liquid production if liquid volumes and/or low formation pressures require it. Plunger lift systems do not require any outside source of energy. The prime mover for pump jacks or Roto-flex units would be small (75 horsepower or less), natural gas-fired internal combustion engines. If a gas lift is installed, it would be set on a 10 ft x 15 ft pad and the prime mover would be a natural gas-fired internal combustion engine rated at 200 horsepower or less or an electric compressor of similar horsepower powered by a generator.

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- c. The tank battery would be surrounded by a secondary containment berm of sufficient capacity to contain 1.1 times the entire capacity of the largest single tank and sufficient freeboard to contain precipitation. All loading lines and valves would be placed inside the berm surrounding the tank battery or would utilize catchment basins to contain spills. All liquid hydrocarbon production and measurement shall conform to the provisions of 43 CFR 3162.7-2 and Onshore Oil and Gas Order No. 4 for the measurement of oil.
- d. Gas meter run(s) would be constructed and located on lease within 500 feet of the wellheads. Meter runs would be housed and/or fenced. As practicably feasible, meters would be equipped with remote telemetry monitoring systems. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- e. A combustor may be installed at this location for control of associated condensate tank emissions. A combustor ranges from 24 inches to 48 inches wide and is approximately 27 ft tall. Combustor placement would be on existing disturbance.
- f. Approximately 888 feet of pipeline corridor (see Topographic Map C) containing up to three lines (one gas pipeline up to 8 inch in diameter, one water line up to 4 inch in diameter and one residue line up to 4 inch in diameter) is proposed trending north to the existing El Paso 11 pipeline corridor. Pipelines would be constructed of steel, polyethylene or fiberglass and would connect to the existing pipeline servicing nearby BBC and El Paso wells. The pipeline crosses entirely UDWR surface.
- g. The new segment of gas pipeline would be surface laid within a 30 foot wide pipeline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates.
- h. The use of the proposed well site and access roads would facilitate the staging of the pipeline construction.
- i. Pipeline construction methods and practices would be planned and conducted by BBC with the objective of enhancing reclamation and fostering the re-establishment of the native plant community.
- j. All permanent above-ground structures would be painted a flat, non-reflective color, such as Juniper Green, to match the standard environmental colors. All facilities would be painted the designated color at the time of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.

Bill Barrett Corporation  
 Surface Use Plan  
 #5-27D-36 BTR  
 Duchesne County, UT

- k. Site security guidelines identified in 43 CFR 3162.7-5 and Onshore Oil and Gas Order No. 3 would be adhered to. Any modifications to proposed facilities would be reflected in the site security diagram submitted.
- l. The site would require periodic maintenance to ensure that drainages are kept open and free of debris, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.

5. Location and Type of Water Supply:

- a. Water for the drilling and completion would be trucked from any of the following locations:

| Water Right No. and Application or Change No. | Applicant                            | Allocation                  | Date      | Point of Diversion   | Source            |
|---|--------------------------------------|-----------------------------|-----------|----------------------|-------------------|
| 43-180  | Duchesne City Water Service District | 5 cfs                       | 8/13/2004 | Knight Diversion Dam | Duchesne River    |
| 43-1202, Change a13837                        | Myton City                           | 5.49 cfr and 3967 acre feet | 3/21/1986 | Knight Diversion Dam | Duchesne River    |
| 43-10444, Appln A57477                        | Duchesne County Upper Country Water  | 2 cfs                       | 1994      | Ditch at Source      | Cow Canyon Spring |
| 43-10446, Appln F57432                        | Duchesne County Upper Country Water  | 1.58 cfs                    | 1994      | Ditch at Source      | Cow Canyon Spring |
| 43-1273, Appln A17462                         | J.J.N.P. Company                     | 7 cfs                       | 1946      | Strawberry River     | Strawberry River  |
| 43-1273, Appln t36590                         | J.J.N.P. Company                     | 4 cfs                       | 6/03/2010 | Strawberry River     | Strawberry River  |

- b. No new water well is proposed with this application.
- c. Should additional water sources be pursued they would be properly permitted through the State of Utah – Division of Water Rights.
- d. Water use would vary in accordance with the formations to be drilled but would be up to approximately 5.41 acre feet for drilling and completion operations.

6. Source of Construction Material:

- a. The use of materials would conform to 43 CFR 3610.2-3.
- b. No construction materials would be removed from the lease or EDA area.

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- c. If any additional gravel is required, it would be obtained from a local supplier having a permitted source of materials within the general area.

7. Methods of Handling Waste Disposal:

- a. All wastes associated with this application would be contained and disposed of utilizing approved facilities.
- b. The reserve pit would be constructed so as not to leak, break or allow any discharge.
- c. The reserve would be lined with 20 mil (minimum) thickness polyethylene nylon reinforced liner material. The liner(s) would overlay straw, dirt and/or bentonite if rock is encountered during excavation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit. A minimum of two feet of free board would be maintained between the maximum fluid level and the top of the reserve pit at all times.
- d. To deter livestock from entering the pit, the three sides exterior to the location would be fenced before drilling starts. Following the conclusion of drilling and completion activities, the fourth side would also be fenced.
- e. Drill cuttings would be contained in the pit and buried on-site for a period not to exceed six months, weather permitting
- f. Produced fluids from the well other than water would be decanted into steel test tank(s) until such time as construction of production facilities is completed. Any oil that may be accumulated would be transferred to a permanent production tank. Produced water may be used in further drilling and completion activities, evaporated in the pit, or would be hauled to one of the state-approved disposal facilities below:

| <b>Disposal Facilities</b>  |
|---|
| 1. RNI Industries, Inc. – Pleasant Valley Disposal Pits, Sec. 25, 26, 35 & 36, T4S-R3W                |
| 2. Pro Water LLC – Blue Bench 13-1 Disposal Well (43-013-30971) NENE, Sec. 13, T3S-R5W                |
| 3. RN Industries, Inc. – Bluebell Disposal Ponds, Sec. 2, 4 & 9, T2S-R2W                              |
| 4. Water Disposal, Inc. – Harmston 1-32-A1 Disposal Well (43-013-30224), UTR #00707, Sec. 32, T1S-R1W |
| 5. Unified Water Pits – Sec. 31, T2S-R4W  |
| 6. Iowa Tank Line Pits – 8500 BLM Fence Road, Pleasant Valley   |

- g. Any salts and/or chemicals, which are an integral part of the drilling system, would be disposed of in the same manner as the drilling fluid.

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- h. Any spills of oil, condensate, produced or frac water, drilling fluids, or other potentially deleterious substances would be recovered and either returned to its origin or disposed of at an approved disposal site, most likely in Duchesne, Utah.
- i. Chemicals on the EPA's Consolidated List of Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA) may be used or stored in quantities over reportable quantities. In the course of drilling, BBC could potentially store and use diesel fuel, sand (silica), hydrochloric acid, and CO<sub>2</sub> gas, all described as hazardous substances in 40 CFR Part 302, Section 302.4, in quantities exceeding 10,000 pounds. In addition, natural gas condensate and crude oil and methanol may be stored or used in reportable quantities. Small quantities of retail products (paint/spray paints, solvents {e.g., WD-40}, and lubrication oil) containing non-reportable volumes of hazardous substances may be stored and used on site at any time. No extremely hazardous substances, as defined in 40 CFR 355, would be used, produced, stored, transported or disposed of in association with the drilling, testing or completion of the wells.
- j. Portable toilets and trash containers would be located onsite during drilling and completion operations. A commercial supplier would install and maintain portable toilets and equipment and would be responsible for removing sanitary waste. Sanitary waste facilities (i.e. toilet holding tanks) would be regularly pumped and their contents disposed of at approved sewage disposal facilities in Duchesne, and/or Uintah Counties, in accordance with applicable rules and regulations regarding sewage treatment and disposal. Accumulated trash and nonflammable waste materials would be hauled to an approved landfill once a week or as often as necessary. All debris and waste materials not contained in the trash containers would be cleaned up, removed from the construction ROW, well pad, or worker housing location, and disposed of at an approved landfill. Trash would be cleaned up everyday.
- k. Sanitary waste equipment and trash bins would be removed from the Project Area upon completion of access road or pipeline construction; following drilling and completion operations at an individual well pad; when worker housing is no longer needed; or as required.
- l. A flare pit may be constructed a minimum of 110' from the wellhead(s) and may be used during completion work. In the event a flare pit proves to be unworkable, a temporary flare stack or open top tank would be installed. BBC would flow back as much fluid and gas as possible into pressurized vessels, separating the fluids from the gas. In some instances, due to the completion fluids utilized within the Project Area, it is not feasible to direct the flow stream from the wellbore through pressurized vessels. In such instances BBC proposes to direct the flow to the open top tanks until flow through the pressurized vessels is feasible. At which point the fluid would either be returned to the reserve pit or placed into a tank(s). The gas would be directed to the flare pit, flare stack (each with a constant source of ignition), or may be directed into the sales pipeline.

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- m. Hydrocarbons would be removed from the reserve pit would as soon as practical. In the event immediate removal is not practical, the reserve pit would be flagged overhead or covered with wire or plastic mesh to protect migrating birds.

8. Ancillary Facilities:

- a. Garbage containers and portable toilets would be located on the well pad.
- b. On well pads where active drilling and completion is occurring, temporary housing would be provided on location for the well pad supervisor, geologist, tool pusher, and others that are required to be on location at all times. The well pad could include up to five single wide mobile homes or fifth wheel campers/trailers.

9. Well Site Layout:

- a. The well would be properly identified in accordance with 43 CFR 3162.6.
- b. The pad layout, cross section diagrams and rig layout are enclosed (see Figures 1 and 2).
- c. The pad and road designs are consistent with industry specifications.
- d. The pad has been staked at its maximum size of 400 feet x 285 feet with an inboard reserve pit size of 100 feet x 200 feet x 8 feet deep. See section 12.d below for disturbance estimates.
- e. Within the approved well pad location, a crawler tractor would strip whatever topsoil is present and stockpile it along the edge of the well pad for use during reclamation. Vegetation would be distributed along the sides of the well pad.
- f. Fill from pit excavation would be stockpiled along the edge of the pit and the adjacent edge of the well pad.
- g. Use of erosion control measures, including proper grading to minimize slopes, diversion terraces and ditches, mulching, terracing, riprap, fiber matting, temporary sediment traps, and broad-based drainage dips or low water crossings would be employed by BBC as necessary and appropriate to minimize erosion and surface runoff during well pad construction and operation. Cut and fill slopes would be constructed such that stability would be maintained for the life of the activity.
- h. All cut and fill slopes would be such that stability can be maintained for the life of the activity.
- i. Diversion ditches would be constructed, if necessary, around the well site to prevent surface waters from entering the well site area.



Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

- j. Water application may be implemented if necessary to minimize the amount of fugitive dust.
- k. All surface disturbing activities would be supervised by a qualified, responsible company representative who is aware of the terms and conditions of the APD and specifications in the approved plans.

10. Plan for Restoration of the Surface:

- a. A site specific reclamation plan would be submitted, if requested, within 90 days of location construction to the surface managing agency or the fee landowners.
- b. Site reclamation would be accomplished for portions of the well pad not required for the continued operation of the well on this pad within six months of completion, weather permitting.
- c. The operator would control noxious weeds along access road use authorizations and well site by spraying or mechanical removal, according to the Utah Noxious Weed Act and as set forth in the approved surface damage agreements.
- d. Rat and mouse holes would be filled and compacted from bottom to top immediately upon release of the drilling rig from location. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. The reserve pit would be allowed to dry prior to the commencement of backfilling work. No attempts would be made to backfill the reserve pit until it is free of standing water. Once dry, the liner would be torn and perforated before backfilling.
- e. The reserve pit and that portion of the location not needed for production facilities/operations would be recontoured to the approximate natural contours. Areas not used for production purposes would be backfilled and blended into the surrounding terrain, reseeded and erosion control measures installed. Mulching, erosion control measures and fertilization may be required to achieve acceptable stabilization. Back slopes and fore slopes would be reduced as practical and scarified with the contour. The reserved topsoil would be evenly distributed over the slopes and scarified along the contour. Slopes would be seeded with the landowner specified seed mix.
- f. Topsoil salvaged from the drill site and stored for more than one year would be placed at the location indicated on the well site layout drawing and graded to a depth optimum to maintain topsoil viability, seeded with the landowner prescribed seed mixture and covered with mulch for protection from wind and water erosion and to discourage the invasion of weeds.



Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

11. Surface and Mineral Ownership:

- a. Surface ownership – Utah Division of Wildlife Resources – 1594 West North Temple, Suite 2110, Salt Lake City, Utah 84114-6301; 801-538-4744. Surface use remains in place through UDWR Right-of-Way DUC-1011EA-169.
- b. Mineral ownership – Ute Indian Tribe - 988 South 7500 East; Ft. Duchesne, Utah 84026; 435-725-4982.

12. Other Information:

- a. Montgomery Archeological Consultants has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Montgomery as MOAC 10-175 dated 9-24-2010.
- b. BBC would require that their personnel, contractors, and subcontractors to comply with Federal regulations intended to protect archeological and cultural resources.
- c. Project personnel and contractors would be educated on and subject to the following requirements:
  - No dogs or firearms within the Project Area.
  - No littering within the Project Area.
  - Smoking within the Project Area would only be allowed in off-operator active locations or in specifically designated smoking areas. All cigarette butts would be placed in appropriate containers and not thrown on the ground or out windows of vehicles; personnel and contractors would abide by all fire restriction orders.
  - Campfires or uncontained fires of any kind would be prohibited.
  - Portable generators used in the Project Area would have spark arrestors.
- d. Disturbance estimates:

**Approximate Acreage Disturbances**

|          |          |       |       |
|----------|----------|-------|-------|
| Well Pad |          | 3.461 | acres |
| Access   | 857 feet | 0.573 | acres |
| Pipeline | 888 feet | 0.595 | acres |

**Total            4.629    acres**

Bill Barrett Corporation  
Surface Use Plan  
#5-27D-36 BTR  
Duchesne County, UT

OPERATOR CERTIFICATION

Certification:


I hereby certify that I, or someone under my direction supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein would be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application and that bond coverage is provided under Bill Barrett Corporations federal nationwide bond. These statements are subject to the provisions of 18 U.S.C. 1001 for the filings of false statements.

|                      |  |
|----------------------|--|
| Executed this        | <u>4th</u> day of <u>August</u> 2011                       |
| Name:                | Venessa Langmacher   |
| Position Title:      | Senior Permit Analyst                                      |
| Address:             | 1099 18 <sup>th</sup> Street, Suite 2300, Denver, CO 80202 |
| Telephone:           | 303-312-8172   |
| E-mail:              | vlangmacher@billbarrettcorp.com                            |
| Field Representative | Kary Eldredge / Bill Barrett Corporation                   |
| Address:             | 1820 W. Highway 40, Roosevelt, UT 84066                    |
| Telephone:           | 435-725-3515 (office); 435-724-6789 (mobile)               |
| E-mail:              | keldredge@billbarrettcorp.com                              |

  
\_\_\_\_\_  
Venessa Langmacher, Senior Permit Analyst


## BILL BARRETT CORPORATION

### TYPICAL 5,000 p.s.i. BLOWOUT PREVENTER



# BILL BARRETT CORPORATION

## TYPICAL 5,000 p.s.i. CHOKE MANIFOLD





August 4, 2011

Ms. Diana Mason – Petroleum Technician  
State of Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P. O. Box 145801  
Salt Lake City, Utah 84114-5801

Re: Directional Drilling R649-3-11  
**Blacktail Ridge Area #5-27D-36 BTR Well**  
Surface: 1,252' FNL & 660' FWL, SWNW, 27-T3S-R6W, USM  
Bottom Hole: 1,980' FNL & 700' FWL, SWNW, 27-T3S-R6W, USM  
Duchesne County, Utah


Dear Ms. Mason,

Pursuant to the filing of Bill Barrett Corporation's ("BBC") Application for Permit to Drill the above referenced well, we hereby submit this letter in accordance with Oil & Gas Conservation Rules R649-2, R649-3, R649-10 and R649-11, pertaining to the Location and Siting of Wells.

- The proposed location is within our Blacktail Ridge Area.
- BBC is permitting this well as a directional well in order to minimize surface disturbance. By locating the well at the surface location and directionally drilling from this location, BBC will be able to utilize the existing road and pipelines in the area.
- The well will be drilled under an Exploration and Development Agreement between the Ute Indian Tribe and Ute Distribution Corporation. Ute Energy, LLC owns a right to participate in this well.
- BBC certifies that it is the working interest owner of all lands within 460 feet of the proposed well location, and together with Ute Energy, LLC, we own 100% of the working interest in these lands.

Based on the information provided, BBC requests that the permit be granted pursuant to R649-3-11. Should you have any questions or need further information, please contact me at 303-312-8544.

Sincerely,

  
David Watts  
Landman

1099 18<sup>TH</sup> STREET  
SUITE 2300  
DENVER, CO 80202  
P 303.293.9100  
F 303.291.0420

**BILL BARRETT CORPORATION**

## LOCATION LAYOUT FOR

#5-27D-36 BTR

SECTION 27, T3S, R6W, U.S.B.&amp;M.

1252' FNL 660' FWL


**FIGURE #1**

SCALE: 1" = 60'

DATE: 08-20-10

DRAWN BY: C.C.

REVISED: 04-27-11



**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**RECEIVED: August 04, 2011**

**BILL BARRETT CORPORATION****TYPICAL CROSS SECTION FOR**






#5-27D-36 BTR

SECTION 27, T3S, R6W, U.S.B.&amp;M.

1252' FNL 660' FWL

**FIGURE #2**

1" = 40'  
X-Section  
Scale  
1" = 100'  
DATE: 08-20-10  
DRAWN BY: C.C.

**NOTE:**

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

**APPROXIMATE ACREAGES**

WELL SITE DISTURBANCE = ± 3.461 ACRES  
ACCESS ROAD DISTURBANCE = ± 0.573 ACRES  
PIPELINE DISTURBANCE = ± 0.595 ACRES  
TOTAL = ± 4.629 ACRES

**\* NOTE:**

FILL QUANTITY INCLUDES 5% FOR COMPACTION

**APPROXIMATE YARDAGES**

(6") Topsoil Stripping = 2,480 Cu. Yds.  
Remaining Location = 15,700 Cu. Yds.  
TOTAL CUT = 18,180 CU.YDS.  
FILL = 8,490 CU.YDS.

EXCESS MATERIAL = 9,690 Cu. Yds.  
Topsoil & Pit Backfill = 4,940 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 4,750 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**RECEIVED: August 04, 2011**

**BILL BARRETT CORPORATION****TYPICAL RIG LAYOUT FOR**


**#5-27D-36 BTR**  
**SECTION 27, T3S, R6W, U.S.B.&M.**  
**1252' FNL 660' FWL**

**FIGURE #3**


SCALE: 1" = 60'  
 DATE: 08-20-10  
 DRAWN BY: C.C.



Proposed  
Access Road



**NOTE:**  
 Flare Pit is to  
 be located a min.  
 of 100' from the  
 Well Head.




**UINTAH ENGINEERING & LAND SURVEYING**  
 85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**RECEIVED: August 04, 2011**




API Well Number: 43013509170000

5-27D-36 BTR  
FACILITY LAYOUT





RECEIVED: August 04, 2011



**API Number: 4301350917**  
**Well Name: 5-27D-36**  
**Township T0.3 . Range R0.6 . Section 27**  
**Meridian: UBM**  
**Operator: BILL BARRETT CORP**

Map Prepared:  
 Map Produced by Diana Mason



# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

|                          |                   |                      |                                     |                   |                  |
|--------------------------|-------------------|----------------------|-------------------------------------|-------------------|------------------|
| <b>Operator</b>          | BILL BARRETT CORP |                      |                                     |                   |                  |
| <b>Well Name</b>         | 5-27D-36          |                      |                                     |                   |                  |
| <b>API Number</b>        | 43013509170000    | <b>APD No</b>        | 4325                                | <b>Field/Unit</b> | CEDAR RIM        |
| <b>Location: 1/4,1/4</b> | SWNW              | <b>Sec</b> 27        | <b>Tw</b> 3.0S                      | <b>Rng</b> 6.0W   | 1252 FNL 660 FWL |
| <b>GPS Coord (UTM)</b>   | 537819 4449249    | <b>Surface Owner</b> | Utah Division of Wildlife Resources |                   |                  |

### **Participants**

James Hereford (BLM), Kary Eldredge (Bill Barrett), Roger Knight (Bill Barrett), Don Hamilton (Star Point), Trevor Anderson (UELS), Matt Serfustini (EIS), Richard Powell (DOGM), Kelly Jo Jackson (Montgomery), Ben Williams (DWR)

### **Regional/Local Setting & Topography**

This location sits just to the north of Rabbit Gulch. The area around this location slopes gradually toward the gulch but drops off steeply close to the drainage. Rabbit Gulch is a large dry wash which flows to Starvation Lake approximately 3 miles to the east. It is the primary drainage and namesake of this region. Duchesne, UT is approximately 11 miles to the east.

### **Surface Use Plan**

#### **Current Surface Use**

Wildlife Habitat  
Deer Winter Range

|                       |                                    |                           |                          |
|-----------------------|------------------------------------|---------------------------|--------------------------|
| <b>New Road Miles</b> | <b>Well Pad</b>                    | <b>Src Const Material</b> | <b>Surface Formation</b> |
| 0.16                  | <b>Width</b> 285 <b>Length</b> 400 | Onsite                    | UNTA                     |

**Ancillary Facilities** N

**Waste Management Plan Adequate?** Y

### **Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

#### **Flora / Fauna**

Deer, elk, coyote, rabbits and other small mammals, song birds, raptors  
Sage, prickly pear cactus, grasses, salt brush, shadscale, rabbit brush, horse brush

#### **Soil Type and Characteristics**

Sandy clay

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required?** N

**Berm Required?** Y

**Erosion Sedimentation Control Required? N****Paleo Survey Run? Y   Paleo Potential Observed? N   Cultural Survey Run? Y   Cultural Resources? N****Reserve Pit****Site-Specific Factors****Site Ranking**

|  |                  |                     |
|--|------------------|---------------------|
| <b>Distance to Groundwater (feet)</b>    | >200             | 0                   |
| <b>Distance to Surface Water (feet)</b>  | >1000            | 0                   |
| <b>Dist. Nearest Municipal Well (ft)</b> | >5280            | 0                   |
| <b>Distance to Other Wells (feet)</b>    | >1320            | 0                   |
| <b>Native Soil Type</b>                  | Mod permeability | 10                  |
| <b>Fluid Type</b>                        | Fresh Water      | 5                   |
| <b>Drill Cuttings</b>                    | Normal Rock      | 0                   |
| <b>Annual Precipitation (inches)</b>     | 10 to 20         | 5                   |
| <b>Affected Populations</b>              |                  |                     |
| <b>Presence Nearby Utility Conduits</b>  | Not Present      | 0                   |
| <b>Final Score</b>                       | 20               | 1 Sensitivity Level |

**Characteristics / Requirements**

The reserve pit will be placed in cut in a stable location. The pit will be 100ft x 200ft x 8ft deep with a total capacity including freeboard of 16,830bbl. Kary Eldredge of BBC said they will use a 16 mil liner with a felt sub-liner. This will be adequate for the site.

**Closed Loop Mud Required? N   Liner Required? Y   Liner Thickness 16   Pit Underlayment Required? Y****Other Observations / Comments**

Richard Powell  
**Evaluator**

5/17/2011  
**Date / Time**

# Application for Permit to Drill Statement of Basis

8/17/2011

Utah Division of Oil, Gas and Mining

Page 1

|                  |   |               |                          |                                     |            |
|------------------|---|---------------|--------------------------|-------------------------------------|------------|
| <b>APD No</b>    | <b>API WellNo</b>   | <b>Status</b> | <b>Well Type</b>         | <b>Surf Owner</b>                   | <b>CBM</b> |
| 4325             | 43013509170000  | LOCKED        | OW                       | S                                   | No         |
| <b>Operator</b>  | BILL BARRETT CORP   |               | <b>Surface Owner-APD</b> | Utah Division of Wildlife Resources |            |
| <b>Well Name</b> | 5-27D-36  |               | <b>Unit</b>              |                                     |            |
| <b>Field</b>     | CEDAR RIM   |               | <b>Type of Work</b>      | DRILL                               |            |
| <b>Location</b>  | SWNW 27 3S 6W U 1252 FNL 660 FWL GPS Coord (UTM) 537816E 4449237N |               |                          |                                     |            |

**Geologic Statement of Basis**

The mineral rights for the proposed well are owned by the Ute Tribe. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill  
**APD Evaluator**

8/17/2011  
**Date / Time**

**Surface Statement of Basis**

This onsite evaluation was arranged by James Hereford of the BLM in cooperation with Bill Barrett Corp and was scheduled prior to the APD being submitted to UDOGM. A surface use agreement is in place. Kary Eldredge of Bill Barrett stated that a 16 mil liner and felt subliner would be used. Mr. Hereford of the BLM requested that the wood removed from this location be piled for use during reclamation. Ben Williams of DWR stated that this is crucial deer winter range and requested that there be no construction or drill from October 15 to April 15 but this can be waived if payment is made. This appears to be a good site for this location.

Richard Powell  
**Onsite Evaluator**

5/17/2011  
**Date / Time**

**Conditions of Approval / Application for Permit to Drill**

|                 |   |
|-----------------|---|
| <b>Category</b> | <b>Condition</b>  |
| Pits            | A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit. |
| Surface         | The well site shall be bermed to prevent fluids from leaving the pad.   |
| Surface         | The reserve pit shall be fenced upon completion of drilling operations.   |

**RECEIVED: August 17, 2011**

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 8/4/2011**API NO. ASSIGNED:** 43013509170000**WELL NAME:** 5-27D-36**OPERATOR:** BILL BARRETT CORP (N2165)**PHONE NUMBER:** 303 312-8172**CONTACT:** Venessa Langmacher**PROPOSED LOCATION:** SWNW 27 030S 060W**Permit Tech Review:** ☒**SURFACE:** 1252 FNL 0660 FWL**Engineering Review:** ☐**BOTTOM:** 1980 FNL 0700 FWL**Geology Review:** ☒**COUNTY:** DUCHESNE**LATITUDE:** 40.19457**LONGITUDE:** -110.55573**UTM SURF EASTINGS:** 537816.00**NORTHINGS:** 4449237.00**FIELD NAME:** CEDAR RIM**LEASE TYPE:** 2 - Indian**LEASE NUMBER:** 2OG0005608**PROPOSED PRODUCING FORMATION(S):** GREEN RIVER-WASATCH**SURFACE OWNER:** 3 - State**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**☒ **PLAT**☒ **Bond:** INDIAN - LPM8874725☐ **Potash**☐ **Oil Shale 190-5**☐ **Oil Shale 190-3**☐ **Oil Shale 190-13**☒ **Water Permit:** Duchesne City Culinary Water Dock☐ **RDCC Review:**☒ **Fee Surface Agreement**☐ **Intent to Commingle****Commingle Approved****LOCATION AND SITING:**☐ **R649-2-3.****Unit:**☐ **R649-3-2. General**☐ **R649-3-3. Exception**☒ **Drilling Unit****Board Cause No:** Cause 139-84**Effective Date:** 12/31/2008**Siting:** 4 Prod LGRRV-WSTC Wells in Drl Units☒ **R649-3-11. Directional Drill****Comments:** Presite Completed**Stipulations:**  
4 - Federal Approval - dmason  
5 - Statement of Basis - bhll  
15 - Directional - dmason**RECEIVED: August 17, 2011**



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** 5-27D-36

**API Well Number:** 43013509170000

**Lease Number:** 2OG0005608

**Surface Owner:** STATE

**Approval Date:** 8/17/2011

**Issued to:**

BILL BARRETT CORP, 1099 18th Street Ste 2300, Denver, CO 80202

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-84. The expected producing formation or pool is the GREEN RIVER-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>



**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas



RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

AUG 08 2011

FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

## APPLICATION FOR PERMIT TO DRILL OR REENTER

|  |   |  |
|--|---|--|
| 1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER   |   | 5. Lease Serial No.<br>2OG0005608  |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone                             |   | 6. If Indian, Allottee or Tribe Name                                       |
| 2. Name of Operator<br>BILL BARRETT CORPORATION Contact: VENESSA LANGMACHER<br>E-Mail: vlangmacher@billbarrettcorp.com   |   | 7. If Unit or CA Agreement, Name and No.                                   |
| 3a. Address<br>1099 18TH STREET SUITE 2300<br>DENVER, CO 80202   | 3b. Phone No. (include area code)<br>Ph: 303-312-8172<br>Fx: 303-291-0420 | 8. Lease Name and Well No.<br>5-27D-36 BTR                                 |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface SWNW 1252FNL 660FWL 40.194606 N Lat, 110.556442 W Lon<br>At proposed prod. zone SWNW 1980FNL 700FWL 40.194606 N Lat, 110.556442 W Lon |   | 9. API Well No.<br>43 013 50917  |
| 14. Distance in miles and direction from nearest town or post office*<br>12.1 MILES NORTHWEST OF DUCHESNE, UT  |   | 10. Field and Pool, or Exploratory<br>CEDAR RIM                            |
| 15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)<br>700' (BOTTOM HOLE)   | 16. No. of Acres in Lease<br>66101.00                                     | 11. Sec., T., R., M., or Blk. and Survey or Area<br>Sec 27 T3S R6W Mer UBM |
| 18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft.<br>2066'   | 19. Proposed Depth<br>9758 MD<br>9645 TVD                                 | 12. County or Parish<br>DUCHESNE   |
| 21. Elevations (Show whether DF, KB, RT, GL, etc.)<br>6064 GL  | 22. Approximate date work will start<br>07/01/2012                        | 13. State<br>UT  |
| 20. BLM/BIA Bond No. on file<br>LPM8874725   |   | 17. Spacing Unit dedicated to this well<br>640.00                          |
| 23. Estimated duration<br>60 DAYS (D&C)  |   |  |

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

|   |   |                     |
|---|---|---------------------|
| 25. Signature<br>(Electronic Submission)                      | Name (Printed/Typed)<br>VENESSA LANGMACHER Ph: 303-312-8172 | Date<br>08/04/2011  |
| Title<br>SENIOR PERMIT ANALYST                                |   |                     |
| Approved by (Signature)<br>                                   | Name (Printed/Typed)<br>Jerry Kenczka                       | Date<br>OCT 24 2011 |
| Title<br>Assistant Field Manager<br>Lands & Mineral Resources | Office<br>VERNAL FIELD OFFICE                               |                     |

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

## CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

## Additional Operator Remarks (see next page)

Electronic Submission #114573 verified by the BLM Well Information System  
For BILL BARRETT CORPORATION, sent to the Vernal  
Committed to AFMSS for processing by LESLIE ROBINSON on 08/08/2011 ()

NOTICE OF APPROVAL

OCT 27 2011

UDOGM

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*

11SS01077A9.

NOS- 5/2/11



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

|          |                          |            |                           |
|----------|--------------------------|------------|---------------------------|
| Company: | Bill Barrett Corporation | Location:  | SWNW, Sec. 27 T3S R6W USM |
| Well No: | 5-27D-36 BTR             | Lease No:  | EDA 2OG0005608            |
| API No:  | 43-013-50860 50917       | Agreement: | 2OG0005608                |

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

|   |  |
|---|--|
| Construction Activity<br>(Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)   | - The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.                                      |
| Construction Completion<br>(Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist) | - Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig. |
| Spud Notice<br>(Notify BLM Petroleum Engineer)  | - Twenty-Four (24) hours prior to spudding the well.   |
| Casing String & Cementing<br>(Notify BLM Supv. Petroleum Tech.)                                       | - Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm_ut_vn_opreport@blm.gov</a> .   |
| BOP & Related Equipment Tests<br>(Notify BLM Supv. Petroleum Tech.)                                   | - Twenty-Four (24) hours prior to initiating pressure tests.   |
| First Production Notice<br>(Notify BLM Petroleum Engineer)  | - Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.   |

RECEIVED

OCT 27 2011

BLM OFIL 0101110000

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

- Any deviation of submitted APD's, which includes BBCs surface use plan, and ROW applications the operator will notify the BLM in writing and will receive written authorization of any such change with appropriate authorization.
- The operator will implement "Safety and Emergency Plan." The operator's safety director will ensure its compliance.
- All operator employees and/or authorized personnel (sub-contractors) in the field will have approved applicable Easement Agreements from the UDWR, APD's, COAs, and ROW permits/authorizations on their person(s) during all phases of construction.
- Additional mitigation measures in Easement Agreement 169 issued by the UDWR shall be followed and implemented onsite during all phases of work.
- All vehicular traffic, personnel movement, construction/restoration operations should be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- Wood shall be saved per the surface owner's recommendations piled up around well pad and along access roads. Wood from the locations can also be used for reclamation purposes and habitat improvements.
- Noxious weeds will be treated, monitored, and controlled along both the access road, pipeline route, and on the well pad itself.
- Minimal vegetation removal around the well pad to lessen the visual impact and to aid in revegetation efforts in the future.
- Insure topsoil stability on location and use topsoil for interim reclamation as soon as possible to maintain viability of topsoil resource.
- Pipeline will be buried adjacent to the access road and reclaimed as soon as recontouring takes place and seeded prior to ground freeze.
- All above ground production facilities will be painted Beetle Green on all locations to help blend in with the surrounding habitat.
- Roads should be crown and ditched to divert any runoff from pooling on the road surface itself, this also aids in lessening erosion on the road and disturbed area. Wing ditches can be installed to also aid in controlling runoff from affecting the proposed road. These should be spaced to adequately catch any runoff along the ditches and aid in diverted water to the surrounding vegetation.
- The operator must conduct operations to minimize adverse effects to surface and subsurface resources, prevent unnecessary surface disturbance, and conform to currently available technologies and practices.

RECEIVED

OCT 27 2011

BLM OF CALIFORNIA

- Site reclamation would be accomplished for portions of the well pad not needed for production, within 6 months of completion, weather permitting. This also includes any roads, and pipeline areas that have been disturbed as well. Roads and pipeline disturbances can undergo reclamation immediately after the pipeline is installed and after the roads are built. Please contact UDWR or the BLM for possible seed mixes to use in the project area. Seeds should be planted in August and prior to ground freeze. Non-natives can be used; however lbs/ac must be kept low to minimize the chance of a monoculture.

RECEIVED

OCT 27 2011

DIV. OF OIL & GAS

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- Production casing cement shall be brought up and into the surface casing. The minimum cement top is 400 ft. above the surface casing shoe.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person

RECEIVED

OCT 27 2011

DM OF DL 00111111

making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM\_UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

RECEIVED

OCT 27 2011

DIV. OF OIL, GAS & MIN.



## OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location ( $\frac{1}{4}$  Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

RECEIVED  
OCT 27 2011

BLM OF CO, Vernal Field Office

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

RECEIVED

OCT 27 2011

DIV. OF OIL, GAS & MINERAL

## BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corporation Rig Name/# Triple A Drilling  
Submitted By Tracey Fallang Phone Number 303-312-8134  
Well Name/Number 5-27D-36 BTR  
Qtr/Qtr SWNW Section 27 Township 3S Range 6W  
Lease Serial Number 2OG0005608  
API Number 43-013-50917

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 4/11/2012 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing  
☐ Intermediate Casing  
☐ Production Casing  
☐ Liner  
☐ Other

RECEIVED

APR 10 2012

DIV. OF OIL, GAS & MINING

Date/Time \_\_\_\_\_ AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point  
☐ BOPE test at intermediate casing point  
☐ 30 day BOPE test  
☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks \_\_\_\_\_

## BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corporation Rig Name/# Triple A Drilling  
Submitted By Tracey Fallang Phone Number 303-312-8134  
Well Name/Number 5-27D-36 BTR  
Qtr/Qtr SWNW Section 27 Township 3S Range 6W  
Lease Serial Number 2OG0005608  
API Number 43-013-50917

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 4/11/2012 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing  
☐ Intermediate Casing  
☐ Production Casing  
☐ Liner  
☐ Other

RECEIVED

APR 10 2012

DIV. OF OIL, GAS & MINING

Date/Time \_\_\_\_\_ AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point  
☐ BOPE test at intermediate casing point  
☐ 30 day BOPE test  
☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks \_\_\_\_\_  
\_\_\_\_\_

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: Bill Barrett Corporation Operator Account Number: N 2165  
Address: 1099 18th Street, Suite 2300  
city Denver  
state CO zip 80202 Phone Number: (303) 312-8172

**Well 1**

| API Number   | Well Name             |                   | QQ        | Sec | Twp                              | Rng | County   |
|--|-----------------------|-------------------|-----------|-----|----------------------------------|-----|----------|
| 4301350917   | 5-27D-36 BTR          |                   | SWNW      | 27  | 3S                               | 6W  | Duchesne |
| Action Code  | Current Entity Number | New Entity Number | Spud Date |     | Entity Assignment Effective Date |     |          |
| A  | 99999                 | 18482             | 4/13/2012 |     | 4/23/2012                        |     |          |
| <b>Comments:</b> Actual spudding operation was conducted by Triple A Drilling @ 8:00 am.<br>GR-US BHL SWNW |                       |                   |           |     |                                  |     |          |

**Well 2**

| API Number       | Well Name             |                   | QQ        | Sec | Twp                              | Rng | County |
|------------------|-----------------------|-------------------|-----------|-----|----------------------------------|-----|--------|
|                  |                       |                   |           |     |                                  |     |        |
| Action Code      | Current Entity Number | New Entity Number | Spud Date |     | Entity Assignment Effective Date |     |        |
|                  |                       |                   |           |     |                                  |     |        |
| <b>Comments:</b> |                       |                   |           |     |                                  |     |        |

**Well 3**

| API Number       | Well Name             |                   | QQ        | Sec | Twp                              | Rng | County |
|------------------|-----------------------|-------------------|-----------|-----|----------------------------------|-----|--------|
|                  |                       |                   |           |     |                                  |     |        |
| Action Code      | Current Entity Number | New Entity Number | Spud Date |     | Entity Assignment Effective Date |     |        |
|                  |                       |                   |           |     |                                  |     |        |
| <b>Comments:</b> |                       |                   |           |     |                                  |     |        |

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

**RECEIVED**

APR 18 2012

Div. of Oil, Gas & Mining

Venessa Langmacher

Name (Please Print)

Venessa Langmacher

Signature

Sr Permit Analyst

Title

4/13/2012

Date

BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corp. Rig Name/# Patterson Rig 506  
Submitted By Lawrence Lorenzen Phone Number 435-828-6095  
Well Name/Number 5-27D-36 BTR  
Qtr/Qtr SW/NW Section 27 Township 3S Range 6W  
Lease Serial Number 2OG0005608  
API Number 43-013-50917

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 5/01/12 05:00 AM ☐ PM ☒

BOPE

- ☒ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

RECEIVED

MAY 01 2012

DIV. OF OIL, GAS & MINING

Date/Time 5/02/2012 5:00 AM ☐ PM ☒

Remarks Estimated date and time based on current conditions.



|  |                                      |   |
|--|--------------------------------------|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |                                      | FORM 9  |
|  |                                      | 5. LEASE DESIGNATION AND SERIAL NUMBER:<br>20G0005608 |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |                                      | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME:                 |
|  |                                      | 7. UNIT or CA AGREEMENT NAME:                         |
| 1. TYPE OF WELL<br>Oil Well  | 8. WELL NAME and NUMBER:<br>5-27D-36 |   |
| 2. NAME OF OPERATOR:<br>BILL BARRETT CORP  | 9. API NUMBER:<br>43013509170000     |   |
| 3. ADDRESS OF OPERATOR:<br>1099 18th Street Ste 2300 , Denver, CO, 80202   | PHONE NUMBER:<br>303 312-8164 Ext    | 9. FIELD and POOL or WILDCAT:<br>CEDAR RIM            |
| 4. LOCATION OF WELL<br>FOOTAGES AT SURFACE:<br>1252 FNL 0660 FWL<br>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:<br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U   | COUNTY:<br>DUCHESNE                  |   |
|  |                                      | STATE:<br>UTAH  |

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |   |  |
|--|--|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT<br>Approximate date work will start:   | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR                  |  |
| <input type="checkbox"/> SUBSEQUENT REPORT<br>Date of Work Completion:           | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME               |  |
| <input type="checkbox"/> SPUD REPORT<br>Date of Spud:                            | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE              |  |
| <input checked="" type="checkbox"/> DRILLING REPORT<br>Report Date:<br>4/30/2012 | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION               |  |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK                      |  |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |  |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON              |  |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL                 |  |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input type="checkbox"/> APD EXTENSION                  |  |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          | OTHER: <input style="width: 100px;" type="text"/>       |  |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Well spud this month; no other April 2012 monthly drilling activity to report.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 May 09, 2012

|                                    |                              |                         |
|------------------------------------|------------------------------|-------------------------|
| NAME (PLEASE PRINT)<br>Brady Riley | PHONE NUMBER<br>303 312-8115 | TITLE<br>Permit Analyst |
| SIGNATURE<br>N/A                   |                              | DATE<br>5/3/2012        |

BLM - Vernal Field Office - Notification Form

Operator Bill Barrett Corp. Rig Name/# Patterson Rig 506  
Submitted By Pat Clark Phone Number 435-828-6095  
Well Name/Number 5-27D-36 BTR  
Qtr/Qtr SW/NW Section 27 Township 3S Range 6W  
Lease Serial Number 2OG0005608  
API Number 43-013-50917

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

RECEIVED

MAY 15 2012

DIV. OF OIL, GAS & MINING

Date/Time 5/13/12 05:00 AM ☒ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☒

Remarks Estimated date and time based on current conditions.

|  |                                      |   |
|--|--------------------------------------|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |                                      | FORM 9  |
|  |                                      | 5. LEASE DESIGNATION AND SERIAL NUMBER:<br>20G0005608 |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |                                      | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME:                 |
|  |                                      | 7. UNIT or CA AGREEMENT NAME:                         |
| 1. TYPE OF WELL<br>Oil Well  | 8. WELL NAME and NUMBER:<br>5-27D-36 |   |
| 2. NAME OF OPERATOR:<br>BILL BARRETT CORP  | 9. API NUMBER:<br>43013509170000     |   |
| 3. ADDRESS OF OPERATOR:<br>1099 18th Street Ste 2300 , Denver, CO, 80202   | PHONE NUMBER:<br>303 312-8164 Ext    | 9. FIELD and POOL or WILDCAT:<br>CEDAR RIM            |
| 4. LOCATION OF WELL<br>FOOTAGES AT SURFACE:<br>1252 FNL 0660 FWL<br>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:<br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U   | COUNTY:<br>DUCHESNE                  |   |
|  |                                      | STATE:<br>UTAH  |

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |   |  |
|--|--|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT<br>Approximate date work will start:   | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR                  |  |
| <input type="checkbox"/> SUBSEQUENT REPORT<br>Date of Work Completion:           | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME               |  |
| <input type="checkbox"/> SPUD REPORT<br>Date of Spud:                            | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE              |  |
| <input checked="" type="checkbox"/> DRILLING REPORT<br>Report Date:<br>5/31/2012 | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION               |  |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK                      |  |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |  |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON              |  |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL                 |  |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input type="checkbox"/> APD EXTENSION                  |  |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          | OTHER: <input type="text"/>                             |  |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

May 2012 monthly drilling activity report is attached.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 June 01, 2012

|                                       |                              |                         |
|---------------------------------------|------------------------------|-------------------------|
| NAME (PLEASE PRINT)<br>Megan Finnegan | PHONE NUMBER<br>303 299-9949 | TITLE<br>Permit Analyst |
| SIGNATURE<br>N/A                      | DATE<br>6/1/2012             |                         |

**5-27D-36 BTR 5/1/2012 06:00 - 5/2/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category            | Com  |
|------------|----------|----------|------|---------------------|--|
| 06:00      | 8.50     | 14:30    | 2    | DRILL ACTUAL        | Drlg 2325-2705', 380' in 8.5 hrs 45 fph. Start build sec @ 2500'. Survey @ 2701' 4.95* @ 160.18 azi. MW 8.9 36 vis |
| 14:30      | 0.50     | 15:00    | 7    | LUBRICATE RIG       | Rig service  |
| 15:00      | 8.00     | 23:00    | 2    | DRILL ACTUAL        | Drlg 2705-3037'. 330' in 8 hrs 41 fph. MW 9# 36 vis Final survey @ 2970 8.62* @ 156.8. Pump sweep prep for TOH     |
| 23:00      | 4.00     | 03:00    | 6    | TRIPS               | TOH for casing. Rig up L/D truck and laydown 8" BHA  |
| 03:00      | 3.00     | 06:00    | 12   | RUN CASING & CEMENT | Rig up casing crew. Pickup float equip and run csg.  |

**5-27D-36 BTR 5/2/2012 06:00 - 5/3/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category            | Com  |
|------------|----------|----------|------|---------------------|--|
| 06:00      | 14.00    | 20:00    | 12   | RUN CASING & CEMENT | Run csg as follows Float shoe, 1 jt csg, Float collar and 68 jts 9 5/8" 36# J55 csg. Land @ 3033'. Fill casing and circulate. HSM rig up HES and cmt as follows; Pump 5 bbls pressure test to 5K, pump 20 bbl fresh water, 40 bbl superflush, 20 bbl water then 281 bbls (500sks) 11#/gal lead cmt, 50 bbls (210sks) 14.8# tail cmt. Then displace with 231 bbls mud. Lost returns with app 120 bbls displacement pumped. Final pumping pressure 475#. Bump plug 500 over. Check floats and pull cmt head. Wait 2 hrs do top job with 250 sks G with 2% cal. Let set 2 hrs pump remaining 100 sks. wait 1.5 hrs pump 150 sks. Annulus full and holding |
| 20:00      | 3.00     | 23:00    | 13   | WAIT ON CEMENT      | Rig down HES and wait on cmt. Inspect brakes on rig. One band cracked nearly in two.   |
| 23:00      | 5.00     | 04:00    | 14   | NIPPLE UP B.O.P     | Strip conductor, cut csg and weld on csg head. Parts arrived. repair brakes on rig.  |
| 04:00      | 2.00     | 06:00    | 9    | CUT OFF DRILL LINE  | Slip & cut 120' of drlg line.  |

**5-27D-36 BTR 5/3/2012 06:00 - 5/4/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category         | Com   |
|------------|----------|----------|------|------------------|---|
| 06:00      | 2.50     | 08:30    | 8    | REPAIR RIG       | Finish putting brakes on rig.   |
| 08:30      | 3.50     | 12:00    | 14   | NIPPLE UP B.O.P  | N/U BOP, Flowline etc.  |
| 12:00      | 4.00     | 16:00    | 15   | TEST B.O.P       | Test pipe & blind rams, HCR valve, choke manifold, upper & lower kelly valves, safety valve and dart valve to 5000#. test annular to 2500# and casing to 1500. All held good. |
| 16:00      | 0.50     | 16:30    | 21   | Set Wear Bushing | Set wear bushing.   |
| 16:30      | 3.00     | 19:30    | 20   | DIRECTIONAL WORK | Pickup 8 3/4" Ultrera U 516M and Sperry .14 rpg motor. Pickup & orient 6" dir tools.  |
| 19:30      | 2.00     | 21:30    | 6    | TRIPS            | TIH   |
| 21:30      | 1.50     | 23:00    | 21   | Drill shoe       | Drill out shoe jt.  |
| 23:00      | 0.50     | 23:30    | 2    | DRILL ACTUAL     | Drlg 3037-3055  |
| 23:30      | 1.00     | 00:30    | 22   | FIT              | Spot FIT pill, Perform FIT to 10.5# Eq MW. Held 317# for 15 min.  |
| 00:30      | 1.50     | 02:00    | 2    | DRILL ACTUAL     | Drlg 3055-3162'.  |
| 02:00      | 1.50     | 03:30    | 20   | DIRECTIONAL WORK | MWD not communicating. Work on improving signal.  |
| 03:30      | 1.00     | 04:30    | 5    | COND MUD & CIRC  | Circ & Cond pump pill prep to TOH   |
| 04:30      | 1.00     | 05:30    | 6    | TRIPS            | TOH to work on MWD>   |

**5-27D-36 BTR 5/4/2012 06:00 - 5/5/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category         | Com   |
|------------|----------|----------|------|------------------|---|
| 06:00      | 2.00     | 08:00    | 6    | TRIPS            | TOH for MWD repair.   |
| 08:00      | 0.50     | 08:30    | 7    | LUBRICATE RIG    | Rig service, held BOP drill   |
| 08:30      | 4.50     | 13:00    | 20   | DIRECTIONAL WORK | Repair MWD.   |
| 13:00      | 2.50     | 15:30    | 6    | TRIPS            | TIH and resume drlg   |
| 15:30      | 14.50    | 06:00    | 2    | DRILL ACTUAL     | Drlg and sliding. 3162-3849'. 687' for day. Survey @ 3722' 14.87*159.89 azi. MW 8.4 |

**5-27D-36 BTR 5/5/2012 06:00 - 5/6/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 0.50     | 06:30    | 7    | LUBRICATE RIG | Rig Service.  |
| 06:30      | 23.50    | 06:00    | 2    | DRILL ACTUAL  | Drlg 3849-5065'. 1216' for day, 52 fph, Survey @ 4927 13.99* @ 164.83 azi, MW 8.9#, vis 36. Brought 730 bbls mud in from storage at Advantage. Mudded up @ 4000'. |

**5-27D-36 BTR 5/6/2012 06:00 - 5/7/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 9.00     | 15:00    | 2    | DRILL ACTUAL  | Drlg 5065-5624', 559' in 9 hrs, 62 fph, survey @ 5624 8.37* @ 174.04 azi. MW 8.9# 38 vis        |
| 15:00      | 0.50     | 15:30    | 7    | LUBRICATE RIG | Rlg service, function test BOP.   |
| 15:30      | 14.50    | 06:00    | 2    | DRILL ACTUAL  | Drlg 5624-6416'. 792' in 14.5 hrs 54.6 fph. Survey @ 6322 3.89* @ 214.77 azi. Mud 9.05# 38 vis. |

**5-27D-36 BTR 5/7/2012 06:00 - 5/8/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category     | Com   |
|------------|----------|----------|------|--------------|---|
| 06:00      | 14.00    | 20:00    | 2    | DRILL ACTUAL | Drlg 6416-6797'. 381' for day, Survey @ 6703' 1.44* @ 204.96 azi. Wt 9.1 42 vis. Having trouble getting wt to bit> Plan to make wiper trip. Inspect brakes. Found crack in brake band. Put circ swedge in pipe and circ while waiting on parts. |
| 20:00      | 10.00    | 06:00    | 8    | REPAIR RIG   | Hang blocks and take brakes apart while waiting on parts. Circulating @ 300 GPM while waiting   |

**5-27D-36 BTR 5/8/2012 06:00 - 5/9/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 15.00    | 21:00    | 8    | REPAIR RIG    | Waiting on brake bands. Arrived at 1830 hrs. Install brake bands. Rig running @ 1900 hrs. |
| 21:00      | 0.50     | 21:30    | 7    | LUBRICATE RIG | Rig service, function BOP   |
| 21:30      | 2.00     | 23:30    | 6    | TRIPS         | Make 15 std wiper trip. Trip was smooth.  |
| 23:30      | 6.50     | 06:00    | 2    | DRILL ACTUAL  | Resume drlg to 7000'. Survey @ 6925' 1.61* @ 155.91 azi.. 9.1# 42 vis                     |

**5-27D-36 BTR 5/9/2012 06:00 - 5/10/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 6.00     | 12:00    | 2    | DRILL ACTUAL  | Drlg 7000-7154'. Survey @ 7147 1.84* 220.35 azi MW 9.1 40 vis. Lost all p rate and diff pressure.   |
| 12:00      | 0.50     | 12:30    | 7    | LUBRICATE RIG | Rlg service adjust brakes, Function test BOP  |
| 12:30      | 11.00    | 23:30    | 6    | TRIPS         | Circ bottoms up pump pill, TOH. Bit cored out. Pickup new Varel VTD616X and fresh motor. Orient dir tools. TIH, Tight spot @ 4100'. Kelly up and work thru, Finish TIH. |
| 23:30      | 6.50     | 06:00    | 2    | DRILL ACTUAL  | Resume drlg 7154-7336. Survey @ 7221 1.33* @ 262.27 azi MW 9.2 Vis 40   |

**5-27D-36 BTR 5/10/2012 06:00 - 5/11/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com                           |
|------------|----------|----------|------|---------------|-------------------------------|
| 06:00      | 9.00     | 15:00    | 2    | DRILL ACTUAL  | Steerable Drlg 7336' - 7812'. |
| 15:00      | 0.50     | 15:30    | 7    | LUBRICATE RIG | Rig Service.                  |
| 15:30      | 14.50    | 06:00    | 2    | DRILL ACTUAL  | Steerable Drlg 7812' - 8383'  |

**5-27D-36 BTR 5/11/2012 06:00 - 5/12/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com   |
|------------|----------|----------|------|-----------------|---|
| 06:00      | 10.50    | 16:30    | 2    | DRILL ACTUAL    | Drig 8383'-8890'  |
| 16:30      | 0.50     | 17:00    | 7    | LUBRICATE RIG   | Rig Service   |
| 17:00      | 6.50     | 23:30    | 2    | DRILL ACTUAL    | Drig 8890' - 9200'. TD well @ 9200' @ 23:00 on 5-12-12. |
| 23:30      | 1.50     | 01:00    | 5    | COND MUD & CIRC | C & C M Mud f/ST. Pump pill.                            |
| 01:00      | 2.50     | 03:30    | 6    | TRIPS           | ST 20 stds. Hole tight.                                 |
| 03:30      | 2.50     | 06:00    | 5    | COND MUD & CIRC | C & C f/toh to log.                                     |

**5-27D-36 BTR 5/12/2012 06:00 - 5/13/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com   |
|------------|----------|----------|------|-----------------|---|
| 06:00      | 5.00     | 11:00    | 6    | TRIPS           | TOH f/Logs.   |
| 11:00      | 6.00     | 17:00    | 11   | WIRELINE LOGS   | Log hole. Ran Quad combo, caliper td up to surf csg, Gamma, sonic array, dual lateralog, den & neu porosity 200' - TD. Logger's TD - 9.196'. R/D loggers. |
| 17:00      | 0.50     | 17:30    | 7    | LUBRICATE RIG   | Rig Service   |
| 17:30      | 7.50     | 01:00    | 6    | TRIPS           | TIH   |
| 01:00      | 1.50     | 02:30    | 5    | COND MUD & CIRC | C&C   |
| 02:30      | 3.50     | 06:00    | 6    | TRIPS           | LDDP  |

**5-27D-36 BTR 5/13/2012 06:00 - 5/14/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category                                   | Com  |
|------------|----------|----------|------|--|--|
| 06:00      | 6.50     | 12:30    | 6    | TRIPS                                      | LDDP. Break kelly. L/D BHA. Pull Wear Bushing.   |
| 12:30      | 8.50     | 21:00    | 12   | RUN CASING & CEMENT                        | Run 5 1/2", 17 #, P-110, LT&C Csg as follows: float shoe, 2 jts csg, float collar, 10 jts csg, mj, 22 jts csg, 33 jts, mj, 143 jts(210 total). P/U jt # 211, tag bottom @ 9200', L/D jt #211. P/U LJ, land csg @ 9187'.  |
| 21:00      | 2.00     | 23:00    | 5    | COND MUD & CIRC                            | C & C f/Cmt.   |
| 23:00      | 4.00     | 03:00    | 12   | RUN CASING & CEMENT                        | HSM, Rig up HES to cmt csg. Pressure test pump & Lines to 5K. Pump 10 bbl water spacer, pump 40 bbls superflush 101, pump 10 bbl water spacer, Pump 318 bbls (770 sks) 11# tuned light lead cmt. Pump 156 bbls (615 sks) 13.5 # tail cmt. displace with 211 bbls water with Cla-web and aldacide. Full returns, 40 Bbls cmt to surface. Final lift pressure 2100#. bump plug 500 over. Check floats. held. HSM RD HES. |
| 03:00      | 3.00     | 06:00    | 21   | Set slips, NDBOP, Clean pits. Release rig. | Set Slips w/20k over, Ndbop, Clean Pits. Release rig @ 06:00 on 5-14-12.   |

**5-27D-36 BTR 5/17/2012 06:00 - 5/18/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 06:00      | 2.00     | 08:00    | LOCL | Lock Wellhead & Secure | Well Secured With 11" Night Cap. BackFill Cellar  |
| 08:00      | 2.00     | 10:00    | IWHD | Install Wellhead       | Safety Meeting With Cameron, Check Surface Casing & 5.5" For Pressure, 0 Psi On Both Sides. N/D 11" Night Cap, Cleaned And Dressed Up 5.5" Csg Top, Set And N/U 11" x 7 1/16" 5k Tbg. Head With 2 1/16' x 5k Gate Valves. Tested Hanger Seals To 5000 Psi, Good Test. Secured Well Head With 7" 5K Night Cap. |
| 10:00      | 20.00    | 06:00    | LOCL | Lock Wellhead & Secure | WSI Shut In And Secured. Construction Crew Prepping For Facilities.   |

**5-27D-36 BTR 5/18/2012 06:00 - 5/19/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com   |
|------------|----------|----------|------|--------------------|---|
| 06:00      | 1.00     | 07:00    | GOP  | General Operations | WSI And Secured.  |
| 07:00      | 0.50     | 07:30    | SRIG | Rig Up/Down        | MIRU SLB W/L Crew And Equipment. Hold Safety Meeting. Rig Up Gauge Ring And Logging Tool.   |
| 07:30      | 4.75     | 12:15    | LOGG | Logging            | P/U Junk Basket/Gauge Ring. RIH, Tagged Up At 9,070', FC At 9,098', 28' Of Fill. POOH, P/U CBL Tool, Rih To PBTD, 9,070', Correlating To HES Spectral Density/ Dual Spaced Neutron Dated 05-12-2012. Run Repeat Section From 9,070' - 8,780', Log Up Hole. Showed Good Bond From TD To 5200', 5200' - 4200' Spotty, 4200' - 1250' Fair To Poor. TOC 1250'. Ran With Pressure. Found Short Joints At 8,625 - 8,645, 7,642 - 7,663 And 6,196 - 6,221'. Pooh, RD Equipment, MOL. |



**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com             |
|------------|----------|----------|------|------------------------|-----------------|
| 12:15      | 17.75    | 06:00    | LOCL | Lock Wellhead & Secure | WSI And Secured |

**5-27D-36 BTR 5/23/2012 06:00 - 5/24/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Well Shut in and secured, Construction crews continue to work on and build production facility. Start prepping location for up coming frac. |

**5-27D-36 BTR 5/24/2012 06:00 - 5/25/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Well Shut in and secured, Construction crews continue to work on and build production facility. Start prepping location for up coming frac. |

**5-27D-36 BTR 5/25/2012 06:00 - 5/26/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Well Shut in and secured, Construction crews continue to work on and build production facility. Set flow back tanks and flow back equipment. Start prepping location for up coming frac. |

**5-27D-36 BTR 5/26/2012 06:00 - 5/27/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Well head shut in and secured. Check pressures on well head 0 psi, Removed Night cap, Set & Tested Cameron Frac Mandrel. N/U 5 1/8' BBC Frac tree, finished tying in flow back lines to frac tree. Pressure tested sand trap & Flow back system, Good test Pressure tested Casing to 8500 psi, held pressure test for 30 minutes. Good test. Con't to prep location for Frac, |

**5-27D-36 BTR 5/27/2012 06:00 - 5/28/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Frac Tree Shut in and secured. No Scheduled Completion or Construction Activity. |

**5-27D-36 BTR 5/28/2012 06:00 - 5/29/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Frac tree shut in and secured. Set Storage tanks and built Containment Berms. |

**5-27D-36 BTR 5/29/2012 06:00 - 5/30/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 24.00    | 06:00    | LOCL | Lock Wellhead & Secure | Frac tree shut in and secured. Construction crews hooked up electrical panel & Con't to insulate production equipment. |

**5-27D-36 BTR 5/31/2012 06:00 - 5/20/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com          |
|------------|----------|----------|------|--------------------|--------------|
| 06:00      | 24.00    | 06:00    | GOP  | General Operations | No Activity. |

|  |  |  |
|--|--|--|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |  | <b>FORM 9</b>  |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |  | <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>20G0005608 |
| <b>1. TYPE OF WELL</b><br>Oil Well   |  | <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>                 |
| <b>2. NAME OF OPERATOR:</b><br>BILL BARRETT CORP   |  | <b>7. UNIT or CA AGREEMENT NAME:</b>                         |
| <b>3. ADDRESS OF OPERATOR:</b><br>1099 18th Street Ste 2300 , Denver, CO, 80202  |  | <b>8. WELL NAME and NUMBER:</b><br>5-27D-36                  |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>1252 FNL 0660 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U  |  | <b>9. API NUMBER:</b><br>43013509170000                      |
| <b>PHONE NUMBER:</b><br>303 312-8164 Ext   |  | <b>9. FIELD and POOL or WILDCAT:</b><br>CEDAR RIM            |
| <b>COUNTY:</b><br>DUCHESNE   |  | <b>STATE:</b><br>UTAH  |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION  |   |  |   |
|--|---|---|--|---|
| <input type="checkbox"/> NOTICE OF INTENT<br>Approximate date work will start:                       | <input type="checkbox"/> ACIDIZE<br><br><input type="checkbox"/> CHANGE TO PREVIOUS PLANS<br><br><input type="checkbox"/> CHANGE WELL STATUS<br><br><input type="checkbox"/> DEEPEN<br><br><input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> ALTER CASING<br><br><input type="checkbox"/> CHANGE TUBING<br><br><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS<br><br><input type="checkbox"/> FRACTURE TREAT<br><br><input type="checkbox"/> PLUG AND ABANDON<br><br><input type="checkbox"/> RECLAMATION OF WELL SITE<br><br><input type="checkbox"/> SIDETRACK TO REPAIR WELL<br><br><input type="checkbox"/> VENT OR FLARE<br><br><input type="checkbox"/> SI TA STATUS EXTENSION<br><br><input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR<br><br><input type="checkbox"/> CHANGE WELL NAME<br><br><input type="checkbox"/> CONVERT WELL TYPE<br><br><input type="checkbox"/> NEW CONSTRUCTION<br><br><input type="checkbox"/> PLUG BACK<br><br><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION<br><br><input type="checkbox"/> TEMPORARY ABANDON<br><br><input type="checkbox"/> WATER DISPOSAL<br><br><input type="checkbox"/> APD EXTENSION | OTHER: <input style="width: 100px;" type="text"/> |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT<br>Date of Work Completion:<br><b>6/9/2012</b> | <input type="checkbox"/> REPERFORATE CURRENT FORMATION<br><br><input type="checkbox"/> TUBING REPAIR<br><br><input type="checkbox"/> WATER SHUTOFF<br><br><input type="checkbox"/> WILDCAT WELL DETERMINATION                       | <input checked="" type="checkbox"/> PRODUCTION START OR RESUME  |  |   |
| <input type="checkbox"/> SPUD REPORT<br>Date of Spud:  |   |   |  |   |
| <input type="checkbox"/> DRILLING REPORT<br>Report Date:   |   |   |  |   |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

This well had first gas sales on 6/7/2012 and first oil sales on 6/9/2012.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 June 12, 2012

|  |                                     |                                       |
|--|-------------------------------------|---------------------------------------|
| <b>NAME (PLEASE PRINT)</b><br>Venessa Langmacher | <b>PHONE NUMBER</b><br>303 312-8172 | <b>TITLE</b><br>Senior Permit Analyst |
| <b>SIGNATURE</b><br>N/A                          | <b>DATE</b><br>6/11/2012            |                                       |

|  |  |  |
|--|--|--|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |  | <b>FORM 9</b>  |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |  | <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>20G0005608 |
| <b>1. TYPE OF WELL</b><br>Oil Well   |  | <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>                 |
| <b>2. NAME OF OPERATOR:</b><br>BILL BARRETT CORP   |  | <b>7. UNIT or CA AGREEMENT NAME:</b>                         |
| <b>3. ADDRESS OF OPERATOR:</b><br>1099 18th Street Ste 2300 , Denver, CO, 80202  |  | <b>8. WELL NAME and NUMBER:</b><br>5-27D-36                  |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>1252 FNL 0660 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U  |  | <b>9. API NUMBER:</b><br>43013509170000                      |
| <b>PHONE NUMBER:</b><br>303 312-8164 Ext   |  | <b>9. FIELD and POOL or WILDCAT:</b><br>CEDAR RIM            |
| <b>COUNTY:</b><br>DUCHESNE   |  | <b>STATE:</b><br>UTAH  |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION   | TYPE OF ACTION   |   |   |  |
|--|--|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT<br>Approximate date work will start:   | <input type="checkbox"/> ACIDIZE                       | <input type="checkbox"/> ALTER CASING                   | <input type="checkbox"/> CASING REPAIR                  |  |
| <input type="checkbox"/> SUBSEQUENT REPORT<br>Date of Work Completion:           | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS      | <input type="checkbox"/> CHANGE TUBING                  | <input type="checkbox"/> CHANGE WELL NAME               |  |
| <input type="checkbox"/> SPUD REPORT<br>Date of Spud:                            | <input type="checkbox"/> CHANGE WELL STATUS            | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE              |  |
| <input checked="" type="checkbox"/> DRILLING REPORT<br>Report Date:<br>6/30/2012 | <input type="checkbox"/> DEEPEN                        | <input type="checkbox"/> FRACTURE TREAT                 | <input type="checkbox"/> NEW CONSTRUCTION               |  |
|  | <input type="checkbox"/> OPERATOR CHANGE               | <input type="checkbox"/> PLUG AND ABANDON               | <input type="checkbox"/> PLUG BACK                      |  |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME    | <input type="checkbox"/> RECLAMATION OF WELL SITE       | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION |  |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       | <input type="checkbox"/> TEMPORARY ABANDON              |  |
|  | <input type="checkbox"/> TUBING REPAIR                 | <input type="checkbox"/> VENT OR FLARE                  | <input type="checkbox"/> WATER DISPOSAL                 |  |
|  | <input type="checkbox"/> WATER SHUTOFF                 | <input type="checkbox"/> SI TA STATUS EXTENSION         | <input type="checkbox"/> APD EXTENSION                  |  |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION    | <input type="checkbox"/> OTHER                          | OTHER: <input style="width: 100px;" type="text"/>       |  |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

June 2012 monthly drilling activity report is attached.

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 July 05, 2012

|  |                                     |                                |
|--|-------------------------------------|--------------------------------|
| <b>NAME (PLEASE PRINT)</b><br>Megan Finnegan | <b>PHONE NUMBER</b><br>303 299-9949 | <b>TITLE</b><br>Permit Analyst |
| <b>SIGNATURE</b><br>N/A                      | <b>DATE</b><br>7/3/2012             |                                |

**5-27D-37 BTR 6/12/2012 06:00 - 6/13/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category         | Com  |
|------------|----------|----------|------|------------------|--|
| 06:00      | 12.00    | 18:00    | 1    | RIGUP & TEARDOWN | Set sub, backyard, derrick on floor. Checking DP, 80%. Eta p/u dir tools & spud, late evening. |
| 18:00      | 11.00    | 05:00    | 1    | RIGUP & TEARDOWN | Wait on daylight. Weld on rig,   |
| 05:00      | 1.00     | 06:00    | 1    | RIGUP & TEARDOWN | RURT w/daylight crew.  |

**5-27D-37 BTR 6/13/2012 06:00 - 6/14/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category         | Com   |
|------------|----------|----------|------|------------------|---|
| 06:00      | 15.00    | 21:00    | 1    | RIGUP & TEARDOWN | RURT. Derrick raised @ 09:00. R/U floor, riser, fill mud pits, R/U bulk LCM (20% cottonseed hulls w/sawdust). Rig on daywork @ 21:00. |
| 21:00      | 1.50     | 22:30    | 14   | NIPPLE UP B.O.P  | N/U Conductor.  |
| 22:30      | 5.00     | 03:30    | 21   | OPEN             | Rack and strap BHA  |
| 03:30      | 1.00     | 04:30    | 2    | DRILL ACTUAL     | P/U bit, mm, scribe. Drill 80' - 126'. Spud @ 03:30.  |
| 04:30      | 1.50     | 06:00    | 20   | DIRECTIONAL WORK | Install Dir tools.  |

**5-27D-37 BTR 6/14/2012 06:00 - 6/15/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com                           |
|------------|----------|----------|------|---------------|-------------------------------|
| 06:00      | 11.00    | 17:00    | 2    | DRILL ACTUAL  | P/U BHA and drill 126' - 594' |
| 17:00      | 0.50     | 17:30    | 7    | LUBRICATE RIG | Rig service                   |
| 17:30      | 10.00    | 03:30    | 2    | DRILL ACTUAL  | Drill 594'-1005'              |
| 03:30      | 2.50     | 06:00    | 6    | TRIPS         | TOOH f/ bit                   |

**5-27D-37 BTR 6/15/2012 06:00 - 6/16/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category | Com |
|------------|----------|----------|------|----------|-----|
|            |          |          |      |          |     |

**5-27D-37 BTR 6/16/2012 06:00 - 6/17/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category         | Com                   |
|------------|----------|----------|------|------------------|-----------------------|
| 06:00      | 10.00    | 16:00    | 2    | DRILL ACTUAL     | Drill 1850'- 2262'    |
| 16:00      | 0.50     | 16:30    | 7    | LUBRICATE RIG    | Rig Service           |
| 16:30      | 6.50     | 23:00    | 2    | DRILL ACTUAL     | Drilling 2262'- 2459' |
| 23:00      | 0.50     | 23:30    | 5    | COND MUD & CIRC  | Circ. f/ trip         |
| 23:30      | 3.00     | 02:30    | 6    | TRIPS            | TOOH change out bit   |
| 02:30      | 1.50     | 04:00    | 20   | DIRECTIONAL WORK | Change MWD            |
| 04:00      | 2.00     | 06:00    | 6    | TRIPS            | TIH                   |

**5-27D-37 BTR 6/17/2012 06:00 - 6/18/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com  |
|------------|----------|----------|------|-----------------|--|
| 06:00      | 1.00     | 07:00    | 6    | TRIPS           | Finish TIH   |
| 07:00      | 5.50     | 12:30    | 2    | DRILL ACTUAL    | DRILLING 2459'-2579  |
| 12:30      | 4.00     | 16:30    | 5    | COND MUD & CIRC | Lost total returns @2579'. Mix and pump LCM, returns back, lost again mix and pump LCM |
| 16:30      | 0.50     | 17:00    | 6    | TRIPS           | Pull 5 stands too 2103'  |
| 17:00      | 10.00    | 03:00    | 5    | COND MUD & CIRC | Mix and pump lcm sweeps stage in hole  |
| 03:00      | 3.00     | 06:00    | 2    | DRILL ACTUAL    | Drilling 2579'-2643'   |

**5-27D-37 BTR 6/18/2012 06:00 - 6/19/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com                   |
|------------|----------|----------|------|-----------------|-----------------------|
| 06:00      | 10.00    | 16:00    | 2    | DRILL ACTUAL    | Drilling 2643'-2833'  |
| 16:00      | 0.50     | 16:30    | 7    | LUBRICATE RIG   | Rig Service           |
| 16:30      | 7.00     | 23:30    | 2    | DRILL ACTUAL    | Drilling 2833'-3012'  |
| 23:30      | 1.00     | 00:30    | 5    | COND MUD & CIRC | Circ sweep @ TD       |
| 00:30      | 2.50     | 03:00    | 6    | TRIPS           | Wiper trip to collars |
| 03:00      | 1.00     | 04:00    | 5    | COND MUD & CIRC | Circ sweep            |
| 04:00      | 2.00     | 06:00    | 6    | TRIPS           | TOOH to run casing    |

**5-27D-37 BTR 6/19/2012 06:00 - 6/20/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category            | Com  |
|------------|----------|----------|------|---------------------|--|
| 06:00      | 1.50     | 07:30    | 6    | TRIPS               | Rig up LD machine & LD 8" DC,s   |
| 07:30      | 1.00     | 08:30    | 20   | DIRECTIONAL WORK    | LD bit,MM&dirc tools   |
| 08:30      | 8.00     | 16:30    | 12   | RUN CASING & CEMENT | rig up casing crew run 9 5/8 casing stage in   |
| 16:30      | 0.50     | 17:00    | 5    | COND MUD & CIRC     | Circ. f/ cement Lost returns   |
| 17:00      | 7.00     | 00:00    | 5    | COND MUD & CIRC     | Mix and pump 30ppg LCM sweeps  |
| 00:00      | 5.00     | 05:00    | 12   | RUN CASING & CEMENT | pressure test lines ,pump 20 bbl fresh water pump 40 bbl super flush,pump 20 bbl fresh water,pump 500 sks of lead cement@ 11#/gal 3.16 yield,pump 235 sks of tail cement@ 14.8#/gal 1.33 yield drop plug,bumped plug @04:50 60psi on lines final 180 psi check floats ,floats held |
| 05:00      | 1.00     | 06:00    | 12   | RUN CASING & CEMENT | W/O Cement   |

**5-27D-37 BTR 6/20/2012 06:00 - 6/21/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category            | Com                          |
|------------|----------|----------|------|---------------------|------------------------------|
| 06:00      | 2.50     | 08:30    | 13   | WAIT ON CEMENT      | WOC                          |
| 08:30      | 1.50     | 10:00    | 12   | RUN CASING & CEMENT | Top Job #1 175 sks@ 15.8ppg  |
| 10:00      | 1.00     | 11:00    | 13   | WAIT ON CEMENT      | WOC                          |
| 11:00      | 1.00     | 12:00    | 12   | RUN CASING & CEMENT | Top Job #2 175 sks @ 15.8ppg |
| 12:00      | 2.00     | 14:00    | 13   | WAIT ON CEMENT      | WOC                          |
| 14:00      | 1.50     | 15:30    | 12   | RUN CASING & CEMENT | Top Job #3 350 sks # 15.8ppg |
| 15:30      | 2.00     | 17:30    | 13   | WAIT ON CEMENT      | WOC cement from vernal       |
| 17:30      | 0.50     | 18:00    | 7    | LUBRICATE RIG       | Rig service                  |
| 18:00      | 3.00     | 21:00    | 13   | WAIT ON CEMENT      | WOC cement from Vernal       |
| 21:00      | 1.00     | 22:00    | 12   | RUN CASING & CEMENT | Top Job #4 175 sks @ 15.8ppg |
| 22:00      | 2.00     | 00:00    | 13   | WAIT ON CEMENT      | WOC                          |
| 00:00      | 1.00     | 01:00    | 12   | RUN CASING & CEMENT | Top Job #5 175 sks @ 15.8ppg |
| 01:00      | 5.00     | 06:00    | 13   | WAIT ON CEMENT      | WOC cement from vernal       |

**5-27D-37 BTR 6/21/2012 06:00 - 6/22/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category            | Com  |
|------------|----------|----------|------|---------------------|--|
| 06:00      | 1.00     | 07:00    | 13   | WAIT ON CEMENT      | WOC  |
| 07:00      | 1.50     | 08:30    | 12   | RUN CASING & CEMENT | Top Job #6 150 sks 15.8ppg,cement to surface   |
| 08:30      | 2.50     | 11:00    | 13   | WAIT ON CEMENT      | WOC  |
| 11:00      | 3.50     | 14:30    | 14   | NIPPLE UP B.O.P     | Cut off casing & weld on wellhead  |
| 14:30      | 4.00     | 18:30    | 14   | NIPPLE UP B.O.P     | Nipple Up BOP  |
| 18:30      | 7.50     | 02:00    | 15   | TEST B.O.P          | Test BOP,Annular 2500,pipe rams,blind rams kill line,upper&lower kelly valves,safety valves & choke manifold to 5000 psi |
| 02:00      | 4.00     | 06:00    | 6    | TRIPS               | Make up bit,MM,Dir. tools/orient MWD,trip in   |

**5-27D-37 BTR 6/22/2012 06:00 - 6/23/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category       | Com  |
|------------|----------|----------|------|----------------|--|
| 06:00      | 5.00     | 11:00    | 21   | OPEN           | Drill out from sfc csg to 30. TOH 32'. Spot hi vis hi LCM pill. Perform FIT. to 315# 10.5 EMW. Failed  |
| 11:00      | 3.00     | 14:00    | 6    | TRIPS          | TOH, Ordered CCR and cmt to sqz. Wait on CCR,  |
| 14:00      | 5.00     | 19:00    | 21   | OPEN           | P/U CCR and RIH. Set CCR @ 2768'.  |
| 19:00      | 3.50     | 22:30    | 18   | SQUEEZE CEMENT | Rig up Pro Petro cmtr's. Est rate of 2 bpm@800#. Pump 10 bbl spacer. Mix and pump 400 sks Class G neat cmt with 2% Cal in last 200 sks. Lost pressure continue mixing @ 2.5 bpm. Displace with fresh water. Caught up with cmt with 27 bbls displacement pumped. Drop rate to .75 bpm. Pressure slowly climbing. 600# at 37 bbl pumped. Shut down. pressure dropped to 125#. Wait 15 min. Pump .25 bbl pressured up to 600#. Dropping slowly. Wait 15 min pump .25 bbl. Pressured to 600# and holding. Sting out. Reverse out 2 bbl cmt from drillpipe. Rlg down cmtr's. |
| 22:30      | 2.50     | 01:00    | 6    | TRIPS          | TOH, L/D tools.  |
| 01:00      | 3.00     | 04:00    | 6    | TRIPS          | P/U Smith MDI516, and fresh MM. Orient dir tools and TIH, Tagged @ 2763'.  |
| 04:00      | 2.00     | 06:00    | 13   | WAIT ON CEMENT | Wait on cmt.   |

**5-27D-37 BTR 6/23/2012 06:00 - 6/24/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com   |
|------------|----------|----------|------|-----------------|---|
| 06:00      | 10.00    | 16:00    | 21   | Drrill out sqz  | Drill out CCR, drill out sqz and drill to 3052. Spot HI vis Hi LCM pill. Perform FIT to 10.5# EMW. Hold for 10 min. Test successful |
| 16:00      | 0.50     | 16:30    | 7    | LUBRICATE RIG   | Rlg service, funtion test BOP.  |
| 16:30      | 7.50     | 00:00    | 2    |                 | Drig 3052-3559'. Fighting losses 3200 on close in pits and mud up @ 3350'. Carry 40 vis and 10% LCM.                                |
| 00:00      | 2.00     | 02:00    | 5    | COND MUD & CIRC | Lost returns, Build volume and increase LCM content.  |
| 02:00      | 4.00     | 06:00    | 2    |                 | Drig 3559-3670'. Survey @ 3531 4.35* @ 95.7 azi. MW 8.5 #/gal 35 vis 10% LCM. Losses for day 1000 bbls                              |

**5-27D-37 BTR 6/24/2012 06:00 - 6/25/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category        | Com  |
|------------|----------|----------|------|-----------------|--|
| 06:00      | 8.00     | 14:00    | 2    | DRILL ACTUAL    | Drig 3670-4035'. Severe losses @ 3900'. Drill blind while mixing & pumping LCM. Survey @ 6.97* @ 113.23 azi. |
| 14:00      | 6.00     | 20:00    | 5    | COND MUD & CIRC | Build volume raise LCM content to 25%, pump Hi LCM sweeps. Regained circulation. Lost app 1650 bbls.         |
| 20:00      | 0.50     | 20:30    | 7    | LUBRICATE RIG   | Rig service, Function BOP.   |
| 20:30      | 6.00     | 02:30    | 2    | DRILL ACTUAL    | Drig 4035-4194'. Torqing up and stalling motor. Survey 6.45* @ 115.94  |
| 02:30      | 3.50     | 06:00    | 6    | TRIPS           | Mix and pump pill. TOH. Bit under guage.   |

**5-27D-37 BTR 6/25/2012 06:00 - 6/26/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 5.00     | 11:00    | 6    | TRIPS         | Chande out MM and pickup new HTC 506FX. Orient dir tools, TIH. Hit tight spot @ 3550'.                  |
| 11:00      | 2.50     | 13:30    | 3    | REAMING       | Pickup kelly, Wash and ream to 4194'.   |
| 13:30      | 4.00     | 17:30    | 2    | DRILL ACTUAL  | Drig 4194-4328'. Survey @ 4293 7.88* @ 113.76 azi Starting to lose mud again.                           |
| 17:30      | 0.50     | 18:00    | 7    | LUBRICATE RIG | Rlg service. Function test BOP.   |
| 18:00      | 12.00    | 06:00    | 2    | DRILL ACTUAL  | Drig 4328-4924'. 596' in 12 hrs 49.6 fph, MW 8.86#/gal 43 vis 30% LCM, Survey 4801', 7.17* @ 114.7 azi. |

**5-27D-37 BTR 6/26/2012 06:00 - 6/27/2012 06:00**

|                           |                      |                    |                                |                         |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|
| API/UWI<br>43013508470000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>DRILLING | Total Depth (ftKB)<br>9,291.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|-------------------------|-------------------------------|---|



**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 11.50    | 17:30    | 2    | DRILL ACTUAL  | Drlg 4924-5389'. 465' in 11.5 hrs 40.4 fph. MW 8.7#/gal. Vis 42 LCM 28%, Survey @ 5371 7.13* @ 123.26 azi |
| 17:30      | 0.50     | 18:00    | 7    | LUBRICATE RIG | Rig service, function BOP   |
| 18:00      | 12.00    | 06:00    | 2    | DRILL ACTUAL  | Drlg 5389-5939'. 550' in 12 hrs 45.8 fph MW 8.9#/gal 48 vis 25% LCM. Survey @ 5752 6.46* @ 136.63 azi.    |

**5-27D-37 BTR 6/27/2012 06:00 - 6/28/2012 06:00**

| API/UWI        | State/Province | County   | Field Name       | Well Status | Total Depth (ftKB) | Primary Job Type      |
|----------------|----------------|----------|------------------|-------------|--------------------|-----------------------|
| 43013508470000 | UT             | Duchesne | Black Tail Ridge | DRILLING    | 9,291.0            | Drilling & Completion |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com  |
|------------|----------|----------|------|---------------|--|
| 06:00      | 4.50     | 10:30    | 2    | DRILL ACTUAL  | Drlg 5939-6161' 222' in 4.5 hrs 49.3 fph. Survey 6133', 5.71* @ 154.99 azi. MW 9 #/gal 40 vis, 22% LCM   |
| 10:30      | 0.50     | 11:00    | 7    | LUBRICATE RIG | Rig Service, Function test BOP.  |
| 11:00      | 19.00    | 06:00    | 2    | DRILL ACTUAL  | Drlg 6191-6701'. 540' in 19 hrs, 28.5 fph. Survey 6577' 3.25* @ 187.99 azi. MW 9.15 #/gal 36 vis 18% LCM |

**5-27D-37 BTR 6/28/2012 06:00 - 6/29/2012 06:00**

| API/UWI        | State/Province | County   | Field Name       | Well Status | Total Depth (ftKB) | Primary Job Type      |
|----------------|----------------|----------|------------------|-------------|--------------------|-----------------------|
| 43013508470000 | UT             | Duchesne | Black Tail Ridge | DRILLING    | 9,291.0            | Drilling & Completion |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category      | Com   |
|------------|----------|----------|------|---------------|---|
| 06:00      | 4.00     | 10:00    | 2    | DRILL ACTUAL  | Drlg 6701-6796'. 95' in 4 hrs. Survey @ 6767' 2.98* @ 190.18 azi, MW 9.0 42 vis 320% LCM.   |
| 10:00      | 0.50     | 10:30    | 7    | LUBRICATE RIG | Rig service, Function test BOP  |
| 10:30      | 19.50    | 06:00    | 2    | DRILL ACTUAL  | Drlg 6796-7215'. 419' in 19.5 hrs 21.5 fph. Survey @ 7085 3.1* @ 183.95 azi. MW 9.2+#/gal 40 vis 20% LCM, DAP 4.3#/bbl. Sliding 2 out of 3 jts trying to drop angle |

**5-27D-36 BTR 6/1/2012 06:00 - 6/2/2012 06:00**

| API/UWI        | State/Province | County   | Field Name       | Well Status | Total Depth (ftKB) | Primary Job Type      |
|----------------|----------------|----------|------------------|-------------|--------------------|-----------------------|
| 43013509170000 | UT             | Duchesne | Black Tail Ridge | COMPLETION  | 9,200.0            | Drilling & Completion |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com  |
|------------|----------|----------|------|--------------------|--|
| 06:00      | 24.00    | 06:00    | GOP  | General Operations | ReHeat Frac Line.<br>HES Spot Mountain Movers. |

**5-27D-36 BTR 6/2/2012 06:00 - 6/3/2012 06:00**

| API/UWI        | State/Province | County   | Field Name       | Well Status | Total Depth (ftKB) | Primary Job Type      |
|----------------|----------------|----------|------------------|-------------|--------------------|-----------------------|
| 43013509170000 | UT             | Duchesne | Black Tail Ridge | COMPLETION  | 9,200.0            | Drilling & Completion |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 2.00     | 08:00    | LOCL | Lock Wellhead & Secure | WSI And Secured. 0 Psi. On Well.   |
| 08:00      | 1.25     | 09:15    | SRIG | Rig Up/Down            | HES And SLB Arrive On Location. Hold Safety Meetings. Start Rigging Up.  |
| 09:15      | 0.75     | 10:00    | PTST | Pressure Test          | Test Lubricator To 4200#. Arm Gun.   |
| 10:00      | 1.25     | 11:15    | PFRT | Perforating            | RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf, .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012. Found And Correlated To Marker Joint At 8,625 - 8,645'. Drop Down To Depth, Perforate Stage 1 CR-5/CR-4A/CR-4 Zone As Follows: 8717 - 18, 8739 - 40, 8759 - 60, 8777 - 78, 8805 - 06, 8821 - 22, 8845 - 46, 8859 - 60, 8887 - 88, 8909 - 10, 8933 - 34, 8953 - 54, 8961 - 62, 8983 - 84, 9000 - 01. 45 Holes. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured. |
| 11:15      | 2.00     | 13:15    | SRIG | Rig Up/Down            | HES Finish Rigging Up  |
| 13:15      | 16.75    | 06:00    | LOCL | Lock Wellhead & Secure | WSI And Secured. SDFD.   |

**5-27D-36 BTR 6/3/2012 06:00 - 6/4/2012 06:00**

| API/UWI        | State/Province | County   | Field Name       | Well Status | Total Depth (ftKB) | Primary Job Type      |
|----------------|----------------|----------|------------------|-------------|--------------------|-----------------------|
| 43013509170000 | UT             | Duchesne | Black Tail Ridge | COMPLETION  | 9,200.0            | Drilling & Completion |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com  |
|------------|----------|----------|------|--------------------|--|
| 06:00      | 0.42     | 06:25    | GOP  | General Operations | HES Crew On Location At 0500 Hrs., Prime Chemical And Fluid Pumps, Pressure Test To 9000 Psi., Hold Safety Meeting. Ran QC On Fluid, Looks Good. |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com  |
|------------|----------|----------|------|--------------------|--|
| 06:25      | 1.50     | 07:55    | FRAC | Frac. Job          | <p>Frac Stage 1. Fluid System: Hybor G 16<br/> Open Well, 0# lcp.<br/> BrokeDown At 2684 Psi. And 10.7 Bpm.<br/> Pump 3900 Gals. 15% Acid With 90 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br/> ShutDown For 15 Min., Let Balls Fall,<br/> Get Stabilized Inj. Rate At 3440 Psi. And 67.6 Bpm. Get Isip, 2484 Psi., .72 FG., 37/45<br/> Holes Open.<br/> Pump FR Pad With 3% KCL, Start XLink, Stage Into Pad Stage, Then To 2#, 3#, 3.5#,<br/> And 4# 20/40 CRC Stages.<br/> Isdp, 3007 Psi., .78 FG.<br/> Total 20/40 CRC: 157,100#<br/> Total 3% KCL: 68,018 Gals.. 1,619 Bbls.. Total Produced Water: 70,756 Gals.. 1,685<br/> Bbls..<br/> BWTR: 3513 Bbls.<br/> Max Rate: 72.9 Bpm<br/> Avg. Rate: 69.4 Bpm<br/> Max. Pressure: 4,455 Psi.<br/> Avg. Pressure: 3,968 Psi.</p>    |
| 07:55      | 0.25     | 08:10    | CTUW | W/L Operation      | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equaize And Open.   |
| 08:10      | 1.50     | 09:40    | PFRT | Perforating        | <p>RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br/> .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br/> Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br/> Found And Correlated To Marker Joint At 8,625 - 8,645'. Drop Down To Depth, Set CBP<br/> At 8,700'. 2450 Psi. On Well. Perforate Stage 2 CR-4/CR-3 Zone As Follows: 8439 - 40,<br/> 8467 - 68,<br/> 8477 - 78, 8497 - 98, 8513 - 14, 8531 - 32, 8547 - 48, 8576 - 78, 8589 - 90, 8613 - 14,<br/> 8645 - 46, 8663 - 64, 8679 - 80. 2250 Psi. On Well. 45 Holes. POOH. LayDown Gun,<br/> Verify All Shots Fired, WSI And Secured.</p>   |
| 09:40      | 0.08     | 09:45    | GOP  | General Operations | Turn Well Over To HES. Pressure Test To 8500 Psi., Equalize To Well Pressure.  |
| 09:45      | 1.42     | 11:10    | FRAC | Frac. Job          | <p>Frac Stage 2. Fluid System: Hybor G 16<br/> Open Well, 1919# lcp.<br/> BrokeDown At 5290 Psi. And 10.4 Bpm.<br/> Pump 3900 Gals. 15% Acid With 84 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br/> ShutDown For 15 Min., Let Balls Fall,<br/> Get Stabilized Inj. Rate At 4159 Psi. And 72.3 Bpm. Get Isip, 2650 Psi., .75 FG., 41/42<br/> Holes Open.<br/> Pump FR Pad With 3% KCL, Start XLink, Stage Into Pad Stage, Then To 2#, 3#, 3.5#,<br/> And 4# 20/40 CRC Stages.<br/> Isdp, 3439 Psi., .84 FG.<br/> Total 20/40 CRC: 165,600#<br/> Total 3% KCL: 69,031 Gals.. 1,644 Bbls.. Total Produced Water: 71,681 Gals.. 1,707<br/> Bbls..<br/> BWTR: 3549 Bbls.<br/> Max Rate: 72.1 Bpm<br/> Avg. Rate: 70.6 Bpm<br/> Max. Pressure: 4,522 Psi.<br/> Avg. Pressure: 4,140 Psi.</p> |
| 11:10      | 0.25     | 11:25    | CTUW | W/L Operation      | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equaize And Open.   |
| 11:25      | 1.25     | 12:40    | PFRT | Perforating        | <p>RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br/> .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br/> Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br/> Found And Correlated To Marker Joint At 8,625 - 8,645'. Drop Down To Depth, Set CBP<br/> At 8,432'. 2600 Psi. On Well. Perforate Stage 3 CR-3 Zone As Follows: 8101 - 02, 8141<br/> - 42, 8159 - 60, 8197 - 98, 8223 - 24, 8245 - 46, 8271 - 72, 8287 - 88, 8305 - 06,<br/> 8325 - 26, 8350 - 51, 8374 - 75, 8393 - 94, 8403 - 04, 8417 - 18. 200 Psi. On Well. 45<br/> Holes. POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.</p>  |
| 12:40      | 0.17     | 12:50    | GOP  | General Operations | Turn Well Over To HES. Pressure Test To 8500 Psi., Equalize To Well Pressure.  |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 12:50      | 1.33     | 14:10    | FRAC | Frac. Job              | Frac Stage 3. Fluid System: Hybor G 16<br>Open Well, 16# lcp.<br>BrokeDown At 3524 Psi. And 9.9 Bpm.<br>Pump 3900 Gals. 15% Acid With 90 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br>ShutDown For 15 Min., Let Balls Fall,<br>Get Stabilized Inj. Rate At 4202 Psi. And 70.3 Bpm. Get Isip, 2087 Psi., .69 FG., 32/45<br>Holes Open.<br>Pump FR Pad With 3% KCL, Start XLink, Stage Into Pad Stage, Then To 2#, 3#, 3.5#,<br>And 4# 20/40 White Stages.<br>Isdp, 2796 Psi., .78 FG.<br>Total 20/40 White: 156,600#<br>Total 3% KCL: 67,171 Gals.. 1,599 Bbls.. Total Produced Water: 65,935 Gals.. 1,570<br>Bbls..<br>BWTR: 3329 Bbls.<br>Max Rate: 72.3 Bpm<br>Avg. Rate: 69.6 Bpm<br>Max. Pressure: 6,590 Psi.<br>Avg. Pressure: 4,493 Psi. |
| 14:10      | 0.33     | 14:30    | CTUW | W/L Operation          | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equilaize And Open.   |
| 14:30      | 1.17     | 15:40    | PFRT | Perforating            | RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br>.36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br>Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br>Found And Correlated To Marker Joint At 7,642 - 7,663'. Drop Down To Depth, Set CBP<br>At 8,090'. 1200 Psi. On Well. Perforate Stage 4 CR-2/Wasatch Zone As Follows: 7817 -<br>18, 7829 - 30,<br>7853 - 54, 7866 - 67, 7889 - 90, 7920 - 21, 7941 - 42, 7961 - 62, 7976 - 77, 7983 - 84,<br>8001 - 02, 8029 - 30, 8041 - 42, 8057 - 58, 8069 - 70. 0 Psi. On Well. 45 Holes. POOH.<br>LayDown Gun, Verify All Shots Fired, WSI And Secured.  |
| 15:40      | 0.17     | 15:50    | GOP  | General Operations     | Turn Well Over To HES. Pressure Test To 8500 Psi., Equalize To Well Pressure.  |
| 15:50      | 1.33     | 17:10    | FRAC | Frac. Job              | Frac Stage 4. Fluid System: Hybor G 16<br>Open Well, 0# lcp.<br>BrokeDown At 2936 Psi. And 14.1 Bpm.<br>Pump 3900 Gals. 15% Acid With 90 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br>ShutDown For 15 Min., Let Balls Fall,<br>Get Stabilized Inj. Rate At 3581 Psi. And 70.7 Bpm. Get Isip, 2100 Psi., .71 FG., 41/45<br>Holes Open.<br>Pump FR Pad With 3% KCL, Start XLink, Stage Into Pad Stage, Then To 2#, 3#, 3.5#,<br>And 4# 20/40 White Stages.<br>Isdp, 2513 Psi., .76 FG.<br>Total 20/40 White: 160,000#<br>Total 3% KCL: 68,241 Gals.. 1,625 Bbls.. Total Produced Water: 68,383 Gals.. 1,628<br>Bbls..<br>BWTR: 3476 Bbls.<br>Max Rate: 70.8 Bpm<br>Avg. Rate: 70.6 Bpm<br>Max. Pressure: 3,733 Psi.<br>Avg. Pressure: 3,455 Psi. |
| 17:10      | 0.25     | 17:25    | CTUW | W/L Operation          | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equilaize And Open.   |
| 17:25      | 1.25     | 18:40    | PFRT | Perforating            | RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br>.36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br>Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br>Found And Correlated To Marker Joint At 7,642 - 7,663'. Drop Down To Depth, Set CBP<br>At 7,810'. 1800 Psi. On Well. Perforate Stage 5 CR-1 Zone As Follows: 7563 - 64, 7587<br>- 88, 7611 - 12, 7633 - 34, 7655 - 56, 7672 - 73, 7690 - 91, 7705 - 06, 7719 - 20,<br>7739 - 40, 7760 - 61, 7775 - 76, 7790 - 91. 1600 Psi. On Well. 39 Holes. POOH.<br>LayDown Gun, Verify All Shots Fired, WSI And Secured.  |
| 18:40      | 0.33     | 19:00    | GOP  | General Operations     | ShutDown And Secure Equipment.   |
| 19:00      | 11.00    | 06:00    | LOCL | Lock Wellhead & Secure | WSI And Secured. SDFD.   |

**5-27D-36 BTR 6/4/2012 06:00 - 6/5/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com   |
|------------|----------|----------|------|--------------------|---|
| 06:00      | 0.34     | 06:20    | GOP  | General Operations | HES Crew On Location At 0500 Hrs., Prime Chemical And Fluid Pumps, Pressure Test<br>To 9000 Psi., Hold Safety Meeting. Ran QC On Fluid, Looks Good. |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category           | Com   |
|------------|----------|----------|------|--------------------|---|
| 06:20      | 1.50     | 07:50    | FRAC | Frac. Job          | <p>Frac Stage 5. Fluid System: Hybor G 16<br/> Open Well, 0# lcp.<br/> BrokeDown At 2124 Psi. And 10.0 Bpm.<br/> Pump 3900 Gals. 15% Acid With 78 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br/> ShutDown For 15 Min., Let Balls Fall,<br/> Get Stabilized Inj. Rate At 3491 Psi. And 70.7 Bpm. Get Isip, 1744 Psi., .67 FG., 36/39<br/> Holes Open.<br/> Pump FR Pad With 3% KCL, Start XLink, Stage Into 1# 100 Mesh Stage, Then To 1#,<br/> 2#, 3#, 3.5#, And 4# 20/40 White Stages.<br/> Isdp, 2133 Psi., .72 FG.<br/> Total 100 Mesh: 20,100#<br/> Total 20/40 White: 167,200#<br/> Total 3% KCL: 86,805 Gals.. 2,067 Bbls.. Total Produced Water: 70,168 Gals.. 1,671<br/> Bbls.<br/> BWTR: 3985 Bbls.<br/> Max Rate: 70.9 Bpm<br/> Avg. Rate: 70.5 Bpm<br/> Max. Pressure: 3,616 Psi.<br/> Avg. Pressure: 3,310 Psi.</p>   |
| 07:50      | 0.25     | 08:05    | CTUW | W/L Operation      | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equaize And Open.  |
| 08:05      | 1.17     | 09:15    | PFRT | Perforating        | <p>RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br/> .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br/> Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br/> Found And Correlated To Marker Joint At 6,196 - 6,221'. Drop Down To Depth, Set CBP<br/> At 7,550'. 1150 Psi. On Well. Perforate Stage 6 CR-1/UteLand Butte/Castle Peak Zone<br/> As Follows: 7333 - 34, 7346 - 47, 7355 - 56, 7365 - 66, 7387 - 88, 7403 - 04, 7415 - 16,<br/> 7431 - 32, 7455 - 56, 7466 - 67, 7477 - 78, 7489 - 90, 7501 - 02,<br/> 7529 - 30, 7539 - 40. 1050 Psi. On Well. 45 Holes. POOH. LayDown Gun, Verify All<br/> Shots Fired, WSI And Secured.</p>   |
| 09:15      | 0.17     | 09:25    | GOP  | General Operations | Turn Well Over To HES. Pressure Test To 8500 Psi., Equalize To Well Pressure.   |
| 09:25      | 1.41     | 10:50    | FRAC | Frac. Job          | <p>Frac Stage 6. Fluid System: Hybor G 16<br/> Open Well, 665# lcp.<br/> BrokeDown At 2010 Psi. And 10.2 Bpm.<br/> Pump 3900 Gals. 15% Acid With 90 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br/> ShutDown For 15 Min., Let Balls Fall,<br/> Get Stabilized Inj. Rate At 2884 Psi. And 70.6 Bpm. Get Isip, 1472 Psi., .64 FG., 41/45<br/> Holes Open.<br/> Pump FR Pad With 3% KCL, Start XLink, Stage Into 1# 100 Mesh Stage, Then To 1#,<br/> 2#, 3#, 3.5#, And 4# 20/40 White Stages.<br/> Isdp, 1873 Psi., .69 FG.<br/> Total 100 Mesh: 20,200#<br/> Total 20/40 White: 166,500#<br/> Total 3% KCL: 83,458 Gals.. 1,987 Bbls.. Total Produced Water: 70,480 Gals.. 1,678<br/> Bbls.<br/> BWTR: 3899 Bbls.<br/> Max Rate: 71.1 Bpm<br/> Avg. Rate: 70.6 Bpm<br/> Max. Pressure: 3,002 Psi.<br/> Avg. Pressure: 2,783 Psi.</p> |
| 10:50      | 0.17     | 11:00    | CTUW | W/L Operation      | Turn Well Over To W/L, Arm Gun, Pick-Up With Baker 20 Setting Kit And HES FAS Drill<br>CBP, Nipple Up To Well. Equaize And Open.  |
| 11:00      | 1.17     | 12:10    | PFRT | Perforating        | <p>RIH With 3 1/8" PJ Omega 3104 Perf. Gun Configured At 120 Degree Phasing, 3 Spf,<br/> .36" Penetration Charges, 16 Gms., .44 Dia. Holes .Correlating To HES Spectral<br/> Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br/> Found And Correlated To Marker Joint At 6,196 - 6,221'. Drop Down To Depth, Set CBP<br/> At 7,320'. 1350 Psi. On Well. Perforate Stage 7 Castle Peak Zone As Follows: 7067 -<br/> 68, 7077 - 78,<br/> 7093 - 94, 7105 - 06, 7119 - 20, 7139 - 40, 7150 - 51, 7169 - 70, 7193 - 94, 7213 - 14,<br/> 7219 - 20, 7231 - 32, 7249 - 50, 7269 - 70, 7299 - 00. 650 Psi. On Well. 45 Holes.<br/> POOH. LayDown Gun, Verify All Shots Fired, WSI And Secured.</p>   |
| 12:10      | 0.25     | 12:25    | GOP  | General Operations | Turn Well Over To HES. Pressure Test To 8500 Psi., Equalize To Well Pressure.   |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 12:25      | 1.50     | 13:55    | FRAC | Frac. Job              | Frac Stage 7. Fluid System: Hybor G 16<br>Open Well, 750# lcp.<br>BrokeDown At 3056 Psi. And 9.9 Bpm.<br>Pump 3900 Gals. 15% Acid With 90 Bio Balls, Flush To 10 Bbls. Over Bottom Perf.,<br>ShutDown For 15 Min., Let Balls Fall,<br>Get Stabilized Inj. Rate At 3556 Psi. And 70.6 Bpm. Get Isip, 1141 Psi., .60 FG., 30/45<br>Holes Open.<br>Pump FR Pad With 3% KCL, Start XLink, Stage Into 1# 100 Mesh Stage, Then To 1#,<br>2#, 3#, 3.5#, And 4# 20/40 White Stages.<br>Isdp, 2049 Psi., .73 FG.<br>Total 100 Mesh: 20,800#<br>Total 20/40 White: 165,100#<br>Total 3% KCL: 84,906 Gals.. 2,022 Bbls.. Total Produced Water: 69,660 Gals.. 1,659<br>Bbls.<br>BWTR: 3922 Bbls.<br>Max Rate: 70.8 Bpm<br>Avg. Rate: 70.6 Bpm<br>Max. Pressure: 3,482 Psi.<br>Avg. Pressure: 2,911 Psi. |
| 13:55      |          | 13:55    | CTUW | W/L Operation          | Turn Well Over To W/L, Pick-Up Baker 20 Setting Kit And HES FAS Drill CBP, Nipple<br>Up To Well. Equilaize And Open.  |
| 13:55      |          | 13:55    | PFRT | Perforating            | RIH With 3 1/8" CCL, Sinker Bar And HES CBP. Correlating To HES Spectral<br>Density/Dual Spaced Neutron Dated 05/12/2012 And SBL CBL/CCL Dated 05/18/2012.<br>Found And Correlated To Marker Joint At 6,196 - 6,221'. Drop Down To Depth, Set CBP<br>At 7,010'. 1500 Psi. On Well. POOH. Bleed Pressure Off Well. LD Tools. WSI And<br>Secured.   |
| 13:55      |          | 13:55    | SRIG | Rig Up/Down            | HES And SLB RigDown Equipment. Move Off Location.   |
| 13:55      |          | 13:55    | LOCL | Lock Wellhead & Secure | WSI And Secured. SDFD.  |

**5-27D-36 BTR 6/5/2012 06:00 - 6/6/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 1.00     | 07:00    | LOCL | Lock Wellhead & Secure | WSI.   |
| 07:00      | 0.50     | 07:30    | SMTG | Safety Meeting         | JSA Safety Meeting.  |
| 07:30      | 2.00     | 09:30    | SRIG | Rig Up/Down            | Set Anchors,<br>MIRU w/o rig.  |
| 09:30      | 0.50     | 10:00    | BOPI | Install BOP's          | Bled off Pressure from Csg.<br>ND Frac tree & Frac Sleeve,<br>NU 7 1/16" 5K Double gate, NU 7 1/16" 5K Drilling Spool, NU 7 1/16" 5K Annular, &<br>function test.    |
| 10:00      | 0.50     | 10:30    | SRIG | Rig Up/Down            | RU work floor & Tbg. equip.  |
| 10:30      | 1.50     | 12:00    | GOP  | General Operations     | Unload Tbg. 2 7/8" L80 EUE. 6.5#   |
| 12:00      | 3.50     | 15:30    | RUTB | Run Tubing             | PU 4 3/4" 4 Blade Bit, 2 7/8" POB sub 3 1/8" O.D. w/float, 1 Jt. 2 7/8" L80 6.5# Tbg.,<br>2.205" XN Nipple, 1 Jt., 2.313" X Nipple, & Tbg.<br>Tag Kill Plug @ 6200'. |
| 15:30      | 1.00     | 16:30    | SRIG | Rig Up/Down            | RU Power Swivel & Rig Pump.  |
| 16:30      | 1.50     | 18:00    | DOPG | Drill Out Plugs        | Drill out top of kill plug lost circulation.<br>N2 online, broke down.<br>Lay down 2 Jts.<br>Repair N2 Unit.   |
| 18:00      | 12.00    | 06:00    | LOCL | Lock Wellhead & Secure | Secure well for the night.<br>WSI.   |

**5-27D-36 BTR 6/6/2012 06:00 - 6/7/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com                |
|------------|----------|----------|------|------------------------|--------------------|
| 06:00      | 1.00     | 07:00    | LOCL | Lock Wellhead & Secure | WSI.               |
| 07:00      | 0.50     | 07:30    | SMTG | Safety Meeting         | JSA Safety Meeting |

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com   |
|------------|----------|----------|------|------------------------|---|
| 07:30      | 12.00    | 19:30    | DOPG | Drill Out Plugs        | <p>Make connection to plug.<br/>Establish circ. w/ N2 foam unit. &amp; Rig pump @ 1 Bbls./min.<br/>Drill Plugs as follows:</p> <p>Plg. @ 6200',<br/>Csg.-100#<br/>Plg. @ 7320', 30' of sand.<br/>Csg.-100#<br/>Plg. @ 7550', 35' of sand.<br/>Csg.-250#<br/>Plg. @ 7810', 25' of sand.<br/>Csg.-150#<br/>Plg. @ 8090', 35' of sand.<br/>Csg.-150#<br/>Plg. @ 8432', 20' of sand.<br/>Csg.-300#<br/>Plg. @ 8700', 20' of sand.<br/>Csg.-0#</p> <p>Circulated Bottoms up.</p> |
| 19:30      | 10.50    | 06:00    | LOCL | Lock Wellhead & Secure | WSI.  |
| 06:00      |          | 06:00    |      |                        |   |
| 06:00      |          | 06:00    |      |                        |   |

**5-27D-36 BTR 6/7/2012 06:00 - 6/8/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr)            | End Time           | Code    | Category               | Com  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|------------|---------------------|--------------------|---------|------------------------|--|------------|---------------------|--------------------|---------|------------|-------|------------|-----|---|---------------|---|-------|-----|------|-----|---|-----|--------------|-------|-----|------|----------|-----|-----|--|----------|--|--|--|--|--|--|---|----------|-------|-------|-----|------|------|----------|--|----------|--|--|--|--|--|--|---|--------------|-------|-----|------|-------|----------|--|--|----------|--|--|--|--|--|--|---|-----------|-------|-------|-----|------|------|----------|--|----------|--|--|--|--|--|--|---|--------------|-------|-----|------|------|----------|--|--|----------|--|--|--|--|--|--|---|---------|-------|-------|--|--|------|----------|--|----------|--|--|--|--|--|--|
| 06:00      | 1.00                | 07:00              | LOCL    | Lock Wellhead & Secure | WSI.   |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 07:00      | 0.50                | 07:30              | SMTG    | Safety Meeting         | JSA Safety Meeting   |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 07:30      | 2.50                | 10:00              | CLN     | Clean Out Hole         | Clean out rat hole.<br>Establish Circ. w/ Rig Pump & N2 Unit.<br>Clean out to FC @ 9097'.<br>Circulate clean.  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 10:00      | 0.50                | 10:30              | SRIG    | Rig Up/Down            | RD Power Swivel.   |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 10:30      | 0.50                | 11:00              | PULT    | Pull Tubing            | Lay down tbg. to landing depth.  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 11:00      | 1.00                | 12:00              | GOP     | General Operations     | <div>PU Hanger, Wash Bowl w/ 5 Bbls., Stage hanger thru BOP stack, Land hanger &amp; Test.<br/>Land Tbg. as follows:<br/>Tubing<br/>Des: Tubing - ProductionSet Depth (ftKB): 6,809.7Run Date: 2012/06/07 12:00<br/>Pull Date:<br/>Tubing Components</div> <table><thead><tr><th>Jts (ft)</th><th>Item Des Top (ftKB)</th><th>OD (in) Btm (ftKB)</th><th>ID (in)</th><th>Wt (lb/ft)</th><th>Grade</th><th>Top Thread</th><th>Len</th></tr></thead><tbody><tr><td>1</td><td>Tubing Hanger</td><td>5</td><td>2.441</td><td>6.5</td><td>L-80</td><td>0.4</td><td>0</td></tr><tr><td>212</td><td>Tubing 2 7/8</td><td>2.441</td><td>6.5</td><td>L-80</td><td>6,742.62</td><td>0.4</td><td>0.4</td></tr><tr><td></td><td>6,743.00</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>1</td><td>X Nipple</td><td>2 7/8</td><td>2.313</td><td>6.5</td><td>L-80</td><td>1.25</td><td>6,743.00</td></tr><tr><td></td><td>6,744.30</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>1</td><td>Tubing 2 7/8</td><td>2.441</td><td>6.5</td><td>L-80</td><td>31.71</td><td>6,744.30</td><td></td></tr><tr><td></td><td>6,776.00</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>1</td><td>XN Nipple</td><td>2 7/8</td><td>2.205</td><td>6.5</td><td>L-80</td><td>1.19</td><td>6,776.00</td></tr><tr><td></td><td>6,777.20</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>1</td><td>Tubing 2 7/8</td><td>2.441</td><td>6.5</td><td>L-80</td><td>31.7</td><td>6,777.20</td><td></td></tr><tr><td></td><td>6,808.90</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>1</td><td>POB sub</td><td>3 1/8</td><td>2.441</td><td></td><td></td><td>0.85</td><td>6,808.90</td></tr><tr><td></td><td>6,809.70</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></tbody></table> | Jts (ft)   | Item Des Top (ftKB) | OD (in) Btm (ftKB) | ID (in) | Wt (lb/ft) | Grade | Top Thread | Len | 1 | Tubing Hanger | 5 | 2.441 | 6.5 | L-80 | 0.4 | 0 | 212 | Tubing 2 7/8 | 2.441 | 6.5 | L-80 | 6,742.62 | 0.4 | 0.4 |  | 6,743.00 |  |  |  |  |  |  | 1 | X Nipple | 2 7/8 | 2.313 | 6.5 | L-80 | 1.25 | 6,743.00 |  | 6,744.30 |  |  |  |  |  |  | 1 | Tubing 2 7/8 | 2.441 | 6.5 | L-80 | 31.71 | 6,744.30 |  |  | 6,776.00 |  |  |  |  |  |  | 1 | XN Nipple | 2 7/8 | 2.205 | 6.5 | L-80 | 1.19 | 6,776.00 |  | 6,777.20 |  |  |  |  |  |  | 1 | Tubing 2 7/8 | 2.441 | 6.5 | L-80 | 31.7 | 6,777.20 |  |  | 6,808.90 |  |  |  |  |  |  | 1 | POB sub | 3 1/8 | 2.441 |  |  | 0.85 | 6,808.90 |  | 6,809.70 |  |  |  |  |  |  |
| Jts (ft)   | Item Des Top (ftKB) | OD (in) Btm (ftKB) | ID (in) | Wt (lb/ft)             | Grade  | Top Thread | Len                 |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | Tubing Hanger       | 5                  | 2.441   | 6.5                    | L-80   | 0.4        | 0                   |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 212        | Tubing 2 7/8        | 2.441              | 6.5     | L-80                   | 6,742.62   | 0.4        | 0.4                 |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,743.00            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | X Nipple            | 2 7/8              | 2.313   | 6.5                    | L-80   | 1.25       | 6,743.00            |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,744.30            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | Tubing 2 7/8        | 2.441              | 6.5     | L-80                   | 31.71  | 6,744.30   |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,776.00            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | XN Nipple           | 2 7/8              | 2.205   | 6.5                    | L-80   | 1.19       | 6,776.00            |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,777.20            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | Tubing 2 7/8        | 2.441              | 6.5     | L-80                   | 31.7   | 6,777.20   |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,808.90            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 1          | POB sub             | 3 1/8              | 2.441   |                        |  | 0.85       | 6,808.90            |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
|            | 6,809.70            |                    |         |                        |  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 12:00      | 0.50                | 12:30              | SRIG    | Rig Up/Down            | RD Tbg. equip. & work floor.   |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 12:30      | 0.50                | 13:00              | BOPR    | Remove BOP's           | ND BOP, NU Producton Tree. Tie in sand can From Tbg. to sales line.  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 13:00      | 0.50                | 13:30              | GOP     | General Operations     | Drop ball, POB, & chase w/ 30 Bbls. @ 4.5 Bbls./min. Drain all fluid equip.  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 13:30      | 1.00                | 14:30              | SRIG    | Rig Up/Down            | RDMO w/o Rig.  |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |
| 14:30      | 15.50               | 06:00              | FBCK    | Flowback Well          | Put Well on Production   |            |                     |                    |         |            |       |            |     |   |               |   |       |     |      |     |   |     |              |       |     |      |          |     |     |  |          |  |  |  |  |  |  |   |          |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |       |          |  |  |          |  |  |  |  |  |  |   |           |       |       |     |      |      |          |  |          |  |  |  |  |  |  |   |              |       |     |      |      |          |  |  |          |  |  |  |  |  |  |   |         |       |       |  |  |      |          |  |          |  |  |  |  |  |  |



**Bill Barrett Corporation****5-27D-36 BTR 6/12/2012 06:00 - 6/13/2012 06:00**

|                           |                      |                    |                                |                           |                               |   |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|
| API/UWI<br>43013509170000 | State/Province<br>UT | County<br>Duchesne | Field Name<br>Black Tail Ridge | Well Status<br>COMPLETION | Total Depth (ftKB)<br>9,200.0 | Primary Job Type<br>Drilling & Completion |
|---------------------------|----------------------|--------------------|--------------------------------|---------------------------|-------------------------------|---|

**Time Log**

| Start Time | Dur (hr) | End Time | Code | Category               | Com  |
|------------|----------|----------|------|------------------------|--|
| 06:00      | 2.00     | 08:00    | CTRL | Crew Travel            | Wireline crew traveled to location.  |
| 08:00      | 4.00     | 12:00    | SRIG | Rig Up/Down            | Move in SLB Wireline equipment, R/U pressure control equipment, P/up 1 11/16" ccl & weight bars. attempt to equalize lubricator, Grease head would not seal up. Bled off pressure, L/D lub & grease head. found bad grease head tubs were bad.   |
| 12:00      | 3.50     | 15:30    | DTIM | Downtime               | Down for 3.5 repairing grease head.  |
| 15:30      | 2.00     | 17:30    | WLWK | Wireline               | RIH and tagged PBTD @ 8820' Uncorrected, Pulled up and Tie into HES open log. Drop down and attempt to work through obstruction. No luck, Pooh with E-line.  |
| 17:30      | 1.50     | 19:00    | WLWK | Wireline               | P/up Production logging tools. RIH with CCL/PBMS/PFCS Spinner tool. Tagged obstruction in the tbg @ 3050', make several attempt to work through obstruction. was unsuccessful, decision was made to Pooh with logging tools and flow bottoms up. Pooh with PBMS, when pulling the logging tools through the well valve section, PBMS and spinner became stuck in the lower master valve. Was unable to jar logging tools free. Called out hot oil truck, Opened casing to reduce casing pressure, equalized casing & tbg pressure. |
| 19:00      | 2.25     | 21:15    | GOP  | General Operations     | R/up hot oil truck pumped 70 bbls of production water down tbg @ 150*. Jar logging tool free. Pulled logging tools 10' up into the lubricator and secured master valves.   |
| 21:15      | 1.00     | 22:15    | LOCL | Lock Wellhead & Secure | RDMO SLB. Turned well back to production.  |



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.  
20G0005608

|   |  |   |  |
|---|--|---|--|
| 1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other   |  | 6. If Indian, Allottee or Tribe Name  |  |
| b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr.<br>Other _____   |  | 7. Unit or CA Agreement Name and No.  |  |
| 2. Name of Operator<br>BILL BARRETT CORPORATION Contact: JULIE WEBB<br>E-Mail: jwebb@billbarrettcorp.com  |  | 8. Lease Name and Well No.<br>5-27D-36 BTR ✓                                |  |
| 3. Address 1099 18TH STREET SUITE 2300<br>DENVER, CO 80202  |  | 9. API Well No.<br>43-013-50917   |  |
| 4. Location of Well (Report location clearly and in accordance with Federal requirements)*<br>At surface SWNW 1252FNL 660FWL 40.194606 N Lat, 110.556442 W Lon<br>At top prod interval reported below SWNW 1966FNL 834FWL<br>At total depth SWNW 2000FNL 784FWL <b>BHL by HSM</b> |  | 10. Field and Pool, or Exploratory<br>CEDAR RIM                             |  |
| 14. Date Spudded<br>04/11/2012  |  | 11. Sec., T., R., M., or Block and Survey<br>or Area Sec 27 T3S R6W Mer UBM |  |
| 15. Date T.D. Reached<br>05/11/2012   |  | 12. County or Parish<br>DUCHESE COUNTY UT                                   |  |
| 16. Date Completed<br><input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.<br>06/07/2012   |  | 13. State<br>UT   |  |
| 17. Elevations (DF, KB, RT, GL)*<br>6062 GL   |  |   |  |
| 18. Total Depth: MD 9200<br>TVD 9121  |  | 19. Plug Back T.D.: MD 9152<br>TVD 9073.2                                   |  |
| 20. Depth Bridge Plug Set: MD<br>TVD  |  |   |  |

|   |  |
|---|--|
| 21. Type Electric & Other Mechanical Logs Run (Submit copy of each)<br>CBL, MUD, BOREHOLE, SP, DEN, DL, MSF | 22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis)<br>Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis)<br>Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit analysis) |
|---|--|

23. Casing and Liner Record (Report all strings set in well)

| Hole Size | Size/Grade  | Wt. (#/ft.) | Top (MD) | Bottom (MD) | Stage Cementer Depth | No. of Sk. & Type of Cement | Slurry Vol. (BBL) | Cement Top* | Amount Pulled |
|-----------|-------------|-------------|----------|-------------|----------------------|-----------------------------|-------------------|-------------|---------------|
| 26.000    | 16.000 COND | 36.0        | 0        | 96          | 96                   |                             |                   | 0           |               |
| 12.250    | 9.625 J-55  | 36.0        | 0        | 3033        | 2325                 | 710                         | 331               | 0           |               |
| 8.750     | 5.500 P-110 | 17.0        | 0        | 9200        | 9187                 | 1385                        | 474               | 1522        | 15000         |
|           |             |             |          |             |                      |                             |                   |             |               |
|           |             |             |          |             |                      |                             |                   |             |               |
|           |             |             |          |             |                      |                             |                   |             |               |
|           |             |             |          |             |                      |                             |                   |             |               |

24. Tubing Record

| Size  | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) | Size | Depth Set (MD) | Packer Depth (MD) |
|-------|----------------|-------------------|------|----------------|-------------------|------|----------------|-------------------|
| 2.875 | 8683           |                   |      |                |                   |      |                |                   |

25. Producing Intervals

| Formation      | Top  | Bottom | Perforated Interval | Size  | No. Holes | Perf. Status |
|----------------|------|--------|---------------------|-------|-----------|--------------|
| A) GREEN RIVER | 7067 | 7791   | 7067 TO 7791        | 0.380 | 129       | OPEN         |
| B) WASATCH     | 7817 | 9001   | 7817 TO 9001        | 0.380 | 117       | OPEN         |
| C)             |      |        |                     |       |           |              |
| D)             |      |        |                     |       |           |              |

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

| Depth Interval | Amount and Type of Material           |
|----------------|---------------------------------------|
| 7067 TO 7791   | GREEN RIVER: SEE TREATMENT STAGES 5-7 |
| 7817 TO 9001   | WASATCH: SEE TREATMENT STAGES 1-4     |
|                |                                       |
|                |                                       |

28. Production - Interval A

| Date First Produced | Test Date         | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|-------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| 06/07/2012          | 06/10/2012        | 24           | →               | 484.0   | 814.0   | 505.0     | 52.0                  |             | FLows FROM WELL   |
| Choke Size          | Tbg. Press. Flwg. | Csg. Press.  | 24 Hr. Rate     | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio         | Well Status |                   |
| 26/64               | SI                | 1480.0       | →               | 484     | 814     | 505       | 1681                  | POW         |                   |

28a. Production - Interval B

| Date First Produced | Test Date         | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|---------------------|-------------------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
|                     |                   |              | →               |         |         |           |                       |             |                   |
| Choke Size          | Tbg. Press. Flwg. | Csg. Press.  | 24 Hr. Rate     | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio         | Well Status |                   |
|                     | SI                |              | →               |         |         |           |                       |             |                   |

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #143411 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*

RECEIVED

JUL 19 2012

Div. of Oil, Gas & Mining

| 28b. Production - Interval C |           |              |                 |         |         |           |                       |             |                   |
|------------------------------|-----------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| Date First Produced          | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|                              |           |              | — ▾             |         |         |           |                       |             |                   |

| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status |
|------------|----------------------|-------------|-------------|---------|---------|-----------|---------------|-------------|
|            |                      |             | — ▾         |         |         |           |               |             |

| 28c. Production - Interval D |           |              |                 |         |         |           |                       |             |                   |
|------------------------------|-----------|--------------|-----------------|---------|---------|-----------|-----------------------|-------------|-------------------|
| Date First Produced          | Test Date | Hours Tested | Test Production | Oil BBL | Gas MCF | Water BBL | Oil Gravity Corr. API | Gas Gravity | Production Method |
|                              |           |              | — ▾             |         |         |           |                       |             |                   |

| Choke Size | Tbg. Press. Flwg. SI | Csg. Press. | 24 Hr. Rate | Oil BBL | Gas MCF | Water BBL | Gas:Oil Ratio | Well Status |
|------------|----------------------|-------------|-------------|---------|---------|-----------|---------------|-------------|
|            |                      |             | — ▾         |         |         |           |               |             |

29. Disposition of Gas(Sold, used for fuel, vented, etc.)  
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

| Formation | Top | Bottom | Descriptions, Contents, etc. | Name          | Top         |
|-----------|-----|--------|------------------------------|---------------|-------------|
|           |     |        |                              |               | Meas. Depth |
|           |     |        |                              | GREEN RIVER   | 3195        |
|           |     |        |                              | MAHOGANY      | 3900        |
|           |     |        |                              | DOUGLAS CREEK | 6148        |
|           |     |        |                              | BLACK SHALE   | 6919        |
|           |     |        |                              | CASTLE PEAK   | 7063        |
|           |     |        |                              | UTELAND BUTTE | 7398        |
|           |     |        |                              | WASATCH       | 7797        |
|           |     |        |                              | TD            | 9200        |

32. Additional remarks (include plugging procedure):  
TOC was calculated by CBL. Conductor was cemented with grout. This well had first gas sales on 6/7/2012 and first oil sales on 6/9/2012.

Treatment Summary Attached.

CBL was mailed due to file size.

33. Circle enclosed attachments:

- |   |                    |               |                       |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.)     | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis   | 7 Other:      |                       |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #143411 Verified by the BLM Well Information System.  
For BILL BARRETT CORPORATION, sent to the Vernal

Name (please print) JULIE WEBB

Title PERMIT ANALYST

Signature

(Electronic Submission)

Date 07/19/2012

Title 18 U.S.C. Section 1001 and Title 18 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\***

## 5-27D-36 BTR Report

| 44. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. (cont.) |                    |                         |                 |
|---|--------------------|-------------------------|-----------------|
| AMOUNT AND TYPE OF MATERIAL                                 |                    |                         |                 |
| <u>Stage</u>  | <u>Bbls Slurry</u> | <u>20/40 White Sand</u> | <u>100 Mesh</u> |
| 1   | 3,513              | 157,100                 |                 |
| 2   | 3,549              | 165,600                 |                 |
| 3   | 3,329              | 156,600                 |                 |
| 4   | 3,474              | 160,000                 |                 |
| 5   | 3,981              | 167,200                 | 20,100          |
| 6   | 3,912              | 166,500                 | 20,200          |
| 7   | 3,923              | 165,100                 | 20,800          |

\*Depth intervals for frac information same as perforation record intervals.

# **Bill Barrett Corp**

Duchesne County, UT (NAD 1927)

Sec. 27-T3S-R6W

5-27D-36 BTR

Plan C

Design: MWD Survey

## **Sperry Drilling Services Final Survey Report**

17 July, 2012

Well Coordinates: 679,339.47 N, 2,263,777.11 E (40° 11' 40.74" N, 110° 33' 20.63" W)

Ground Level: 6,062.00 ft

Local Coordinate Origin:

Centered on Well 5-27D-36 BTR

Viewing Datum:

KB @ 6078.00ft (Patterson 506)

TVDs to System:

N

North Reference:

True

Unit System:

API - US Survey Feet - Custom

Geodetic Scale Factor Applied

Version: 2003.16 Build: 43I

**HALLIBURTON**

## Design Report for 5-27D-36 BTR - MWD Survey

| Measured Depth (ft)     | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) |
|-------------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|
| 0.00                    | 0.00            | 0.00        | 0.00                | 0.00       | 0.00       | 0.00                  | 0.00                  |
| 131.00                  | 0.12            | 83.82       | 131.00              | 0.01       | 0.14       | 0.01                  | 0.09                  |
| <b>First MWD Survey</b> |                 |             |                     |            |            |                       |                       |
| 191.00                  | 0.12            | 131.30      | 191.00              | -0.02      | 0.25       | 0.07                  | 0.16                  |
| 252.00                  | 0.12            | 220.51      | 252.00              | -0.11      | 0.25       | 0.16                  | 0.28                  |
| 314.00                  | 0.39            | 222.92      | 314.00              | -0.31      | 0.07       | 0.32                  | 0.44                  |
| 376.00                  | 0.17            | 203.01      | 376.00              | -0.55      | -0.11      | 0.52                  | 0.38                  |
| 436.00                  | 0.18            | 141.85      | 436.00              | -0.71      | -0.09      | 0.67                  | 0.30                  |
| 497.00                  | 0.32            | 149.62      | 497.00              | -0.93      | 0.06       | 0.92                  | 0.24                  |
| 559.00                  | 0.51            | 150.65      | 559.00              | -1.32      | 0.28       | 1.35                  | 0.31                  |
| 620.00                  | 0.57            | 174.85      | 619.99              | -1.86      | 0.44       | 1.91                  | 0.38                  |
| 681.00                  | 0.45            | 146.84      | 680.99              | -2.36      | 0.60       | 2.44                  | 0.45                  |
| 742.00                  | 0.36            | 84.46       | 741.99              | -2.55      | 0.92       | 2.68                  | 0.70                  |
| 803.00                  | 0.21            | 0.02        | 802.99              | -2.42      | 1.11       | 2.60                  | 0.65                  |
| 864.00                  | 0.18            | 282.85      | 863.99              | -2.28      | 1.02       | 2.45                  | 0.40                  |
| 925.00                  | 0.24            | 282.48      | 924.99              | -2.23      | 0.80       | 2.35                  | 0.10                  |
| 988.00                  | 0.21            | 114.93      | 987.99              | -2.25      | 0.77       | 2.37                  | 0.71                  |
| 1,052.00                | 0.18            | 206.47      | 1,051.99            | -2.39      | 0.84       | 2.52                  | 0.44                  |
| 1,115.00                | 0.24            | 123.78      | 1,114.99            | -2.55      | 0.90       | 2.69                  | 0.45                  |
| 1,178.00                | 0.64            | 115.87      | 1,177.99            | -2.78      | 1.33       | 3.00                  | 0.64                  |
| 1,242.00                | 0.29            | 139.89      | 1,241.98            | -3.06      | 1.75       | 3.36                  | 0.61                  |
| 1,305.00                | 0.31            | 184.25      | 1,304.98            | -3.35      | 1.84       | 3.67                  | 0.36                  |
| 1,369.00                | 0.64            | 213.37      | 1,368.98            | -3.82      | 1.63       | 4.08                  | 0.62                  |
| 1,432.00                | 0.89            | 220.06      | 1,431.97            | -4.49      | 1.13       | 4.63                  | 0.42                  |
| 1,496.00                | 0.50            | 194.55      | 1,495.97            | -5.14      | 0.74       | 5.18                  | 0.76                  |
| 1,560.00                | 0.33            | 154.60      | 1,559.97            | -5.58      | 0.74       | 5.61                  | 0.51                  |
| 1,622.00                | 0.48            | 188.72      | 1,621.97            | -6.00      | 0.78       | 6.03                  | 0.45                  |
| 1,686.00                | 0.67            | 205.43      | 1,685.96            | -6.60      | 0.58       | 6.57                  | 0.39                  |
| 1,749.00                | 0.32            | 153.20      | 1,748.96            | -7.09      | 0.50       | 7.04                  | 0.85                  |
| 1,813.00                | 0.37            | 67.77       | 1,812.96            | -7.17      | 0.77       | 7.17                  | 0.73                  |
| 1,876.00                | 0.91            | 37.21       | 1,875.96            | -6.70      | 1.26       | 6.81                  | 0.99                  |
| 1,940.00                | 1.21            | 43.43       | 1,939.95            | -5.80      | 2.04       | 6.10                  | 0.50                  |
| 2,003.00                | 0.84            | 44.93       | 2,002.94            | -4.99      | 2.82       | 5.48                  | 0.59                  |
| 2,066.00                | 0.62            | 68.44       | 2,065.93            | -4.54      | 3.46       | 5.17                  | 0.58                  |
| 2,130.00                | 0.34            | 127.09      | 2,129.93            | -4.53      | 3.94       | 5.26                  | 0.83                  |
| 2,193.00                | 0.33            | 100.24      | 2,192.93            | -4.67      | 4.26       | 5.47                  | 0.25                  |
| 2,257.00                | 0.49            | 93.86       | 2,256.93            | -4.72      | 4.72       | 5.62                  | 0.26                  |
| 2,320.00                | 0.62            | 163.28      | 2,319.92            | -5.07      | 5.09       | 6.03                  | 1.02                  |
| 2,384.00                | 1.05            | 184.28      | 2,383.92            | -5.98      | 5.14       | 6.94                  | 0.81                  |
| 2,448.00                | 1.21            | 165.33      | 2,447.90            | -7.22      | 5.27       | 8.18                  | 0.63                  |
| 2,511.00                | 2.72            | 162.50      | 2,510.87            | -9.29      | 5.89       | 10.33                 | 2.40                  |
| 2,574.00                | 3.60            | 163.57      | 2,573.77            | -12.61     | 6.90       | 13.79                 | 1.40                  |
| 2,638.00                | 3.99            | 163.27      | 2,637.63            | -16.67     | 8.10       | 18.02                 | 0.61                  |
| 2,701.00                | 4.95            | 160.18      | 2,700.44            | -21.33     | 9.66       | 22.90                 | 1.57                  |
| 2,765.00                | 6.21            | 160.56      | 2,764.13            | -27.19     | 11.75      | 29.07                 | 1.97                  |
| 2,828.00                | 7.08            | 159.69      | 2,826.71            | -34.05     | 14.23      | 36.29                 | 1.39                  |
| 2,892.00                | 7.47            | 159.71      | 2,890.19            | -41.65     | 17.04      | 44.32                 | 0.61                  |
| 2,955.00                | 8.28            | 157.47      | 2,952.60            | -49.68     | 20.20      | 52.84                 | 1.37                  |
| 2,970.00                | 8.62            | 156.80      | 2,967.44            | -51.71     | 21.05      | 55.00                 | 2.36                  |
| 3,087.00                | 8.70            | 159.04      | 3,083.10            | -68.03     | 27.67      | 72.36                 | 0.30                  |

## Design Report for 5-27D-36 BTR - MWD Survey

| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|
| 3,151.00            | 8.10            | 161.05      | 3,146.42            | -76.82     | 30.87      | 81.62                 | 1.04                  |
| 3,214.00            | 8.97            | 158.10      | 3,208.72            | -85.57     | 34.14      | 90.88                 | 1.55                  |
| 3,278.00            | 9.65            | 157.31      | 3,271.87            | -95.15     | 38.07      | 101.07                | 1.08                  |
| 3,341.00            | 10.43           | 158.23      | 3,333.91            | -105.32    | 42.22      | 111.89                | 1.26                  |
| 3,405.00            | 11.38           | 159.55      | 3,396.75            | -116.61    | 46.58      | 123.85                | 1.53                  |
| 3,468.00            | 11.93           | 160.92      | 3,458.45            | -128.59    | 50.88      | 136.47                | 0.98                  |
| 3,532.00            | 12.57           | 162.03      | 3,521.00            | -141.47    | 55.19      | 149.97                | 1.07                  |
| 3,595.00            | 12.71           | 162.42      | 3,582.47            | -154.60    | 59.40      | 163.69                | 0.26                  |
| 3,659.00            | 13.80           | 161.15      | 3,644.76            | -168.53    | 63.99      | 178.29                | 1.76                  |
| 3,722.00            | 14.87           | 159.89      | 3,705.80            | -183.23    | 69.20      | 193.76                | 1.77                  |
| 3,786.00            | 15.23           | 158.30      | 3,767.61            | -198.76    | 75.13      | 210.19                | 0.86                  |
| 3,849.00            | 15.53           | 158.36      | 3,828.35            | -214.28    | 81.30      | 226.67                | 0.48                  |
| 3,913.00            | 15.85           | 159.05      | 3,889.96            | -230.41    | 87.58      | 243.77                | 0.58                  |
| 3,976.00            | 16.12           | 161.44      | 3,950.53            | -246.74    | 93.44      | 260.96                | 1.13                  |
| 4,039.00            | 15.83           | 162.72      | 4,011.10            | -263.23    | 98.78      | 278.22                | 0.72                  |
| 4,102.00            | 15.78           | 164.28      | 4,071.72            | -279.68    | 103.65     | 295.33                | 0.68                  |
| 4,166.00            | 16.11           | 164.62      | 4,133.25            | -296.62    | 108.37     | 312.88                | 0.54                  |
| 4,229.00            | 16.42           | 163.76      | 4,193.73            | -313.60    | 113.18     | 330.49                | 0.62                  |
| 4,293.00            | 16.08           | 163.46      | 4,255.17            | -330.78    | 118.23     | 348.36                | 0.55                  |
| 4,356.00            | 15.34           | 162.59      | 4,315.82            | -347.09    | 123.21     | 365.36                | 1.23                  |
| 4,419.00            | 15.33           | 161.72      | 4,376.58            | -362.95    | 128.31     | 381.94                | 0.37                  |
| 4,483.00            | 15.47           | 161.66      | 4,438.28            | -379.09    | 133.65     | 398.84                | 0.22                  |
| 4,546.00            | 15.03           | 163.05      | 4,499.06            | -394.88    | 138.68     | 415.34                | 0.91                  |
| 4,610.00            | 14.34           | 162.46      | 4,560.97            | -410.37    | 143.48     | 431.50                | 1.10                  |
| 4,673.00            | 14.36           | 161.75      | 4,622.01            | -425.23    | 148.28     | 447.04                | 0.28                  |
| 4,737.00            | 14.05           | 161.54      | 4,684.05            | -440.14    | 153.23     | 462.66                | 0.49                  |
| 4,800.00            | 13.80           | 161.95      | 4,745.20            | -454.54    | 157.98     | 477.73                | 0.43                  |
| 4,864.00            | 13.65           | 163.83      | 4,807.37            | -469.05    | 162.44     | 492.86                | 0.74                  |
| 4,927.00            | 13.99           | 164.83      | 4,868.55            | -483.54    | 166.51     | 507.89                | 0.66                  |
| 4,991.00            | 13.72           | 166.14      | 4,930.68            | -498.37    | 170.35     | 523.20                | 0.65                  |
| 5,054.00            | 13.71           | 165.91      | 4,991.89            | -512.87    | 173.96     | 538.13                | 0.09                  |
| 5,118.00            | 12.87           | 165.36      | 5,054.17            | -527.12    | 177.61     | 552.83                | 1.33                  |
| 5,181.00            | 11.62           | 166.44      | 5,115.74            | -540.08    | 180.87     | 566.18                | 2.02                  |
| 5,244.00            | 11.85           | 166.60      | 5,177.42            | -552.54    | 183.85     | 579.00                | 0.37                  |
| 5,307.00            | 12.00           | 167.06      | 5,239.06            | -565.21    | 186.82     | 592.01                | 0.28                  |
| 5,370.00            | 11.12           | 167.17      | 5,300.78            | -577.52    | 189.63     | 604.64                | 1.40                  |
| 5,434.00            | 10.30           | 168.91      | 5,363.67            | -589.15    | 192.11     | 616.53                | 1.38                  |
| 5,497.00            | 9.63            | 171.22      | 5,425.72            | -599.89    | 193.99     | 627.42                | 1.24                  |
| 5,561.00            | 9.01            | 173.15      | 5,488.87            | -610.15    | 195.41     | 637.75                | 1.08                  |
| 5,624.00            | 8.37            | 174.04      | 5,551.15            | -619.61    | 196.47     | 647.22                | 1.04                  |
| 5,688.00            | 7.70            | 176.35      | 5,614.52            | -628.52    | 197.23     | 656.09                | 1.16                  |
| 5,751.00            | 7.13            | 178.24      | 5,676.99            | -636.64    | 197.62     | 664.10                | 0.98                  |
| 5,814.00            | 7.05            | 180.04      | 5,739.51            | -644.42    | 197.74     | 671.73                | 0.37                  |
| 5,878.00            | 6.63            | 181.07      | 5,803.06            | -652.04    | 197.66     | 679.16                | 0.68                  |
| 5,941.00            | 6.41            | 184.25      | 5,865.65            | -659.18    | 197.34     | 686.07                | 0.67                  |
| 6,005.00            | 6.09            | 190.71      | 5,929.27            | -666.08    | 196.44     | 692.62                | 1.21                  |
| 6,068.00            | 5.50            | 196.27      | 5,991.95            | -672.26    | 194.97     | 698.35                | 1.29                  |
| 6,131.00            | 5.09            | 205.12      | 6,054.68            | -677.69    | 192.94     | 703.22                | 1.45                  |
| 6,195.00            | 4.80            | 215.94      | 6,118.44            | -682.43    | 190.16     | 707.26                | 1.52                  |
| 6,259.00            | 4.82            | 214.60      | 6,182.22            | -686.81    | 187.06     | 710.88                | 0.18                  |
| 6,322.00            | 3.89            | 214.77      | 6,245.03            | -690.74    | 184.34     | 714.15                | 1.48                  |

**Design Report for 5-27D-36 BTR - MWD Survey**

| Measured Depth (ft)            | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) |
|--------------------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|
| 6,385.00                       | 2.98            | 221.26      | 6,307.92            | -693.73    | 182.04     | 716.58                | 1.57                  |
| 6,449.00                       | 3.17            | 231.15      | 6,371.83            | -696.09    | 179.57     | 718.36                | 0.88                  |
| 6,512.00                       | 2.57            | 231.37      | 6,434.75            | -698.07    | 177.11     | 719.76                | 0.95                  |
| 6,575.00                       | 1.76            | 212.01      | 6,497.71            | -699.77    | 175.49     | 721.08                | 1.72                  |
| 6,639.00                       | 1.37            | 199.51      | 6,561.68            | -701.32    | 174.72     | 722.44                | 0.81                  |
| 6,703.00                       | 1.44            | 204.98      | 6,625.66            | -702.77    | 174.12     | 723.73                | 0.24                  |
| 6,766.00                       | 1.67            | 197.49      | 6,688.64            | -704.37    | 173.51     | 725.15                | 0.49                  |
| 6,830.00                       | 2.13            | 163.38      | 6,752.61            | -706.39    | 173.57     | 727.15                | 1.87                  |
| 6,893.00                       | 2.02            | 142.80      | 6,815.57            | -708.40    | 174.58     | 729.32                | 1.19                  |
| 6,957.00                       | 1.57            | 178.61      | 6,879.54            | -710.18    | 175.28     | 731.21                | 1.85                  |
| 7,020.00                       | 1.77            | 192.46      | 6,942.51            | -711.99    | 175.09     | 732.94                | 0.71                  |
| 7,083.00                       | 1.79            | 205.57      | 7,005.48            | -713.83    | 174.46     | 734.60                | 0.65                  |
| 7,147.00                       | 1.84            | 220.35      | 7,069.45            | -715.51    | 173.36     | 736.01                | 0.73                  |
| 7,211.00                       | 1.33            | 262.27      | 7,133.42            | -716.39    | 171.96     | 736.58                | 1.92                  |
| 7,274.00                       | 1.61            | 285.61      | 7,196.40            | -716.25    | 170.38     | 736.10                | 1.04                  |
| 7,338.00                       | 1.64            | 280.76      | 7,260.38            | -715.84    | 168.62     | 735.33                | 0.22                  |
| 7,401.00                       | 1.67            | 265.19      | 7,323.35            | -715.75    | 166.82     | 734.85                | 0.71                  |
| 7,465.00                       | 1.43            | 263.26      | 7,387.33            | -715.92    | 165.09     | 734.66                | 0.38                  |
| 7,528.00                       | 1.22            | 303.24      | 7,450.31            | -715.65    | 163.75     | 734.10                | 1.47                  |
| 7,592.00                       | 0.79            | 308.79      | 7,514.30            | -715.00    | 162.84     | 733.27                | 0.69                  |
| 7,655.00                       | 0.74            | 252.09      | 7,577.30            | -714.85    | 162.11     | 732.97                | 1.16                  |
| 7,719.00                       | 1.02            | 223.11      | 7,641.29            | -715.39    | 161.33     | 733.34                | 0.81                  |
| 7,782.00                       | 0.98            | 248.31      | 7,704.28            | -716.00    | 160.45     | 733.74                | 0.70                  |
| 7,845.00                       | 1.18            | 299.21      | 7,767.27            | -715.88    | 159.38     | 733.40                | 1.50                  |
| 7,909.00                       | 1.24            | 289.87      | 7,831.26            | -715.33    | 158.15     | 732.60                | 0.32                  |
| 7,972.00                       | 1.30            | 246.59      | 7,894.24            | -715.38    | 156.86     | 732.37                | 1.49                  |
| 8,036.00                       | 1.60            | 228.23      | 7,958.22            | -716.26    | 155.52     | 732.95                | 0.86                  |
| 8,099.00                       | 1.54            | 231.96      | 8,021.20            | -717.37    | 154.20     | 733.75                | 0.19                  |
| 8,163.00                       | 1.51            | 244.48      | 8,085.18            | -718.26    | 152.76     | 734.32                | 0.52                  |
| 8,226.00                       | 1.71            | 241.72      | 8,148.15            | -719.07    | 151.19     | 734.77                | 0.34                  |
| 8,289.00                       | 1.75            | 245.81      | 8,211.12            | -719.91    | 149.48     | 735.23                | 0.21                  |
| 8,353.00                       | 2.06            | 251.79      | 8,275.09            | -720.67    | 147.50     | 735.55                | 0.57                  |
| 8,416.00                       | 2.03            | 264.29      | 8,338.05            | -721.13    | 145.31     | 735.54                | 0.71                  |
| 8,479.00                       | 1.86            | 277.31      | 8,401.01            | -721.11    | 143.19     | 735.07                | 0.75                  |
| 8,543.00                       | 2.01            | 260.93      | 8,464.98            | -721.16    | 141.05     | 734.66                | 0.89                  |
| 8,607.00                       | 2.13            | 238.80      | 8,528.94            | -721.95    | 138.92     | 734.98                | 1.25                  |
| 8,670.00                       | 2.54            | 228.61      | 8,591.88            | -723.48    | 136.87     | 736.04                | 0.92                  |
| 8,733.00                       | 2.70            | 222.29      | 8,654.82            | -725.50    | 134.83     | 737.58                | 0.52                  |
| 8,796.00                       | 2.78            | 213.27      | 8,717.75            | -727.87    | 132.99     | 739.51                | 0.70                  |
| 8,860.00                       | 2.85            | 210.58      | 8,781.67            | -730.54    | 131.33     | 741.76                | 0.23                  |
| 8,923.00                       | 2.96            | 208.84      | 8,844.59            | -733.32    | 129.75     | 744.13                | 0.22                  |
| 8,987.00                       | 3.12            | 205.36      | 8,908.50            | -736.34    | 128.21     | 746.76                | 0.38                  |
| 9,051.00                       | 3.20            | 202.41      | 8,972.40            | -739.56    | 126.78     | 749.61                | 0.28                  |
| 9,114.00                       | 3.45            | 201.61      | 9,035.30            | -742.95    | 125.41     | 752.63                | 0.40                  |
| 9,138.00                       | 3.43            | 201.08      | 9,059.25            | -744.29    | 124.89     | 753.82                | 0.16                  |
| <b>Final MWD Survey</b>        |                 |             |                     |            |            |                       |                       |
| 9,200.00                       | 3.43            | 201.08      | 9,121.14            | -747.75    | 123.55     | 756.92                | 0.00                  |
| <b>Survey Projection to TD</b> |                 |             |                     |            |            |                       |                       |



## Design Report for 5-27D-36 BTR - MWD Survey

### Vertical Section Information

| Angle<br>Type | Target                               | Azimuth<br>(°) | Origin<br>Type | Origin<br>+N/_S<br>(ft) | +E/-W<br>(ft) | Start<br>TVD<br>(ft) |
|---------------|--------------------------------------|----------------|----------------|-------------------------|---------------|----------------------|
| Target        | 5-27D-36 BTR_PlanC -<br>Rev0_BHL Tgt | 167.72         | Slot           | 0.00                    | 0.00          | 0.00                 |

### Survey tool program

| From<br>(ft) | To<br>(ft) | Survey/Plan        | Survey Tool |
|--------------|------------|--------------------|-------------|
| 131.00       | 9,200.00   | Sperry MWD Surveys | MWD         |

### Targets

| Target Name<br>- hit/miss target<br>- Shape  | Dip<br>Angle<br>(°) | Dip<br>Dir.<br>(°) | TVD<br>(ft) | +N/-S<br>(ft) | +E/-W<br>(ft) | Northing<br>(ft) | Easting<br>(ft) | Latitude         | Longitude         |
|--|---------------------|--------------------|-------------|---------------|---------------|------------------|-----------------|------------------|-------------------|
| 5-27D-36   | 0.00                | 0.00               | 6,339.00    | -727.49       | 158.33        | 678,613.75       | 2,263,943.09    | 40° 11' 33.551 N | 110° 33' 18.591 W |
| - actual wellpath misses target center by 39.58ft at 6418.20ft MD (6341.07 TVD, -694.99 N, 180.83 E) |                     |                    |             |               |               |                  |                 |                  |                   |
| - Rectangle (sides W200.00 H200.00 D2,748.00)  |                     |                    |             |               |               |                  |                 |                  |                   |
| 5-27D-36   | 0.00                | 0.00               | 9,087.00    | -727.49       | 158.33        | 678,613.75       | 2,263,943.09    | 40° 11' 33.551 N | 110° 33' 18.591 W |
| - actual wellpath misses target center by 46.59ft at 9138.00ft MD (9059.25 TVD, -744.29 N, 124.89 E) |                     |                    |             |               |               |                  |                 |                  |                   |
| - Point  |                     |                    |             |               |               |                  |                 |                  |                   |
| 5-27D-36   | 0.00                | 0.00               | 0.00        | 0.00          | 0.00          | 679,339.47       | 2,263,777.11    | 40° 11' 40.740 N | 110° 33' 20.632 W |
| - actual wellpath hits target center   |                     |                    |             |               |               |                  |                 |                  |                   |
| - Polygon  |                     |                    |             |               |               |                  |                 |                  |                   |
| Point 1  |                     |                    |             | 0.00          | -575.00       | 678,764.55       | 2,263,783.17    |                  |                   |
| Point 2  |                     |                    |             | 0.00          | -875.00       | 678,464.59       | 2,263,786.34    |                  |                   |
| Point 3  |                     |                    |             | 0.00          | -575.00       | 678,764.55       | 2,263,783.17    |                  |                   |

# HALLIBURTON

## North Reference Sheet for Sec. 27-T3S-R6W - 5-27D-36 BTR - Plan C

All data is in US Feet unless otherwise stated. Directions and Coordinates are relative to True North Reference.

Vertical Depths are relative to KB @ 6078.00ft (Patterson 506). Northing and Easting are relative to 5-27D-36 BTR

Coordinate System is US State Plane 1927 (Exact solution), Utah Central 4302 using datum NAD 1927 (NADCON CONUS), ellipsoid Clarke 1866

Projection method is Lambert Conformal Conic (2 parallel)

Central Meridian is 111° 30' 0.000 W°, Longitude Origin: 0° 0' 0.000 E°, Latitude Origin: 40° 39' 0.000 N°

False Easting: 2,000,000.00ft, False Northing: 0.00ft, Scale Reduction: 0.99991848

Grid Coordinates of Well: 679,339.47 ft N, 2,263,777.11 ft E


Geographical Coordinates of Well: 40° 11' 40.74" N, 110° 33' 20.63" W

Grid Convergence at Surface is: 0.60°

Based upon Minimum Curvature type calculations, at a Measured Depth of 9,200.00ft

the Bottom Hole Displacement is 757.89ft in the Direction of 170.62° (True).


Magnetic Convergence at surface is: -10.86° (28 April 2012, , BGGM2011)



Project: Duchesne County, UT (NAD.1927)  
Site: Sec. 27-T3S-R6W  
Well: 5-27D-36 BTR

Bill Barrett Corp


**HALLIBURTON**  
Sperry Drilling



Project: Duchesne County, UT (NAD 1927)  
Site: Sec. 27-T3S-R6W  
Well: 5-27D-36 BTR

Bill Barrett Corp

**HALLIBURTON**  
Sperry Drilling



|  |   |   |
|--|---|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |   | <b>FORM 9</b>   |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. |   | <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626442 |
| <b>1. TYPE OF WELL</b><br>Oil Well   |   | <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>                  |
| <b>2. NAME OF OPERATOR:</b><br>BILL BARRETT CORP   |   | <b>7. UNIT or CA AGREEMENT NAME:</b>                          |
| <b>3. ADDRESS OF OPERATOR:</b><br>1099 18th Street Ste 2300 , Denver, CO, 80202  |   | <b>8. WELL NAME and NUMBER:</b><br>5-27D-36                   |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>1252 FNL 0660 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U  |   | <b>9. API NUMBER:</b><br>43013509170000                       |
| <b>PHONE NUMBER:</b><br>303 312-8164 Ext   |   | <b>9. FIELD and POOL or WILDCAT:</b><br>CEDAR RIM             |
| <b>COUNTY:</b><br>DUCHESNE   |   | <b>STATE:</b><br>UTAH   |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA  |   |   |
| <b>TYPE OF SUBMISSION</b>  | <b>TYPE OF ACTION</b>                                   |   |
| <input type="checkbox"/> NOTICE OF INTENT<br>Approximate date work will start:   | <input type="checkbox"/> ACIDIZE                        |   |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT<br>Date of Work Completion:<br>9/15/2012   | <input type="checkbox"/> ALTER CASING                   |   |
| <input type="checkbox"/> SPUD REPORT<br>Date of Spud:  | <input type="checkbox"/> CASING REPAIR                  |   |
| <input type="checkbox"/> DRILLING REPORT<br>Report Date:   | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS       |   |
|  | <input type="checkbox"/> CHANGE TUBING                  |   |
|  | <input type="checkbox"/> CHANGE WELL STATUS             |   |
|  | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS |   |
|  | <input type="checkbox"/> DEEPEN                         |   |
|  | <input type="checkbox"/> FRACTURE TREAT                 |   |
|  | <input type="checkbox"/> OPERATOR CHANGE                |   |
|  | <input type="checkbox"/> PLUG AND ABANDON               |   |
|  | <input type="checkbox"/> PRODUCTION START OR RESUME     |   |
|  | <input type="checkbox"/> RECLAMATION OF WELL SITE       |   |
|  | <input type="checkbox"/> REPERFORATE CURRENT FORMATION  |   |
|  | <input type="checkbox"/> SIDETRACK TO REPAIR WELL       |   |
|  | <input type="checkbox"/> TUBING REPAIR                  |   |
|  | <input type="checkbox"/> VENT OR FLARE                  |   |
|  | <input type="checkbox"/> WATER SHUTOFF                  |   |
|  | <input type="checkbox"/> SI TA STATUS EXTENSION         |   |
|  | <input type="checkbox"/> WILDCAT WELL DETERMINATION     |   |
|  | <input checked="" type="checkbox"/> OTHER               |   |
|  | OTHER: <input type="text" value="Lease"/>               |   |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.<br>The tribal lease has been earned for this well. The new lease number is 1420H626442 containing 640 acres (Section 27: All).  |   |   |
| Accepted by the<br>Utah Division of<br>Oil, Gas and Mining<br><b>FOR RECORD ONLY</b><br>October 01, 2012   |   |   |
| <b>NAME (PLEASE PRINT)</b><br>Venessa Langmacher   | <b>PHONE NUMBER</b><br>303 312-8172                     | <b>TITLE</b><br>Senior Permit Analyst                         |
| <b>SIGNATURE</b><br>N/A  | <b>DATE</b><br>9/28/2012                                |   |

|  |   |   |   |  |   |
|--|---|---|---|--|---|
| <b>STATE OF UTAH</b><br>DEPARTMENT OF NATURAL RESOURCES<br>DIVISION OF OIL, GAS, AND MINING  |   | <b>FORM 9</b>   |   |  |   |
| <b>SUNDRY NOTICES AND REPORTS ON WELLS</b><br><br>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.   |   | <b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b><br>1420H626442   |   |  |   |
| <b>1. TYPE OF WELL</b><br>Oil Well   |   | <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  |   |  |   |
| <b>2. NAME OF OPERATOR:</b><br>BILL BARRETT CORP   |   | <b>7. UNIT or CA AGREEMENT NAME:</b>  |   |  |   |
| <b>3. ADDRESS OF OPERATOR:</b><br>1099 18th Street Ste 2300 , Denver, CO, 80202  |   | <b>8. WELL NAME and NUMBER:</b><br>5-27D-36   |   |  |   |
| <b>4. LOCATION OF WELL</b><br><b>FOOTAGES AT SURFACE:</b><br>1252 FNL 0660 FWL<br><b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b><br>Qtr/Qtr: SWNW Section: 27 Township: 03.0S Range: 06.0W Meridian: U  |   | <b>9. API NUMBER:</b><br>43013509170000   |   |  |   |
| <b>5. FIELD and POOL or WILDCAT:</b><br>CEDAR RIM  |   | <b>9. FIELD and POOL or WILDCAT:</b><br>CEDAR RIM   |   |  |   |
| <b>COUNTY:</b><br>DUCHESNE   |   | <b>STATE:</b><br>UTAH   |   |  |   |
| <b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>   |   |   |   |  |   |
| <b>TYPE OF SUBMISSION</b>  | <b>TYPE OF ACTION</b>   |   |   |  |   |
| <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b><br>Approximate date work will start:<br>4/24/2017<br><br><input type="checkbox"/> <b>SUBSEQUENT REPORT</b><br>Date of Work Completion:<br><br><input type="checkbox"/> <b>SPUD REPORT</b><br>Date of Spud:<br><br><input type="checkbox"/> <b>DRILLING REPORT</b><br>Report Date:  | <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE<br/> <input type="checkbox"/> CHANGE TO PREVIOUS PLANS<br/> <input type="checkbox"/> CHANGE WELL STATUS<br/> <input type="checkbox"/> DEEPEN<br/> <input type="checkbox"/> OPERATOR CHANGE<br/> <input type="checkbox"/> PRODUCTION START OR RESUME<br/> <input type="checkbox"/> REPERFORATE CURRENT FORMATION<br/> <input type="checkbox"/> TUBING REPAIR<br/> <input type="checkbox"/> WATER SHUTOFF<br/> <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING<br/> <input type="checkbox"/> CHANGE TUBING<br/> <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS<br/> <input type="checkbox"/> FRACTURE TREAT<br/> <input type="checkbox"/> PLUG AND ABANDON<br/> <input type="checkbox"/> RECLAMATION OF WELL SITE<br/> <input type="checkbox"/> SIDETRACK TO REPAIR WELL<br/> <input type="checkbox"/> VENT OR FLARE<br/> <input checked="" type="checkbox"/> SI TA STATUS EXTENSION<br/> <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR<br/> <input type="checkbox"/> CHANGE WELL NAME<br/> <input type="checkbox"/> CONVERT WELL TYPE<br/> <input type="checkbox"/> NEW CONSTRUCTION<br/> <input type="checkbox"/> PLUG BACK<br/> <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION<br/> <input type="checkbox"/> TEMPORARY ABANDON<br/> <input type="checkbox"/> WATER DISPOSAL<br/> <input type="checkbox"/> APD EXTENSION<br/>           OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table> |   | <input type="checkbox"/> ACIDIZE<br><input type="checkbox"/> CHANGE TO PREVIOUS PLANS<br><input type="checkbox"/> CHANGE WELL STATUS<br><input type="checkbox"/> DEEPEN<br><input type="checkbox"/> OPERATOR CHANGE<br><input type="checkbox"/> PRODUCTION START OR RESUME<br><input type="checkbox"/> REPERFORATE CURRENT FORMATION<br><input type="checkbox"/> TUBING REPAIR<br><input type="checkbox"/> WATER SHUTOFF<br><input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING<br><input type="checkbox"/> CHANGE TUBING<br><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS<br><input type="checkbox"/> FRACTURE TREAT<br><input type="checkbox"/> PLUG AND ABANDON<br><input type="checkbox"/> RECLAMATION OF WELL SITE<br><input type="checkbox"/> SIDETRACK TO REPAIR WELL<br><input type="checkbox"/> VENT OR FLARE<br><input checked="" type="checkbox"/> SI TA STATUS EXTENSION<br><input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR<br><input type="checkbox"/> CHANGE WELL NAME<br><input type="checkbox"/> CONVERT WELL TYPE<br><input type="checkbox"/> NEW CONSTRUCTION<br><input type="checkbox"/> PLUG BACK<br><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION<br><input type="checkbox"/> TEMPORARY ABANDON<br><input type="checkbox"/> WATER DISPOSAL<br><input type="checkbox"/> APD EXTENSION<br>OTHER: <input style="width: 100px;" type="text"/> |
| <input type="checkbox"/> ACIDIZE<br><input type="checkbox"/> CHANGE TO PREVIOUS PLANS<br><input type="checkbox"/> CHANGE WELL STATUS<br><input type="checkbox"/> DEEPEN<br><input type="checkbox"/> OPERATOR CHANGE<br><input type="checkbox"/> PRODUCTION START OR RESUME<br><input type="checkbox"/> REPERFORATE CURRENT FORMATION<br><input type="checkbox"/> TUBING REPAIR<br><input type="checkbox"/> WATER SHUTOFF<br><input type="checkbox"/> WILDCAT WELL DETERMINATION  | <input type="checkbox"/> ALTER CASING<br><input type="checkbox"/> CHANGE TUBING<br><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS<br><input type="checkbox"/> FRACTURE TREAT<br><input type="checkbox"/> PLUG AND ABANDON<br><input type="checkbox"/> RECLAMATION OF WELL SITE<br><input type="checkbox"/> SIDETRACK TO REPAIR WELL<br><input type="checkbox"/> VENT OR FLARE<br><input checked="" type="checkbox"/> SI TA STATUS EXTENSION<br><input type="checkbox"/> OTHER  | <input type="checkbox"/> CASING REPAIR<br><input type="checkbox"/> CHANGE WELL NAME<br><input type="checkbox"/> CONVERT WELL TYPE<br><input type="checkbox"/> NEW CONSTRUCTION<br><input type="checkbox"/> PLUG BACK<br><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION<br><input type="checkbox"/> TEMPORARY ABANDON<br><input type="checkbox"/> WATER DISPOSAL<br><input type="checkbox"/> APD EXTENSION<br>OTHER: <input style="width: 100px;" type="text"/> |   |  |   |
| <b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b><br><div style="display: flex; justify-content: space-between;"> <div style="width: 70%;"> <p>Well was shut in on 4/25/15 due to low production &amp; low commodity prices. On 4/24/16 the well will be shut in for 1 year. Current economics do not justify returning well to production. For this reason BBC is requesting an additional 1 year shut in, before a MIT is required, until 4/24/17. The well currently has 0 psi tubing, 1492 psi casing, 7 psi Braden Head. With minimal to zero Braden Head pressure and 1492 psi casing pressure, it is evident that the 5-1/2" production casing has full integrity &amp; all formations are protected. Fluid level was found at 7,300 ft. from surface with TOC at 1,520 ft. Well is shut in at the wellhead &amp; all surface equipment has been drained/winterized. Well is still on an active lease operator route &amp; is checked frequently for any surface &amp; potential downhole issues. Well would be RTP if economics are justified at higher commodity price before 4/24/17.</p> </div> <div style="width: 25%; text-align: right;"> <p><b>Accepted by the<br/>Utah Division of<br/>Oil, Gas and Mining</b></p> <p><b>Date:</b> May 04, 2016</p> <p><b>By:</b> </p> </div> </div> |   |   |   |  |   |

Effective Date: 11/1/2016

| <b>FORMER OPERATOR:</b>  | <b>NEW OPERATOR:</b>   |
|--|--|
| Bill Barrett Corporation<br>1099 18th Street, Suite 2300<br>Denver, CO 80202 | Rig II, LLC<br>1582 West 2600 South<br>Woods Cross, UT 84087 |
| CA Number(s):  | Unit(s):   |

**WELL INFORMATION:**

| Well Name         | Sec | TWN | RNG | API | Entity | Mineral | Surface | Type | Status |
|-------------------|-----|-----|-----|-----|--------|---------|---------|------|--------|
| See Attached List |     |     |     |     |        |         |         |      |        |

**OPERATOR CHANGES DOCUMENTATION:**

1. Sundry or legal documentation was received from the **FORMER** operator on: 10/21/2016
2. Sundry or legal documentation was received from the **NEW** operator on: 10/21/2016
3. New operator Division of Corporations Business Number: 8256968-0160

**REVIEW:**

1. Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: N/A
2. Receipt of Acceptance of Drilling Procedures for APD on: 10/21/2016
3. Reports current for Production/Disposition & Sundries: 11/2/2016
4. OPS/SI/TA well(s) reviewed for full cost bonding: 11/3/2016
5. UIC5 on all disposal/injection/storage well(s) approved on: 11/3/2016
6. Surface Facility(s) included in operator change: None
7. Inspections of PA state/fee well sites complete on (only upon operators request): 11/3/2016

**NEW OPERATOR BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: UTB000712
2. Indian well(s) covered by Bond Number: LPM 922467
3. State/fee well(s) covered by Bond Number(s): 9219529

**DATA ENTRY:**

1. Well(s) update in the **OGIS** on: 11/7/2016
2. Entity Number(s) updated in **OGIS** on: 11/7/2016
3. Unit(s) operator number update in **OGIS** on: N/A
4. Surface Facilities update in **OGIS** on: N/A
5. State/Fee well(s) attached to bond(s) in **RBDMS** on: 11/7/2016
6. Surface Facilities update in **RBDMS** on: N/A

**COMMENTS:**



From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

| Well Name           | Sec | TWN  | RNG  | API Number | Entity | Mineral | Surface | Type | Status |
|---------------------|-----|------|------|------------|--------|---------|---------|------|--------|
| SWD 9-36 BTR        | 9   | 030S | 060W | 4301350646 | 18077  | Indian  | Fee     | WD   | A      |
| 16-6D-46 BTR SWD    | 6   | 040S | 060W | 4301350781 | 18327  | Indian  | Fee     | WD   | A      |
| 6-32-36 BTR SWD     | 32  | 030S | 060W | 4301350921 | 18329  | Indian  | Fee     | WD   | A      |
| LC TRIBAL 8-26D-47  | 26  | 040S | 070W | 4301334024 |        | Indian  | Indian  | OW   | APD    |
| 16-21D-37 BTR       | 21  | 030S | 070W | 4301350758 |        | Indian  | Fee     | OW   | APD    |
| 14-11D-37 BTR       | 11  | 030S | 070W | 4301350862 |        | Indian  | Fee     | OW   | APD    |
| 7-17D-46 BTR        | 17  | 040S | 060W | 4301350883 |        | Indian  | Indian  | OW   | APD    |
| 14-12D-37 BTR       | 12  | 030S | 070W | 4301350894 |        | Indian  | Fee     | OW   | APD    |
| 1-18D-36 BTR        | 18  | 030S | 060W | 4301350922 |        | Indian  | Fee     | OW   | APD    |
| 13-2D-45 BTR        | 2   | 040S | 050W | 4301350931 |        | Indian  | Indian  | OW   | APD    |
| 5H-16-46 BTR        | 16  | 040S | 060W | 4301350992 |        | Indian  | Indian  | OW   | APD    |
| 9H-17-45 BTR        | 17  | 040S | 050W | 4301351098 |        | Indian  | Indian  | OW   | APD    |
| 13H-8-46 BTR UB     | 8   | 040S | 060W | 4301351124 |        | Indian  | Indian  | OW   | APD    |
| 8H-9-46 BTR         | 9   | 040S | 060W | 4301351140 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 7-31D-37  | 31  | 030S | 070W | 4301351147 |        | Indian  | Fee     | OW   | APD    |
| 14-16D-45 BTR       | 16  | 040S | 050W | 4301351178 |        | Indian  | Indian  | OW   | APD    |
| 16-19D-37 BTR       | 19  | 030S | 070W | 4301351179 |        | Indian  | Fee     | OW   | APD    |
| 6-2D-45 BTR         | 2   | 040S | 050W | 4301351234 |        | Indian  | Indian  | OW   | APD    |
| 2-2D-45 BTR         | 2   | 040S | 050W | 4301351235 |        | Indian  | Indian  | OW   | APD    |
| 10-26-35 BTR        | 26  | 030S | 050W | 4301351248 |        | Indian  | Fee     | OW   | APD    |
| LC TRIBAL 1H-33-46  | 33  | 040S | 060W | 4301351257 |        | Indian  | Fee     | OW   | APD    |
| LC TRIBAL 9-25D-46  | 25  | 040S | 060W | 4301351276 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 8H-30-45  | 30  | 040S | 050W | 4301351277 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 16H-30-45 | 30  | 040S | 050W | 4301351279 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 13-30D-45 | 30  | 040S | 050W | 4301351282 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 16H-36-46 | 36  | 040S | 060W | 4301351291 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 13H-30-46 | 30  | 040S | 060W | 4301351321 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 13H-31-46 | 31  | 040S | 060W | 4301351326 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 16-31D-46 | 31  | 040S | 060W | 4301351328 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 5H-26-47  | 26  | 040S | 070W | 4301351337 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 5H-19-45  | 20  | 040S | 050W | 4301351349 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 16-36D-47 | 36  | 040S | 070W | 4301351363 |        | Indian  | Indian  | OW   | APD    |
| 15-4D-47 BTR        | 4   | 040S | 070W | 4301351377 |        | Indian  | Fee     | OW   | APD    |
| 16-23D-46 LC TRIBAL | 23  | 040S | 060W | 4301351396 |        | Indian  | Fee     | OW   | APD    |
| 15-2D-36 BTR        | 2   | 030S | 060W | 4301351419 |        | Indian  | Fee     | OW   | APD    |
| 16-23D-37 BTR       | 23  | 030S | 070W | 4301351420 |        | Indian  | Fee     | OW   | APD    |
| 11-9D-47 BTR        | 9   | 040S | 070W | 4301351422 |        | Indian  | Fee     | OW   | APD    |
| 15-13D-47 BTR       | 13  | 040S | 070W | 4301351424 |        | Indian  | Indian  | OW   | APD    |
| LC TRIBAL 15-19D-46 | 19  | 040S | 060W | 4301351426 |        | Indian  | Indian  | OW   | APD    |
| 16-13D-45 BTR       | 13  | 040S | 050W | 4301351428 |        | Indian  | Indian  | OW   | APD    |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |  |        |        |    |     |
|---------------------|----|------|------|------------|--|--------|--------|----|-----|
| 14-12D-45 BTR       | 12 | 040S | 050W | 4301351444 |  | Indian | Indian | OW | APD |
| 16-14D-45 BTR       | 14 | 040S | 050W | 4301351445 |  | Indian | Indian | OW | APD |
| 5-13D-45 BTR        | 13 | 040S | 050W | 4301351446 |  | Indian | Indian | OW | APD |
| LC TRIBAL 16-26D-46 | 26 | 040S | 060W | 4301351450 |  | Indian | State  | OW | APD |
| LC TRIBAL 16-34D-46 | 34 | 040S | 060W | 4301351451 |  | Indian | State  | OW | APD |
| 16-12D-45 BTR       | 12 | 040S | 050W | 4301351452 |  | Indian | Indian | OW | APD |
| 8-12D-45 BTR        | 12 | 040S | 050W | 4301351453 |  | Indian | Indian | OW | APD |
| LC TRIBAL 1-35D-46  | 35 | 040S | 060W | 4301351454 |  | Indian | Fee    | OW | APD |
| 16-25D-37 BTR       | 25 | 030S | 070W | 4301351455 |  | Indian | Fee    | OW | APD |
| LC TRIBAL 13H-29-46 | 28 | 040S | 060W | 4301351462 |  | Indian | Fee    | OW | APD |
| LC TRIBAL 14-30D-37 | 30 | 030S | 070W | 4301351494 |  | Indian | Fee    | OW | APD |
| 7-13D-45 BTR        | 13 | 040S | 050W | 4301351497 |  | Indian | Indian | OW | APD |
| LC TRIBAL 4H-35-46  | 35 | 040S | 060W | 4301351515 |  | Indian | Fee    | OW | APD |
| LC TRIBAL 13H-19-46 | 19 | 040S | 060W | 4301351543 |  | Indian | Indian | OW | APD |
| 16-26D-37 BTR       | 26 | 030S | 070W | 4301351598 |  | Indian | Fee    | OW | APD |
| LC TRIBAL 16-31D-37 | 31 | 030S | 070W | 4301351610 |  | Indian | Fee    | OW | APD |
| 5-4-35 BTR          | 4  | 030S | 050W | 4301351613 |  | Indian | Fee    | OW | APD |
| LC TRIBAL 16-31D-47 | 31 | 040S | 070W | 4301351616 |  | Indian | Indian | OW | APD |
| LC TRIBAL 13H-31-47 | 31 | 040S | 070W | 4301351617 |  | Indian | Indian | OW | APD |
| LC TRIBAL 13-32D-47 | 32 | 040S | 070W | 4301351619 |  | Indian | Indian | OW | APD |
| LC TRIBAL 16H-32-47 | 32 | 040S | 070W | 4301351620 |  | Indian | Indian | OW | APD |
| LC TRIBAL 1-32D-47  | 32 | 040S | 070W | 4301351624 |  | Indian | Indian | OW | APD |
| LC TRIBAL 4H-32-47  | 32 | 040S | 070W | 4301351625 |  | Indian | Indian | OW | APD |
| LC TRIBAL 13-28D-47 | 28 | 040S | 070W | 4301351627 |  | Indian | Indian | OW | APD |
| LC TRIBAL 13H-29-47 | 28 | 040S | 070W | 4301351628 |  | Indian | Indian | OW | APD |
| LC TRIBAL 16H-28-47 | 28 | 040S | 070W | 4301351629 |  | Indian | Indian | OW | APD |
| LC TRIBAL 1-28D-47  | 28 | 040S | 070W | 4301351639 |  | Indian | Indian | OW | APD |
| LC TRIBAL 1H-27-47  | 28 | 040S | 070W | 4301351640 |  | Indian | Indian | OW | APD |
| LC TRIBAL 4H-28-47  | 28 | 040S | 070W | 4301351641 |  | Indian | Indian | OW | APD |
| LC TRIBAL 7-25D-58  | 25 | 050S | 080W | 4301351643 |  | Indian | Indian | OW | APD |
| LC TRIBAL 6-25D-58  | 25 | 050S | 080W | 4301351644 |  | Indian | Indian | OW | APD |
| LC TRIBAL 13H-24-58 | 24 | 050S | 080W | 4301351645 |  | Indian | Indian | OW | APD |
| LC TRIBAL 16-24D-58 | 24 | 050S | 080W | 4301351646 |  | Indian | Indian | OW | APD |
| LC Tribal 8-23D-46  | 23 | 040S | 060W | 4301351654 |  | Indian | Fee    | OW | APD |
| LC Tribal 16-35D-45 | 35 | 040S | 050W | 4301351656 |  | Indian | Fee    | OW | APD |
| LC Tribal 13H-35-45 | 35 | 040S | 050W | 4301351657 |  | Indian | Fee    | OW | APD |
| LC Tribal 16-36D-45 | 36 | 040S | 050W | 4301351658 |  | Indian | Fee    | OW | APD |
| LC Tribal 13H-36-45 | 36 | 040S | 050W | 4301351659 |  | Indian | Fee    | OW | APD |
| LC Tribal 5-36D-45  | 36 | 040S | 050W | 4301351661 |  | Indian | Fee    | OW | APD |
| LC Tribal 8-26D-46  | 26 | 040S | 060W | 4301351663 |  | Indian | Fee    | OW | APD |
| 3-29D-36 BTR        | 29 | 030S | 060W | 4301351665 |  | Indian | Fee    | OW | APD |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |        |        |    |     |
|---------------------|----|------|------|------------|--------|--------|----|-----|
| LC Tribal 5-35D-45  | 35 | 040S | 050W | 4301351666 | Indian | Fee    | OW | APD |
| LC Tribal 5-24D-46  | 24 | 040S | 060W | 4301351668 | Indian | Indian | OW | APD |
| LC TRIBAL 6-12D-58  | 12 | 050S | 080W | 4301351696 | Indian | Indian | OW | APD |
| LC TRIBAL 8-12D-58  | 12 | 050S | 080W | 4301351697 | Indian | Indian | OW | APD |
| LC TRIBAL 16H-22-47 | 21 | 040S | 070W | 4301351700 | Indian | Indian | OW | APD |
| 5-25D-37 BTR        | 25 | 030S | 070W | 4301351803 | Indian | Fee    | OW | APD |
| 8-3D-36 BTR         | 3  | 030S | 060W | 4301351804 | Indian | Fee    | OW | APD |
| 14-26D-37 BTR       | 26 | 030S | 070W | 4301351805 | Indian | Fee    | OW | APD |
| 9-4-35 BTR          | 4  | 030S | 050W | 4301351806 | Indian | Fee    | OW | APD |
| 11-4D-35 BTR        | 4  | 030S | 050W | 4301351807 | Indian | Fee    | OW | APD |
| 16-27D-37 BTR       | 27 | 030S | 070W | 4301351808 | Indian | Fee    | OW | APD |
| 14-27D-37 BTR       | 27 | 030S | 070W | 4301351809 | Indian | Fee    | OW | APD |
| 14-16D-46 BTR       | 16 | 040S | 060W | 4301351812 | Indian | Indian | OW | APD |
| LC Tribal 16-35D-48 | 35 | 040S | 080W | 4301351847 | Indian | Indian | OW | APD |
| LC Tribal 13H-35-48 | 35 | 040S | 080W | 4301351848 | Indian | Indian | OW | APD |
| LC Tribal 13-2D-58  | 11 | 050S | 080W | 4301351850 | Indian | Indian | OW | APD |
| 5-13D-36 BTR        | 13 | 030S | 060W | 4301351862 | Indian | Fee    | OW | APD |
| 5-8D-36 BTR         | 8  | 030S | 060W | 4301351871 | Indian | Fee    | OW | APD |
| 16-1D-36 BTR        | 1  | 030S | 060W | 4301351872 | Indian | Fee    | OW | APD |
| 8-18D-46 BTR        | 18 | 040S | 060W | 4301351897 | Indian | Fee    | OW | APD |
| LC Tribal 5-36D-46  | 36 | 040S | 060W | 4301351905 | Indian | Indian | OW | APD |
| LC Tribal 5-26D-45  | 26 | 040S | 050W | 4301351907 | Indian | Indian | OW | APD |
| 14-13D-45 BTR       | 13 | 040S | 050W | 4301351974 | Indian | Indian | OW | APD |
| 14-34D-46 DLB       | 34 | 040S | 060W | 4301351975 | Indian | Fee    | OW | APD |
| LC Tribal 5-21D-45  | 21 | 040S | 050W | 4301352001 | Indian | Indian | OW | APD |
| LC Tribal 8-22D-45  | 22 | 040S | 050W | 4301352002 | Indian | Indian | OW | APD |
| LC Tribal 8-25D-45  | 25 | 040S | 050W | 4301352007 | Indian | Indian | OW | APD |
| LC Tribal 16-25D-45 | 25 | 040S | 050W | 4301352008 | Indian | Indian | OW | APD |
| LC Tribal 16-22D-45 | 22 | 040S | 050W | 4301352009 | Indian | Indian | OW | APD |
| LC Tribal 16-26D-45 | 26 | 040S | 050W | 4301352010 | Indian | Indian | OW | APD |
| LC Tribal 14-31D-37 | 31 | 030S | 070W | 4301352016 | Indian | Fee    | OW | APD |
| 5-12D-45 BTR        | 12 | 040S | 050W | 4301352030 | Indian | Indian | OW | APD |
| LC Tribal 9-20D-45  | 20 | 040S | 050W | 4301352031 | Indian | Indian | OW | APD |
| LC Tribal 13-35D-47 | 35 | 040S | 070W | 4301352055 | Indian | Indian | OW | APD |
| LC Tribal 1-23D-47  | 23 | 040S | 070W | 4301352057 | Indian | Indian | OW | APD |
| 9-17D-46 BTR        | 17 | 040S | 060W | 4301352059 | Indian | Indian | OW | APD |
| 11-18D-46 BTR       | 18 | 040S | 060W | 4301352060 | Indian | Indian | OW | APD |
| 9-10D-47 BTR        | 10 | 040S | 070W | 4301352092 | Indian | Fee    | OW | APD |
| LC Tribal 1-17D-47  | 17 | 040S | 070W | 4301352096 | Indian | Fee    | OW | APD |
| 7-35D-37 BTR        | 35 | 030S | 070W | 4301352115 | Indian | Fee    | OW | APD |
| 14-25D-37 BTR       | 25 | 030S | 070W | 4301352116 | Indian | Fee    | OW | APD |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |        |        |    |     |
|---------------------|----|------|------|------------|--------|--------|----|-----|
| LC Tribal 5-25-46   | 25 | 040S | 060W | 4301352126 | Indian | Indian | OW | APD |
| 8-33D-35 BTR        | 33 | 030S | 050W | 4301352161 | Indian | Fee    | OW | APD |
| 5-4D-36 BTR         | 4  | 030S | 060W | 4301352175 | Indian | Fee    | OW | APD |
| 7-4D-36 BTR         | 4  | 030S | 060W | 4301352176 | Indian | Fee    | OW | APD |
| LC Tribal 4-36D-47  | 36 | 040S | 070W | 4301352186 | Indian | Indian | OW | APD |
| LC Tribal 4-22D-46  | 22 | 040S | 060W | 4301352944 | Indian | Indian | OW | APD |
| LC Tribal 16-22D-46 | 22 | 040S | 060W | 4301352945 | Indian | Indian | OW | APD |
| LC Tribal 11-19D-46 | 19 | 040S | 060W | 4301352946 | Indian | Indian | OW | APD |
| LC Tribal 7-20D-45  | 20 | 040S | 050W | 4301352947 | Indian | Indian | OW | APD |
| 15-11D-35 BTR       | 11 | 030S | 050W | 4301353056 | Indian | Fee    | OW | APD |
| 13-11D-35 BTR       | 11 | 030S | 050W | 4301353057 | Indian | Fee    | OW | APD |
| BTR 16-36D-37       | 36 | 030S | 070W | 4301353059 | Indian | Fee    | OW | APD |
| 4-29D-35 BTR        | 30 | 030S | 050W | 4301353060 | Indian | Fee    | OW | APD |
| 1-30D-35 BTR        | 30 | 030S | 050W | 4301353061 | Fee    | Fee    | OW | APD |
| LC TRIBAL 3-23D-46  | 23 | 040S | 060W | 4301353066 | Indian | State  | OW | APD |
| LC Tribal 14-23D-46 | 23 | 040S | 060W | 4301353067 | Indian | State  | OW | APD |
| LC Tribal 13-25D-46 | 25 | 040S | 060W | 4301353068 | Indian | Indian | OW | APD |
| LC Tribal 14-26D-46 | 26 | 040S | 060W | 4301353069 | Indian | State  | OW | APD |
| LC Tribal 5-26D-46  | 26 | 040S | 060W | 4301353070 | Indian | State  | OW | APD |
| LC Tribal 11-35D-45 | 35 | 040S | 050W | 4301353071 | Indian | State  | OW | APD |
| LC Tribal 7-35D-45  | 35 | 040S | 050W | 4301353072 | Indian | State  | OW | APD |
| LC Tribal 3-35D-45  | 35 | 040S | 050W | 4301353075 | Indian | State  | OW | APD |
| LC Tribal 14-36D-45 | 36 | 040S | 050W | 4301353076 | Indian | State  | OW | APD |
| LC Tribal 13-36D-45 | 36 | 040S | 050W | 4301353077 | Indian | State  | OW | APD |
| LC Tribal 10-36D-45 | 36 | 040S | 050W | 4301353078 | Indian | State  | OW | APD |
| LC Tribal 8-36D-45  | 36 | 040S | 050W | 4301353079 | Indian | State  | OW | APD |
| LC Tribal 6-36D-45  | 36 | 040S | 050W | 4301353080 | Indian | State  | OW | APD |
| LC Tribal 1-34D-46  | 34 | 040S | 060W | 4301353081 | Indian | State  | OW | APD |
| LC Tribal 9-27D-46  | 27 | 040S | 060W | 4301353082 | Indian | State  | OW | APD |
| LC Tribal 13-35D-45 | 35 | 040S | 050W | 4301353083 | Indian | State  | OW | APD |
| LC Tribal 8-35D-45  | 35 | 040S | 050W | 4301353084 | Indian | State  | OW | APD |
| LC Tribal 15-35D-45 | 35 | 040S | 050W | 4301353085 | Indian | State  | OW | APD |
| LC Tribal 12-25D-45 | 25 | 040S | 050W | 4301353122 | Indian | Indian | OW | APD |
| LC Tribal 14-25D-45 | 25 | 040S | 050W | 4301353123 | Indian | Indian | OW | APD |
| LC Tribal 10-25D-45 | 25 | 040S | 050W | 4301353124 | Indian | Indian | OW | APD |
| LC Tribal 11-26-45  | 26 | 040S | 050W | 4301353125 | Indian | Indian | OW | APD |
| LC Tribal 13-26D-45 | 26 | 040S | 050W | 4301353126 | Indian | Indian | OW | APD |
| LC Tribal 7-31D-46  | 31 | 040S | 060W | 4301353127 | Indian | Indian | OW | APD |
| LC Tribal 7-19D-45  | 19 | 040S | 050W | 4301353128 | Indian | Indian | OW | APD |
| LC Tribal 5-19D-45  | 19 | 040S | 050W | 4301353130 | Indian | Indian | OW | APD |
| LC Tribal 7-25D-46  | 25 | 040S | 060W | 4301353132 | Indian | Indian | OW | APD |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |       |        |        |    |     |
|---------------------|----|------|------|------------|-------|--------|--------|----|-----|
| LC Tribal 7-24D-46  | 24 | 040S | 060W | 4301353134 |       | Indian | Indian | OW | APD |
| LC Tribal 14-31D-46 | 31 | 040S | 060W | 4301353135 |       | Indian | Indian | OW | APD |
| LC Tribal 14-30D-46 | 30 | 040S | 060W | 4301353136 |       | Indian | Indian | OW | APD |
| 13-4-35 BTR SWD     | 4  | 030S | 050W | 4301353293 |       | Fee    | Fee    | OW | APD |
| LC FEE 14-26D-47    | 26 | 040S | 070W | 4301353294 |       | Fee    | Indian | OW | APD |
| LC Fee 5-25D-47     | 25 | 040S | 070W | 4301353295 |       | Fee    | Indian | OW | APD |
| 7-35-46 LC SWD      | 35 | 040S | 060W | 4301353296 |       | Fee    | Fee    | OW | APD |
| LC Fee 1H-33-47     | 32 | 040S | 070W | 4301353309 |       | Fee    | Indian | OW | APD |
| LC FEE 14-2D-58     | 2  | 050S | 080W | 4301353312 |       | Fee    | Indian | OW | APD |
| LC FEE 13H-21-47    | 21 | 040S | 070W | 4301353313 |       | Fee    | Indian | OW | APD |
| LC Fee 16-21D-47    | 21 | 040S | 070W | 4301353326 |       | Fee    | Indian | OW | APD |
| 16-7D-46 BTR        | 7  | 040S | 060W | 4301353328 |       | Fee    | Indian | OW | APD |
| LC Fee 15-26D-47    | 26 | 040S | 070W | 4301353331 |       | Fee    | Indian | OW | APD |
| LC Fee 4-24D-47     | 23 | 040S | 070W | 4301353332 |       | Fee    | Indian | OW | APD |
| LC Fee 5-34D-47     | 34 | 040S | 070W | 4301353333 |       | Fee    | Indian | OW | APD |
| LC Fee 5-35D-47     | 35 | 040S | 070W | 4301353334 |       | Fee    | Indian | OW | APD |
| 13-34D-47 LC Fee    | 34 | 040S | 070W | 4301353337 |       | Fee    | Indian | OW | APD |
| 14-35D-35 BTR       | 35 | 030S | 050W | 4301352120 |       | Fee    | Fee    | OW | DRL |
| 6-17D-46 BTR        | 17 | 040S | 060W | 4301351078 |       | Indian | Indian | OW | OPS |
| 5-34D-35 BTR        | 34 | 030S | 050W | 4301351187 |       | Indian | Fee    | OW | OPS |
| 5-10D-45 BTR        | 10 | 040S | 050W | 4301351221 |       | Indian | Indian | OW | OPS |
| 5-3D-45 BTR         | 3  | 040S | 050W | 4301351810 |       | Indian | Indian | OW | OPS |
| 9-34D-35 BTR        | 34 | 030S | 050W | 4301352117 |       | Fee    | Fee    | OW | OPS |
| 5-35D-35 BTR        | 35 | 030S | 050W | 4301352118 |       | Fee    | Fee    | OW | OPS |
| 1-2D-46 BTR         | 2  | 040S | 060W | 4301353086 |       | Indian | Fee    | OW | OPS |
| 7-21-46 DLB         | 21 | 040S | 060W | 4301333567 | 16526 | Indian | Indian | OW | P   |
| LC TRIBAL 1H-27-46  | 27 | 040S | 060W | 4301333568 | 18175 | Indian | Fee    | GW | P   |
| 7-29-46 DLB         | 29 | 040S | 060W | 4301333584 | 17603 | Indian | Fee    | GW | P   |
| LC TRIBAL 12H-28-46 | 28 | 040S | 060W | 4301333631 | 18132 | Indian | Indian | GW | P   |
| LC TRIBAL 13H-21-46 | 21 | 040S | 060W | 4301333632 | 18107 | Indian | Indian | GW | P   |
| 12-36-36 BTR        | 36 | 030S | 060W | 4301333638 | 16336 | Indian | Fee    | GW | P   |
| 5-5-46 BTR          | 5  | 040S | 060W | 4301333639 | 16542 | Indian | Fee    | OW | P   |
| 5-23-36 BTR         | 23 | 030S | 060W | 4301333642 | 16675 | Indian | Fee    | GW | P   |
| 14-29-36 BTR        | 29 | 030S | 060W | 4301333643 | 16725 | Indian | Fee    | OW | P   |
| 14-30-36 BTR        | 30 | 030S | 060W | 4301333644 | 16701 | Indian | Fee    | GW | P   |
| 7-20-46 DLB         | 20 | 040S | 060W | 4301333657 | 16584 | Indian | Indian | OW | P   |
| LC TRIBAL 5-21D-46  | 21 | 040S | 060W | 4301333658 | 18887 | Indian | Indian | OW | P   |
| 5-20-46 DLB         | 20 | 040S | 060W | 4301333659 | 18750 | Indian | Indian | GW | P   |
| LC TRIBAL 13H-20-46 | 20 | 040S | 060W | 4301333678 | 17979 | Indian | Indian | GW | P   |
| 14-7-46 BTR         | 7  | 040S | 060W | 4301333806 | 16890 | Indian | Indian | GW | P   |
| 7-8-45 BTR          | 8  | 040S | 050W | 4301333820 | 16974 | Indian | Indian | OW | P   |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |       |        |        |    |   |
|---------------------|----|------|------|------------|-------|--------|--------|----|---|
| 1-5-45 BTR          | 5  | 040S | 050W | 4301333868 | 16931 | Indian | Indian | OW | P |
| 5-16-36 BTR         | 16 | 030S | 060W | 4301333970 | 17195 | Indian | Fee    | OW | P |
| 5-29-36 BTR         | 29 | 030S | 060W | 4301333972 | 17557 | Indian | Fee    | OW | P |
| 4-30-36 BTR         | 30 | 030S | 060W | 4301333973 | 17249 | Indian | Fee    | OW | P |
| 7-19-46 DLB         | 19 | 040S | 060W | 4301334004 | 19018 | Indian | Indian | OW | P |
| 5-25-36 BTR         | 25 | 030S | 060W | 4301334021 | 17126 | Fee    | Fee    | OW | P |
| 5-4-45 BTR          | 4  | 040S | 050W | 4301334089 | 17507 | Indian | Indian | OW | P |
| 13-2-46 BTR         | 2  | 040S | 060W | 4301334090 | 18618 | Indian | Indian | OW | P |
| 2-3-45 BTR          | 3  | 040S | 050W | 4301334099 | 17932 | Indian | Indian | OW | P |
| 7-6-45 BTR          | 6  | 040S | 050W | 4301334100 | 17653 | Indian | Indian | OW | P |
| 1-9-45 BTR          | 9  | 040S | 050W | 4301334101 | 17910 | Indian | Indian | OW | P |
| 8-10-45 BTR         | 10 | 040S | 050W | 4301334102 | 17530 | Indian | Indian | OW | P |
| 7-17-45 BTR         | 17 | 040S | 050W | 4301334104 | 17933 | Indian | Indian | OW | P |
| 16-7-45 BTR         | 7  | 040S | 050W | 4301334111 | 17665 | Indian | Indian | OW | P |
| 15-18-45 BTR        | 18 | 040S | 050W | 4301334112 | 17832 | Indian | Indian | OW | P |
| 6-12-46 BTR         | 12 | 040S | 060W | 4301334114 | 17964 | Indian | Indian | OW | P |
| 5-13-46 BTR         | 13 | 040S | 060W | 4301334115 | 17833 | Indian | Indian | OW | P |
| 16-26-36 BTR        | 26 | 030S | 060W | 4301334132 | 18028 | Indian | Fee    | OW | P |
| 1-23-36 BTR         | 23 | 030S | 060W | 4301334136 | 17722 | Indian | Fee    | OW | P |
| 15-10-36 BTR        | 10 | 030S | 060W | 4301334277 | 17419 | Indian | Fee    | OW | P |
| 14-5-46 BTR         | 5  | 040S | 060W | 4301350307 | 17624 | Fee    | Fee    | OW | P |
| 14X-22-46 DLB       | 22 | 040S | 060W | 4301350351 | 17604 | Indian | Indian | OW | P |
| 16-13-36 BTR        | 13 | 030S | 060W | 4301350372 | 17853 | Indian | Fee    | OW | P |
| 5-33-46 DLB         | 33 | 040S | 060W | 4301350397 | 17765 | Indian | Fee    | OW | P |
| 5-34-46 DLB         | 34 | 040S | 060W | 4301350415 | 17801 | Indian | State  | GW | P |
| LC FEE 12H-32-46    | 32 | 040S | 060W | 4301350431 | 18003 | Fee    | Fee    | OW | P |
| 1-13D-47 BTR        | 13 | 040S | 070W | 4301350445 | 18205 | Indian | Fee    | OW | P |
| 16-8D-45 BTR        | 8  | 040S | 050W | 4301350466 | 18799 | Indian | Indian | OW | P |
| 7-13D-46 BTR        | 13 | 040S | 060W | 4301350470 | 18076 | Indian | Indian | OW | P |
| 14-8D-45 BTR        | 8  | 040S | 050W | 4301350567 | 18207 | Indian | Indian | OW | P |
| 14-5D-45 BTR        | 5  | 040S | 050W | 4301350568 | 18108 | Indian | Indian | OW | P |
| 16-31D-36 BTR       | 31 | 030S | 060W | 4301350573 | 18004 | Indian | Fee    | OW | P |
| 5-7D-46 BTR         | 7  | 040S | 060W | 4301350574 | 18176 | Indian | Indian | OW | P |
| LC TRIBAL 13H-33-46 | 34 | 040S | 060W | 4301350575 | 18223 | Indian | State  | OW | P |
| 5-8-45 BTR          | 8  | 040S | 050W | 4301350607 | 18279 | Indian | Indian | OW | P |
| 16-6D-45 BTR        | 6  | 040S | 050W | 4301350610 | 18177 | Indian | Indian | OW | P |
| 5-18D-45 BTR        | 18 | 040S | 050W | 4301350611 | 18300 | Indian | Indian | OW | P |
| 7-26-37 BTR         | 26 | 030S | 070W | 4301350641 | 18131 | Indian | Fee    | OW | P |
| 3-11D-36 BTR        | 11 | 030S | 060W | 4301350642 | 18299 | Indian | Fee    | OW | P |
| 16-1D-46 BTR        | 1  | 040S | 060W | 4301350675 | 18525 | Indian | Indian | OW | P |
| 14-3-45 BTR         | 3  | 040S | 050W | 4301350676 | 18363 | Indian | Indian | OW | P |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |       |        |        |    |   |
|---------------------|----|------|------|------------|-------|--------|--------|----|---|
| 4-17D-45 BTR        | 17 | 040S | 050W | 4301350687 | 18517 | Indian | Indian | OW | P |
| 5-6D-45 BTR         | 6  | 040S | 050W | 4301350688 | 18726 | Indian | Indian | OW | P |
| 7-7D-45 BTR         | 7  | 040S | 050W | 4301350689 | 18380 | Indian | Indian | OW | P |
| 14-10D-45 BTR       | 10 | 040S | 050W | 4301350754 | 18447 | Indian | Indian | OW | P |
| 14-9D-45 BTR        | 9  | 040S | 050W | 4301350755 | 18379 | Indian | Indian | OW | P |
| 13-16D-36 BTR       | 16 | 030S | 060W | 4301350757 | 18206 | Indian | State  | OW | P |
| 5-9D-36 BTR         | 9  | 030S | 060W | 4301350843 | 18381 | Indian | Fee    | OW | P |
| 16-5D-46 BTR        | 5  | 040S | 060W | 4301350844 | 18280 | Fee    | Fee    | OW | P |
| 5-27D-37 BTR        | 27 | 030S | 070W | 4301350847 | 18526 | Indian | Fee    | OW | P |
| 7-4D-45 BTR         | 4  | 040S | 050W | 4301350884 | 18562 | Indian | Indian | OW | P |
| 2-16D-45 BTR        | 16 | 040S | 050W | 4301350899 | 18619 | Indian | Indian | OW | P |
| 16-10D-45 BTR       | 10 | 040S | 050W | 4301350902 | 18725 | Indian | Indian | OW | P |
| 5-2D-36 BTR         | 2  | 030S | 060W | 4301350913 | 18886 | Indian | Fee    | OW | P |
| 13H-27-36 BTR       | 27 | 030S | 060W | 4301350918 | 18445 | Indian | State  | OW | P |
| 8-16D-46 BTR        | 16 | 040S | 060W | 4301350953 | 19027 | Indian | Indian | OW | P |
| 16-16D-46 BTR       | 16 | 040S | 060W | 4301350956 | 19028 | Indian | Indian | OW | P |
| 16-9D-45 BTR        | 9  | 040S | 050W | 4301350962 | 18662 | Indian | Indian | OW | P |
| 14-31D-36 BTR       | 31 | 030S | 060W | 4301350973 | 18524 | Indian | Fee    | OW | P |
| 5-10D-36 BTR        | 10 | 030S | 060W | 4301350978 | 18989 | Indian | Fee    | OW | P |
| 1-32D-36 BTR        | 32 | 030S | 060W | 4301350979 | 18648 | Indian | Fee    | OW | P |
| 16-12D-36 BTR       | 12 | 030S | 060W | 4301350980 | 18748 | Indian | Fee    | OW | P |
| 2-18D-45 BTR        | 18 | 040S | 050W | 4301350991 | 18776 | Indian | Indian | OW | P |
| 3-1-46 BTR          | 1  | 040S | 060W | 4301351017 | 18777 | Indian | Fee    | OW | P |
| 10-5-45 BTR         | 5  | 040S | 050W | 4301351062 | 18724 | Indian | Indian | OW | P |
| 12-4D-45 BTR        | 4  | 040S | 050W | 4301351063 | 18813 | Indian | Indian | OW | P |
| 1-10D-45 BTR        | 10 | 040S | 050W | 4301351064 | 18966 | Indian | Indian | OW | P |
| 16-2D-46 BTR        | 2  | 040S | 060W | 4301351079 | 18830 | Indian | Indian | OW | P |
| 9H-4-45 BTR         | 4  | 040S | 050W | 4301351092 | 18814 | Indian | Indian | OW | P |
| 12-17-45 BTR        | 17 | 040S | 050W | 4301351097 | 18984 | Indian | Indian | OW | P |
| 5-9D-46 BTR         | 9  | 040S | 060W | 4301351109 | 19313 | Indian | Fee    | OW | P |
| 14-9D-36 BTR        | 9  | 030S | 060W | 4301351144 | 19004 | Indian | Fee    | OW | P |
| 5-31D-36 BTR        | 31 | 030S | 060W | 4301351146 | 18691 | Indian | Fee    | OW | P |
| 4-9D-45 BTR         | 9  | 040S | 050W | 4301351157 | 18883 | Indian | Indian | OW | P |
| 8-12D-46 BTR        | 12 | 040S | 060W | 4301351159 | 18911 | Indian | Indian | OW | P |
| LC TRIBAL 16-23D-47 | 23 | 040S | 070W | 4301351180 | 18617 | Indian | Indian | OW | P |
| 14-7D-45 BTR        | 7  | 040S | 050W | 4301351222 | 18949 | Indian | Indian | OW | P |
| 5-16D-45 BTR        | 16 | 040S | 050W | 4301351223 | 18987 | Indian | Indian | OW | P |
| 4-5D-45 BTR         | 5  | 040S | 050W | 4301351242 | 18882 | Indian | Indian | OW | P |
| LC TRIBAL 16H-19-45 | 19 | 040S | 050W | 4301351278 | 18627 | Indian | Indian | OW | P |
| LC TRIBAL 13-19D-45 | 19 | 040S | 050W | 4301351280 | 18628 | Indian | Indian | OW | P |
| LC TRIBAL 5-30D-45  | 30 | 040S | 050W | 4301351281 | 19448 | Indian | Indian | OW | P |



From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                     |    |      |      |            |       |        |        |    |    |
|---------------------|----|------|------|------------|-------|--------|--------|----|----|
| LC TRIBAL 15-24D-46 | 24 | 040S | 060W | 4301351283 | 18626 | Indian | Indian | OW | P  |
| LC TRIBAL 13H-24-46 | 19 | 040S | 050W | 4301351289 | 18629 | Indian | Indian | OW | P  |
| 7-16-47 BTR         | 16 | 040S | 070W | 4301351296 | 18950 | Indian | Fee    | OW | P  |
| 14-18D-45 BTR       | 18 | 040S | 050W | 4301351313 | 19005 | Indian | Indian | OW | P  |
| LC TRIBAL 16-30D-46 | 30 | 040S | 060W | 4301351320 | 19006 | Indian | Indian | OW | P  |
| LC TRIBAL 5-20D-45  | 20 | 040S | 050W | 4301351331 | 19449 | Indian | Indian | OW | P  |
| 11-8D-46 BTR        | 8  | 040S | 060W | 4301351336 | 19314 | Indian | Indian | OW | P  |
| 5-7D-45 BTR         | 7  | 040S | 050W | 4301351350 | 18951 | Indian | Indian | OW | P  |
| 7-5-35 BTR          | 5  | 030S | 050W | 4301351599 | 19078 | Indian | Fee    | OW | P  |
| 13-5D-35 BTR        | 5  | 030S | 050W | 4301351600 | 18996 | Indian | Fee    | OW | P  |
| 11-5D-35 BTR        | 5  | 030S | 050W | 4301351601 | 19061 | Fee    | Fee    | OW | P  |
| 15-5D-35 BTR        | 5  | 030S | 050W | 4301351602 | 19062 | Fee    | Fee    | OW | P  |
| 9-5D-35 BTR         | 5  | 030S | 050W | 4301351609 | 19029 | Indian | Fee    | OW | P  |
| 3-5D-35 BTR         | 5  | 030S | 050W | 4301351638 | 19079 | Indian | Fee    | OW | P  |
| 7-8-46 BTR          | 8  | 040S | 060W | 4301351702 | 19315 | Indian | Indian | OW | P  |
| 7-30-46 DLB         | 30 | 040S | 060W | 4301351703 | 18997 | Fee    | Indian | OW | P  |
| 3-13D-46 BTR        | 13 | 040S | 060W | 4301351718 | 18881 | Indian | Indian | OW | P  |
| 2-13D-46 BTR        | 13 | 040S | 060W | 4301351719 | 18885 | Indian | Indian | OW | P  |
| 12-12D-46 BTR       | 12 | 040S | 060W | 4301351720 | 18867 | Indian | Indian | OW | P  |
| 10-12D-46 BTR       | 12 | 040S | 060W | 4301351721 | 18856 | Indian | Indian | OW | P  |
| 11-11D-47 BTR       | 11 | 040S | 070W | 4301352091 | 19633 | Fee    | Fee    | OW | P  |
| 7-12D-47 BTR        | 12 | 040S | 070W | 4301352094 | 19600 | Indian | Fee    | OW | P  |
| 5-12D-47 BTR        | 12 | 040S | 070W | 4301352095 | 19634 | Indian | Fee    | OW | P  |
| 14-33D-35 BTR       | 33 | 030S | 050W | 4301352162 | 19450 | Indian | Fee    | OW | P  |
| 16-33D-35 BTR       | 33 | 030S | 050W | 4301352163 | 19451 | Indian | Fee    | OW | P  |
| 14-22-46 DLB        | 22 | 040S | 060W | 4301333660 | 17604 | Indian | Indian | D  | PA |
| 13H-31-36 BTR       | 31 | 030S | 060W | 4301350465 | 18485 | Indian | Fee    | OW | PA |
| 16X-23D-36 BTR      | 23 | 030S | 060W | 4301350623 | 18007 | Indian | State  | OW | PA |
| 8-6-45 BTR          | 6  | 040S | 050W | 4301350900 | 18561 | Indian | Indian | OW | PA |
| 13-13-36 BTR        | 13 | 030S | 060W | 4301350919 | 18364 | Indian | Fee    | OW | PA |
| 7-28-46 DLB         | 28 | 040S | 060W | 4301333569 | 16460 | Indian | Indian | OW | S  |
| 5-21-36 BTR         | 21 | 030S | 060W | 4301333641 | 16674 | Indian | Fee    | GW | S  |
| 13-26-36 BTR        | 26 | 030S | 060W | 4301333980 | 17569 | Indian | Fee    | OW | S  |
| 14-1-46 BTR         | 1  | 040S | 060W | 4301334113 | 18516 | Indian | Indian | OW | S  |
| 16-21-36 BTR        | 21 | 030S | 060W | 4301334130 | 17721 | Indian | Fee    | OW | S  |
| 14-21-36 BTR        | 21 | 030S | 060W | 4301334131 | 18006 | Indian | Fee    | OW | S  |
| 7-16-36 BTR         | 16 | 030S | 060W | 4301334133 | 17834 | Indian | Fee    | OW | S  |
| 1-30-36 BTR         | 30 | 030S | 060W | 4301334134 | 17905 | Indian | Fee    | OW | S  |
| 16-30-36 BTR        | 30 | 030S | 060W | 4301334135 | 18005 | Indian | Fee    | OW | S  |
| 3-23-36 BTR         | 23 | 030S | 060W | 4301334137 | 17860 | Indian | Fee    | OW | S  |
| 16-16-36 BTR        | 16 | 030S | 060W | 4301334138 | 17666 | Indian | Fee    | OW | S  |

From: Bill Barrett Corporation

To: Rig II, LLC

Effective 11/1/2016

|                           |    |      |      |            |       |        |        |    |    |
|---------------------------|----|------|------|------------|-------|--------|--------|----|----|
| 4-26-36 BTR               | 26 | 030S | 060W | 4301334139 | 17620 | Fee    | Fee    | OW | S  |
| 9-11-36 BTR               | 11 | 030S | 060W | 4301334276 | 17451 | Indian | Fee    | OW | S  |
| 3-36-36 BTR               | 36 | 030S | 060W | 4301350398 | 17955 | Indian | Fee    | OW | S  |
| 7-10-36 BTR               | 10 | 030S | 060W | 4301350437 | 18052 | Indian | Fee    | OW | S  |
| 16-12D-46 BTR             | 12 | 040S | 060W | 4301350467 | 18051 | Indian | Indian | OW | S  |
| 13H-13-46 BTR             | 13 | 040S | 060W | 4301350468 | 18208 | Indian | Indian | OW | S  |
| 13-12-46 BTR              | 12 | 040S | 060W | 4301350469 | 18233 | Indian | Indian | OW | S  |
| 14-8D-36 BTR              | 8  | 030S | 060W | 4301350612 | 18163 | Indian | Fee    | OW | S  |
| 14-7D-36 BTR              | 7  | 030S | 060W | 4301350613 | 18330 | Indian | Fee    | OW | S  |
| 16-9-36 BTR               | 9  | 030S | 060W | 4301350645 | 18078 | Indian | Fee    | OW | S  |
| 7-27-37 BTR               | 27 | 030S | 070W | 4301350647 | 18090 | Indian | Fee    | OW | S  |
| 16-12D-37 BTR             | 12 | 030S | 070W | 4301350785 | 18446 | Indian | Fee    | OW | S  |
| 14-21D-37 BTR             | 21 | 030S | 070W | 4301350859 | 18548 | Indian | Fee    | OW | S  |
| 10-18D-36 BTR             | 18 | 030S | 060W | 4301350915 | 18884 | Indian | Fee    | OW | S  |
| 5-27D-36                  | 27 | 030S | 060W | 4301350917 | 18482 | Indian | State  | OW | S  |
| 10-36D-36 BTR             | 36 | 030S | 060W | 4301351005 | 18523 | Indian | Fee    | OW | S  |
| 14-6D-45 BTR              | 6  | 040S | 050W | 4301351158 | 18967 | Indian | Indian | OW | S  |
| 5H-1-46 BTR UTELAND BUTTE | 6  | 040S | 050W | 4301351215 | 18728 | Indian | Indian | OW | S  |
| 5H-1-46 BTR WASATCH       | 6  | 040S | 050W | 4301351216 | 18727 | Indian | Indian | OW | S  |
| 1-25D-36 BTR              | 25 | 030S | 060W | 4301351294 | 18798 | Indian | Fee    | OW | S  |
| 5-5D-35 BTR               | 5  | 030S | 050W | 4301351605 | 19055 | Indian | Fee    | OW | S  |
| 16-23-36 BTR              | 23 | 030S | 060W | 4301333971 | 17182 | Indian | Fee    | OW | TA |
| LC TRIBAL 14-23D-47       | 23 | 040S | 070W | 4301334022 | 18616 | Indian | Indian | OW | TA |
| 5-32D-36 BTR              | 32 | 030S | 060W | 4301350756 | 18328 | Indian | Fee    | OW | TA |



October 20, 2016

Re: Bill Barrett Corporation Transfer to New Operator

Dear Ms. Medina:

Attached please find the change of operation Form 9, Form 5's and Request to Transfer APD form changing the operator from Bill Barrett Corporation to RIG II, LLC, effective 11/1/2016. Badlands Energy – Utah, LLC will be a sub-operator.

**New Operator Contact information:**

RIG II, LLC  
1582 West 2600 South  
Woods Cross, Utah 84087-0298  
Telephone: (801) 683-4245  
Fax: (801) 298-9889

Upon reviewing the attached, please contact myself with any questions at 303-312-8115.

Sincerely,

Bill Barrett Corporation

Brady Riley  
Permit Analyst

**RECEIVED**  
OCT 21 2016  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:  
(see attached well list)

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
N/A

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:  
(see attached well list)

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

RIG II, LLC

N4055

3. ADDRESS OF OPERATOR:

1582 West 2600 South

CITY Wood Cross

STATE UT

ZIP 84087

PHONE NUMBER:

(801) 683-4245

4. LOCATION OF WELL

FOOTAGES AT SURFACE: (see attached well list)

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ NOTICE OF INTENT  
(Submit in Duplicate)

Approximate date work will start:

11/1/2016

☐ SUBSEQUENT REPORT  
(Submit Original Form Only)

Date of work completion:

TYPE OF ACTION

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☒ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

RIG II, LLC IS SUBMITTING THIS SUNDRY AS NOTIFICATION THAT THE WELLS LISTED ON THE ATTACHED LIST HAVE BEEN SOLD TO RIG II, LLC BY BILL BARRETT CORPORATION EFFECTIVE 11/1/2016. PLEASE REFER ALL FUTURE CORRESPONDENCE TO THE ADDRESS BELOW.

RIG II, LLC

1582 West 2600 South

Woods Cross, Utah 84087-0298

801-683-4245

(STATE/FEE BOND # 9219529/ BLM BOND # UTB000712/ BIA BOND # LPM9224670)

BILL BARRETT CORPORATION N4165

Duane Zavala

NAME (PLEASE PRINT)

Duane Zavala

SIGNATURE

Senior Vice President -

EH&S, Government and Regulatory Affairs

RIG II, LLC

Jesse McSwain

NAME (PLEASE PRINT)

Jesse McSwain

SIGNATURE

Manager

NAME (PLEASE PRINT) Jesse McSwain

TITLE Manager

SIGNATURE

Jesse McSwain

DATE

10/20/16

(This space for State use only)

APPROVED

NOV 07 2016

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**Request to Transfer Application or Permit to Drill**


(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

|   |   |
|---|---|
| <b>Well name:</b>                               | (See attached list)   |
| <b>API number:</b>                              |   |
| <b>Location:</b>                                | Qtr-Qtr:                      Section:                      Township:                      Range: |
| <b>Company that filed original application:</b> | Bill Barrett Corporation  |
| <b>Date original permit was issued:</b>         |   |
| <b>Company that permit was issued to:</b>       | Bill Barrett Corporation  |

| Check one                           | Desired Action:   |
|-------------------------------------|---|
|                                     | <b>Transfer pending (unapproved) Application for Permit to Drill to new operator</b>  |
|                                     | The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application. |
| <input checked="" type="checkbox"/> | <b>Transfer approved Application for Permit to Drill to new operator</b>  |
|                                     | The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.   |

| Following is a checklist of some items related to the application, which should be verified.  | Yes                                 | No                                  |
|---|-------------------------------------|-------------------------------------|
| If located on private land, has the ownership changed?  | <input checked="" type="checkbox"/> | <input type="checkbox"/>            |
| <input type="checkbox"/> If so, has the surface agreement been updated?   | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?                           | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?                                      | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?                                      | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Has the approved source of water for drilling changed?  | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? | <input type="checkbox"/>            | <input checked="" type="checkbox"/> |
| Is bonding still in place, which covers this proposed well? Bond No. <small>9219529-LUDGM / UTB000712-BLM / LPM9224670-BIA</small>                                  | <input checked="" type="checkbox"/> | <input type="checkbox"/>            |

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) Jesse McSwain Title Manager  
Signature  Date 10/20/16  
Representing (company name) RIG II, LLC

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING


UIC FORM 5

**TRANSFER OF AUTHORITY TO INJECT**


|  |   |
|--|---|
| Well Name and Number<br><b>6-32-36 BTR SWD</b>   | API Number<br><b>4301350921</b>   |
| Location of Well<br><br>Footage : <b>1628 FNL 1553 FWL</b> County : <b>DUCHENSE</b><br><br>QQ, Section, Township, Range: <b>SENW    32    3S    6W</b> State : <b>UTAH</b> | Field or Unit Name<br><b>CEDAR RIM</b><br><br>Lease Designation and Number<br><b>2OG0005608</b> |

**EFFECTIVE DATE OF TRANSFER:** 11/1/2016


**CURRENT OPERATOR**

|   |   |
|---|---|
| Company: <u>BILL BARRETT CORPORATION</u>            | Name: <u>Duane Zavadii</u>  |
| Address: <u>1099 18th Street Ste 2300</u>           | Signature: <u></u> |
| city <u>DENVER</u> state <u>CO</u> zip <u>80202</u> | Title: <u>Senior Vice President -</u>   |
| Phone: <u>(303) 293-9100</u>                        | Title: <u>EH&amp;S, Government and Regulatory Affairs</u>   |
| Comments:   | Date: <u>10/20/16</u>   |

**NEW OPERATOR**

|   |   |
|---|---|
| Company: <u>RIG II, LLC</u>                             | Name: <u>Jesse McSwain</u>  |
| Address: <u>1582 West 2600 South</u>                    | Signature: <u></u> |
| city <u>Wood Cross</u> state <u>UT</u> zip <u>84087</u> | Title: <u>Manager</u>   |
| Phone: <u>(801) 683-4245</u>                            | Date: <u>10/20/16</u>   |
| Comments:   |   |

(This space for State use only)

Transfer approved by:   
Title: UIC Geologist

Approval Date: 11/3/16

Comments:

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 5


TRANSFER OF AUTHORITY TO INJECT

|  |  |
|--|--|
| Well Name and Number<br>16-6D-46 BTR SWD   | API Number<br>4301350781   |
| Location of Well<br>Footage : 0200 FSL 0099 FEL<br>County : DUCHESNE<br>QQ, Section, Township, Range: SESE 6 4S 6W<br>State : UTAH | Field or Unit Name<br>ALTAMONT<br>Lease Designation and Number<br>2OG0005608 |

EFFECTIVE DATE OF TRANSFER: 11/1/2016


CURRENT OPERATOR

Company: BILL BARRETT CORPORATION  
Address: 1099 18th Street Ste 2300  
city DENVER state CO zip 80202  
Phone: (303) 293-9100  
Comments:


Name: Duane Zavadii  
Signature:   
Senior Vice President -  
Title: EH&S, Government and Regulatory Affairs  
Date: 10/20/16

NEW OPERATOR

Company: RIG II, LLC  
Address: 1582 West 2600 South  
city Wood Cross state UT zip 84087  
Phone: (801) 683-4245  
Comments:

Name: Jesse McSwain  
Signature:   
Title: Manager  
Date: 10/20/16

(This space for State use only)

Transfer approved by:   
Title: VIC

Approval Date: 11/3/16

Comments:



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING


UIC FORM 5

**TRANSFER OF AUTHORITY TO INJECT**


|  |   |
|--|---|
| Well Name and Number<br><b>SWD 9-36 BTR</b>  | API Number<br><b>4301350646</b>   |
| Location of Well<br><br>Footage : <b>0539 FSL 0704 FEL</b><br><br>County : <b>DUCHESNE</b><br><br>QQ, Section, Township, Range: <b>SESE 9 3S 6W</b><br><br>State : <b>UTAH</b> | Field or Unit Name<br><b>CEDAR RIM</b><br><br>Lease Designation and Number<br><b>2OG0005608</b> |

**EFFECTIVE DATE OF TRANSFER:** 11/1/2016

**CURRENT OPERATOR**

|   |   |
|---|---|
| Company: <u>BILL BARRETT CORPORATION</u>            | Name: <u>Duane Zavadi</u>   |
| Address: <u>1099 18th Street Ste 2300</u>           | Signature: <u></u> |
| city <u>DENVER</u> state <u>CO</u> zip <u>80202</u> | Title: <u>Senior Vice President -<br/>EH&amp;S, Government and Regulatory Affairs</u>                 |
| Phone: <u>(303) 293-9100</u>                        | Date: <u>10/20/16</u>   |
| Comments:   |   |

**NEW OPERATOR**

|   |  |
|---|--|
| Company: <u>RIG II, LLC</u>                             | Name: <u>Jesse McSwain</u>   |
| Address: <u>1582 West 2600 South</u>                    | Signature: <u></u> |
| city <u>Wood Cross</u> state <u>UT</u> zip <u>84087</u> | Title: <u>Manager</u>  |
| Phone: <u>(801) 683-4245</u>                            | Date: <u>10/20/16</u>  |
| Comments:   |  |

(This space for State use only)

Transfer approved by: \_\_\_\_\_ Approval Date: \_\_\_\_\_

Title: \_\_\_\_\_

Comments:

*This well was approved by USEPA.  
EPA approval will be required.*